Final Concept Design Report

Inland Link Road connecting Agnes Water and Baffle Creek

R2018071

Prepared for Gladstone Regional Council

19 March 2019







Contact Information

Document Information

Cardno (Qld) Pty Ltd Prepared for Gladstone Regional Council

ABN 57 051 074 992 Project Name Inland Link Road connecting

Agnes Water and Baffle Creek

Level 1, 101 Goondoon Street

Gladstone QLD 4860 File Reference R2018071.Concept Design

Report.010 - Final.docx

www.cardno.com Job Reference R2018071

Phone +61 7 4972 7890

Date 19 March 2019

ax +61 7 4972 1859 Version Number 003

Author(s):

Australia

Fax

Name Stephen Whitaker

Job title Senior Planner / Technical Lead

(Planning) - Regional

Spitalon

Queensland

Name Gerry Moore Effective Date 19/03/2019

Job title Senior Civil Designer

Approved By:

Name Megan Kraft Date Approved 19/03/2019

Job title Senior Engineer

Document History

Version	Effective Date	Description of Revision	Prepared by	Reviewed by
001	5 March 2019	Draft	Stephen Whitaker / Gerry Moore	Cameron Franklin
002	11 March 2019	Revised Draft	Stephen Whitaker / Gerry Moore	Cameron Franklin
003	19 March 2019	Final	Stephen Whitaker / Gerry Moore	Megan Kraft

[©] Cardno. Copyright in the whole and every part of this document belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or in or on any media to any person other than by agreement with Cardno.

This document is produced by Cardno solely for the benefit and use by the client in accordance with the terms of the engagement. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by any third party on the content of this document.



Executive Summary

Cardno has been engaged by Gladstone Regional Council ('Council') to prepare concept designs for a new Inland Link Road connecting Agnes Water and Baffle Creek. Cardno has also undertaken an analysis of the design options to identify a recommended design option that Council can further progress. The design and analysis work undertaken by Cardno have been informed by technical assessments prepared as part of the project and other available information.

Council has identified a need to investigate the improvement of road connections between Agnes Water and Baffle Creek. The existing route, utilising primarily Round Hill Road and Tableland Road, is particularly inefficient and Council is seeking to reduce the travel distance and time through the construction of a shorter alternative route. The new route is intended to benefit both residents and tourists, noting the local / regional service role played by Agnes Water, whilst also improving local connectivity in emergency situations.

Cardno has prepared concept designs for eight (8) design options (refer to **Appendix A**), which are each supported by preliminary opinions of cost (**Appendix B**). An options analysis has been undertaken consisting of two stages:

- > Stage 1 involving an initial qualitative assessment of all eight (8) design options to identify five (5) preferred design options; and
- > Stage 2 involving a multiple criteria analysis of the five (5) preferred design options to identify a single recommended design option.

The analysis undertaken identifies that Design Option 2A is the recommended design option on the following basis:

- > Design Option 2A provides value for money for Council, when compared to alternative designs, based on the concept designs prepared, for both interim and ultimate road designs;
- > Design Option 2A is wholly located in Council owned or controlled land or existing road reserves and is not anticipated to require the resumption of any privately owned land;
- > Design Option 2A has an acceptable environmental impact, acknowledging that the broader area is subject to a variety of environmental constraints;
- > Design Option 2A connects to Anderson Way in the north, which is considered to be highly suitable to support anticipated traffic volumes based on existing road construction and overall road network layout;
- > Design Option 2A connects to Maude Hill Road in the south, which is considered to be the most suitable tie in point in the south of the study area;
- > Design Option 2A provides an efficient and direct connection between the north and south of the study area:
- > Design Option 2A achieves Council's objectives in relation to the project;
- > It is anticipated that limited external works would be required to facilitate the delivery of Design Option 2A;
- > The connection points in the north and south of Design Option 2A are considered to minimise traffic related impacts on surrounding residents having regard to the form and function of existing roads;
- > Design Option 2A does not impact on existing recreational facilities; and
- Design Option 2A does not present any notable safety concerns, with any potential concerns relating to speed management able to be controlled through design interventions in the road environment, as required and further investigated.

In order to further progress with the project, Cardno recommends that Council:

- > Complete a detailed review of the recommended design option;
- Complete further investigations, as required, to confirm the accuracy of currently available information, noting the present limitations, in order to confirm the most suitable road alignment and design. These may include, but may not necessarily be limited to:
 - Detailed land survey of the corridor within which the recommended design option is to be located;
 - Environmental field assessment, to confirm the findings of the desktop assessment documented in this
 report and confirm approval requirements, further to the findings documented in Table 5-4;



- Detailed flood assessment, particularly relating to the recommended design option, to confirm requirements in relation to waterway crossings and road levels; and
- Detailed geotechnical investigations associated with the recommended design option, to confirm the required pavement design;
- Identify any instances where speed control measures may be required as part of the recommended design option to improve safety;
- > Undertake further internal consultation to identify any additional matters of technical consideration;
- Engage with various external stakeholders (as relevant) including (but not limited to) local land holders and the broader community, local businesses and tourism operators, the Department of Natural Resources and Mines (with respect to new road reserves and other titling matters), the Department of Environment and Science (where required in relation to the Deepwater National Park), the Department of the Environment and Energy (relating to the EPBC Act) and Ergon Energy (with respect to the relationship between the new road and existing electricity infrastructure);
- > Consider the co-location of telecommunications infrastructure in the road design, if appropriate; and
- > Progress with the detailed design of the proposed road, when appropriate, to allow for the accurate costing of the project.



Table of Contents

	1	Introdu	uction	1
	2	Projec	ct Background	2
	3	Metho	odology	4
		3.1	Design Approach and Considerations	4
		3.2	Consultation	5
		3.3	Information Gathering	5
		3.4	Options Analysis	5
		3.5	Qualifications and Assumptions	7
	4	Design	n Options	9
		4.1	Summary	9
		4.2	General Design Principles	9
	5	Techn	nical Assessments	11
		5.1	Drainage Assessment	11
		5.2	Geotechnical Sampling and Testing	11
		5.3	Environmental Assessment	12
		5.4	Land Titling and Ownership	23
		5.5	Speed Control	24
	6	Option	ns Analysis	25
		6.1	Stage 1 – Initial Assessment	25
		6.2	Stage 2 – Multiple Criteria Analysis	28
		6.3	Summary	29
	7	Conclu	usion and Recommendations	31
۱n	nenc	licos		

Appendix A	Design Options
Appendix B	Preliminary Opinion of Cost
Appendix C	Geotechnical Report
Appendix D	Certificates of Title
Appendix E	Meeting Minutes
Appendix F	MCA Explanatory Table

Tables

Table 3-1	Road Design Standard	4
Table 4-1	Design Options	9
Table 5-1	Regional Ecosystems	14
Table 5-2	Protected Areas	18



Table 5-3	Mapped Waterways	18
Table 5-4	Recommendations and Approval Requirements	21
Table 5-5	Land Titling and Ownership	23
Table 6-1	Initial Assessment	25
Table 6-2	Multiple Criteria Analysis	29
Figure	s	
Figure 2-1	Potential Alignments identified by Council	3
Figure 3-1	Options Analysis Methodology	6
Figure 3-2	Multiple Criteria Analysis	7
Figure 5-1	Extract of Protected Plants Flora Survey Trigger Map	17
Figure 5-2	Queensland Waterways for Waterway Barrier Works Extract	19
Figure 5-3	Extract of Wetland protection area mapping and alignment options	20
Figure 5-4	Land subject to Environmental Authorities	20
Figure 6-1	Analysis Process	30



1 Introduction

Cardno has been engaged by Gladstone Regional Council ('Council') to prepare concept designs for a new Inland Link Road connecting Agnes Water and Baffle Creek. Cardno has also undertaken an analysis of the design options to identify a recommended design option that Council can further progress. The design and analysis work undertaken by Cardno have been informed by technical assessments prepared as part of the project and other available information.

This report discusses the design options prepared by Cardno and documents the analysis exercise undertaken. The report contains the following chapters.

- > Chapter 2 provides a summary of the background to the project, including Council's work to date;
- > Chapter 3 outlines the methodology employed by Cardno in completing the design and analysis work documented in this report;
- > Chapter 4 provides a description of each of the design options prepared by Cardno;
- > Chapter 5 provides a summary of the technical assessments undertaken as part of the project, to inform the design and analysis work;
- > Chapter 6 documents the analysis of the design options and identifies the recommended design option; and
- > Chapter 7 provides a summary of the work undertaken and provides recommendations to Council for further work associated with the project.

The report is supported by a variety of information contained in technical appendices, the most relevant of which is **Appendix A**, which contains the concept design drawings for each of the design options.



2 Project Background

Council has identified a need to investigate the improvement of road connections between Agnes Water and Baffle Creek. The existing route, utilising primarily Round Hill Road and Tableland Road, is particularly inefficient and Council is seeking to reduce the travel distance and time through the construction of a shorter alternative route. The new route is intended to benefit both residents and tourists, noting the local / regional service role played by Agnes Water, whilst also improving local connectivity in emergency situations.

Council intends to deliver the road in three (3) stages:

- 1. Interim construction to an access track standard, with gravel surface and 5.5 metre width;
- 2. Upgraded construction to a two lane gravel road, with an intended design speed of 110km/h; and
- 3. Ultimate construction to a two lane sealed road, with an intended design speed of 110km/h.

Council has undertaken a preliminary review of the local area and has identified a broad potential corridor for the new link road. Within this broad corridor, five (5) potential alignments for the link road have been identified:

- > Alignment 1: A new road running from Jobson Road in the north, partly utilising the existing sewerage treatment plant access road and connecting to Maude Hill Road in the south;
- > Alignment 2: A new road running from Jobson Road in the north utilising a new alignment to the east of the sewerage treatment plant access road and connecting to Maude Hill Road in the south;
- > Alignment 3: A new road running from Rocky Crossing Road in the north-west, then running southward to connect to Maude Hill Road;
- Alignment 4: A new road running from Springs Road in the north to Wreck Rock Road in the south. The interim construction of this road will follow an existing access track partly located within the Deepwater National Park while the upgraded and ultimate alignment will reflect an amended alignment to cater for the 110km/h design speed; and
- Alignment 5: A new road running from Uxbridge Road in the north-west along existing road reserves in a general north-south alignment and then an east-west alignment and connecting to Maude Hill Road in the south.

Alignments 1, 2 and 3 are common in the southern section, which generally follows an existing Ergon Energy maintenance track before connecting to Maude Hill Road.

The general location of each of the preliminary alignment options is shown in Figure 2-1.






Figure 2-1 Potential Alignments identified by Council

Council has engaged Cardno to prepare a concept design for each of the preliminary alignments to allow Council to further consider the project before proceeding toward detailed design, funding and construction. The design work completed by Cardno is documented in the design options discussed in Chapter 4 and assessed in Chapters 5 and 6.



3 Methodology

Chapter 3 describes the methodology employed by Cardno in completing the design and analysis work for the project.

3.1 Design Approach and Considerations

Cardno has prepared concept designs for a total of eight design options, consisting of:

- > The five (5) design options identified by Council, as discussed in Chapter 2; and
- Three (3) alternative design options resulting from further refinement and review of the Council identified options.

These design options are provided in Appendix A.

The design options have been prepared on the basis of the ultimate design achieving compliance, to the greatest extent practical, with Council's distributor road standard in rural areas, as described in Table 7 of Council's Road Hierarchy Policy (Policy No. P-2014/31). Table 3-1 describes the key parameters of this design standard.

Table 3-1 Road Design Standard

Parameter	Standard
Design speed	110km/h
Minimum road reserve width	30 metres
Carriageway Form	2 lanes
Road surface	Sealed
Shoulder surface	Sealed
Minimum curve radius	1,100 metres
Minimum formation width	13 metres
Carriageway width	9 metres
Through lane width	3.5 metre
Shoulder width	1 metre
Minimum verge width	1 metre (typically 2 metres)
Maximum longitudinal grade	7%

The ultimate design cross section, as derived from Table 3-1, has been applied to all road alignments, with localised areas of deficiency resolved on a case by case basis. Alternative standards, including Austroads Guide to Road Design, have been consulted in resolving deficiencies. Further discussion is provided in Chapter 4 of this report.

The interim design and upgraded designs have been produced based on the ultimate design cross section, with the exception of Option 4, which includes an alternative alignment for the interim design.



3.2 Consultation

Cardno has completed the design and analysis work in direct consultation and collaboration with Council. Specific consultation activities undertaken with Council for the project include:

- > A project inception with Council held on 16 January 2019 to confirm project objectives and methodology;
- A design workshop with Council held on 6 February 2019 to present preliminary versions of the design options;
- A design workshop with Council held on 6 March 2019 to discuss a draft version of the project deliverables;
- Provision of a draft version of all project deliverables for Council review and incorporation of Council comments in the final project deliverables; and
- Ongoing liaison with Council throughout the course of the project, to discuss and resolve specific technical matters.

Minutes of project meetings are provided in **Appendix E**.

3.3 Information Gathering

The following information has informed the design and analysis work undertaken:

- > Cadastral information sourced from the Queensland Government's Digital Cadastral Database (DCDB);
- > Certificates of title sourced from the Queensland Government (refer to Appendix D);
- > Survey data provided by Gladstone Regional Council covering design options outlined in the original project brief;
- > LIDAR data sourced from the Commonwealth Government's Elevation System Information (ELVIS) covering the remaining design options;
- Seotechnical sampling undertaken by Construction Sciences at select locations between 23 and 25 January 2019. Further discussion in relation to geotechnical sampling and testing is provided in Section 5.2:
- > The resources listed in Section 5.3.1, used to inform the Environmental Assessment; and
- Observations made during a site inspection of the northern connection points of select design options, undertaken on 6 February 2019.

3.4 Options Analysis

Upon completion of the concept designs, an options analysis was undertaken in order to identify a recommended design. The options analysis has been conducted in two stages:

- > Stage 1 Initial Assessment; and
- Stage 2 Multiple Criteria Analysis.

The methodology employed in these two stages is discussed in greater detail in the following sub-sections and summarised in Figure 3-1. Further detail in relation to the methodology employed in the Multiple Criteria Analysis is also provided in **Appendix F**.






Figure 3-1 Options Analysis Methodology

3.4.2 Stage 1 – Initial Assessment

Stage 1 involves the assessment of all eight (8) design options. The intent of Stage 1 is to identify five (5) preferred design options that will be further considered in Stage 2. Stage 1 employs a qualitative analysis of each design option, identifying benefits and potential areas of concern, based on available information. Preliminary opinions of cost have also been prepared for each design option (refer to **Appendix B**) and have been used to inform financial considerations associated with the analysis.

The selection of the preferred design options was undertaken in consultation with Council as part of the project's design workshop (refer to Section 3.2).

3.4.3 Stage 2 - Multiple Criteria Analysis

Stage 2 involves the assessment of the five (5) preferred design options utilising a multiple-criteria analysis (MCA). MCA is an evaluation method which ranks the performance of options against criteria. Each design option is rated against criterion, which collectively form an evaluation matrix. Criteria are weighted to represent their importance. The weights are combined with the evaluation matrix to attain an overall rank or score for each decision option. Figure 3-2 provides an overview of the MCA process that was used as part of the Stage 2 analysis.






Figure 3-2 Multiple Criteria Analysis

The criteria used for the MCA are described in Section 6.2 of this report. The criteria and their weightings were formulated in consultation with Council, having regard to the intention and objectives of the project and the technical assessments undertaken.

3.5 Qualifications and Assumptions

The design and analysis work documented in this report has been undertaken based on the information available at the time the work was completed. In the event that new or changed information becomes available, this may change the relevance of the designs presented or the accuracy of the analysis undertaken. The following specific qualifications and assumptions are relevant to the project:

- > The design recommendations included in this design package are conceptual in nature only and are not for construction. All engineering details including Safety in Design considerations shall be confirmed during the detail design phase of the project by the relevant engineering disciplines;
- > All horizontal and vertical alignments have been prepared using publicly available base information such as cadastral boundaries and LIDAR information. The accuracy of this base information shall be confirmed prior to commencement of the detail design works;
- Superelevation, whilst not considered as part of the concept design, is acknowledged as being required in the detail design phase of the project. An allowance has been made within each option's "Opinion of Cost" (Appendix B) to account for this;
- A general assessment of the major cross drainage locations has been considered and applied across all relevant options. Particular consideration to drainage and waterway barrier works requirements have been made with both requirements noted within this report. A full detailed assessment will need to be undertaken during the detail design phase of the project to determine the dominant requirement for each major crossing and further cross drainage requirements;
- > A hydraulic assessment of the design options is not part of the concept design scope and will need to be undertaken as part of the detail design phase of the project;
- > The location of, and impact of the design options on, any Ergon Energy assets has been assumed based on available information. A detailed land survey of the locations of Ergon Energy infrastructure is to be commissioned in the near future and will be incorporated into the findings of this report once complete; and



> Easements affecting relevant lots have been identified in Section 5.4 of this report, however the terms of these easements have not been reviewed. It is recommended that the terms of any affected easement be reviewed by Council (or its legal advisors) to inform the project.



4 Design Options

4.1 Summary

This report relates to eight (8) design options prepared by Cardno for the proposed Inland Link Road. The design options have been summarised in Table 4-1 below. The numbering used in Table 4-1 has been consistently used throughout this report and the supporting documentation. The design options are based on the Council supplied alignments discussed in Chapter 2 of this report, with numbering of the design options also linking to these alignment (i.e. Design Option 2A is a derivative of Alignment 2).

Table 4-1 Design Options

Design Option	Northern Connection	Southern Connection			
1	Jobson Road	Maude Hill Road			
2	Jobson Road	Maude Hill Road			
2A	Anderson Way	Maude Hill Road			
2B	Streeter Drive	Maude Hill Road			
3	Rocky Crossing Road	Maude Hill Road			
3A	Rocky Crossing Road	Maude Hill Road			
4 (Interim)	Chrings Dood	Wreck Rock Road			
4 (Ultimate)	Springs Road	WIECK ROCK ROAG			
5	Uxbridge Road	Maude Hill Road			

Design Options 1, 2, 2A, 2B, 3 and 3A share the same alignment in the south of the study area. This section of road has been referred to as the shared southern section for the purposes of this report.

Design Option 4 comprises different interim and ultimate alignments, with Design Option 4 initially involving the upgrading of an existing access track to the interim design standard, prior to the construction of a new road on a different alignment under the ultimate scenario. The interim and ultimate alignments are considered to form a single design option for the purpose of this report.

Concept drawings for each of the design options are presented in Appendix A.

4.2 General Design Principles

The design options and road profiles are intended to maximise the use of the natural terrain providing a realistic, efficient and safe design for public use.

The topography of the site area is generally low-lying flat / gently sloping land with exception of the tie in locations for Design Options 1, 2, 2A, 3 and 3A and Design Option 4 to the east through the Deepwater National Park. The major consideration or limitation to these alignments is these undulating areas, particularly when applying geometric constraints and tying into existing road formations. As a result, these areas will have some degree of cutting and filling to traverse through the ridges / gullies, which in some instances may produce high volumes and structural requirements.

Where the use of retaining structures has been recommended, further geotechnical and structural investigations will be required in order to determine a suitable structural solution. However, for the purposes of the conceptual design and quantification, Cardno has assumed a face slope of 5V:1H for all retaining structures (benching has not been considered at this point).

With the exception of Design Options 4 (interim) and 5, all alignments achieve a design speed of 110km/h across the majority of their lengths. Joining into external road networks does however adversely affect the achievable design speed for all design options. It is recommended to locally reduce the design speed to a maximum of 70km/h through difficult locations in order to provide a safe, compliant and cost effective road design.

The intension of Design Option 4 (interim) is to upgrade the existing four-wheel drive track, providing access for two-wheeled vehicles. Achieving the desirable 110km/h design speed set out in Council's Road Hierarchy Policy is not feasible due to steep and undulating terrain within the study area. Significant earthworks and



heavy retaining structures will be required to achieve compliance with these requirements. Design Option 4 (Ultimate) is intended to provide a 110km/h design speed alignment.

In relation to Design Option 5, horizontal constraints associated with the boundaries of the road reserve mean that a 110km/h design speed is generally not achievable. Whilst a vertical profile has been applied to the concept design, further direction from Council will be required to understand the design intention of this option.



5 Technical Assessments

Technical assessments have been undertaken to inform the location, design and assessment of the design options. The overarching findings of the technical assessments are presented in this chapter, with commentary in relation to each design option provided in Chapter 6.

5.1 Drainage Assessment

The rational method has been employed to complete a drainage assessment of the upstream catchment of the design options. It is noted that the Queensland Urban Drainage Manual does not limit the catchment size to which the rational method can be applied in a rural setting.

Longitudinal and cross drainage have been considered and allowances made to cater for overland flows expected within the project catchment area. It is not practical to analyse all drainage details as part of this concept design exercise, however table drains and cross drainage culverts (located at 500 metre intervals) have been accounted for throughout the project. Confirmation of the drainage requirements will be undertaken during the detail design phase of the project.

It is noted that each of the preferred design options traverse waterways classified by the Department of Agriculture and Fisheries as subject to assessment for waterway barrier works purposes. For Design Options 2, 2A and 3A waterways are only mapped in the shared southern section. Culverts required for waterway crossings in each of the design options have been sized having regard to the findings of the drainage assessment and the requirements associated with waterway barrier works (where applicable), which are further discussed in greater detail in Section 5.3.2.4 of this report.

The following summary is provided in relation to the drainage assessment undertaken:

- > Ideally, the flood immunity of new crossings consider a Q20 flood event;
- > Preliminary drainage calculations at major crossings exceed 400m³/sec in a Q20 event, indicating significant structures will need to be constructed to achieve this level of flood immunity. The costs associated with these types of crossings could be prohibitive;
- > Requirements at major crossings associated with waterway barrier works are far less than hydraulic requirements, meaning hydraulic requirements will be the key design determinant;
- > Given the rural setting it may be more appropriate for the road and subsequent crossings to be designed at a lower flood immunity (such as Q1 or even Q0.5) in order to reduce construction costs. This will require Council's approval; and
- Further consideration is also required with regard to the treatment of the road surface, to reduce costs and environmental impacts associated with flood events. For an unsealed road this may include the use of cement stabilised pavements.

In order to understand the relationship between the proposed road and the hydraulic characteristics of the surrounding locality, a flood / hydraulic assessment at varying levels is required. It is recommended that a 'Time of Closure' assessment be included in this assessment. This will allow Council to determine an achievable and acceptable level of immunity for the road and the required crossings. The cost estimates provided in **Appendix B** have assumed a nominal amount for waterway crossings given the unknown nature of required works.

5.2 Geotechnical Sampling and Testing

Construction Sciences Pty Ltd undertook soil sampling at 23 boreholes in the study area between 23 and 25 January 2019. The findings of the testing of each collected soil sample are documented in the report provided as **Appendix C**. The findings of the geotechnical report have been used to inform the pavement design presented as part of the design options provided as **Appendix A**.

Given the vast project area and uncertainty of the preferred option, a typical pavement has been applied throughout the project. This pavement aims to account for the poorer low-lying areas, sandy material to the east (Design Option 4) and rocky northern tie in locations of the central options. These have been detailed in the concept drawings (**Appendix A**) and include a recommendation that a geotextile material be placed under the sub-grade material to provide a more stable foundation for the road pavement.



5.3 Environmental Assessment

5.3.1 Methodology

An Environmental Assessment has been undertaken with specific consideration of the preferred design options discussed in Section 6.2 of this report. The assessment has been informed by undertaking a range of desktop searches using available database and mapping resources, including:

- > Agnes Water STP Rising Main Replacement Protected Plant Assessment (GHD Pty Ltd 2015);
- high resolution aerial photography sourced from Nearmap;
- > historical imagery;
- > Protected Plants Trigger Mapping under the Nature Conservation Act 1992 ('the NC Act);
- > mapping associated with the Koala State Planning Regulatory Provisions;
- > the Vegetation Management Act 1999 ('the VM Act') Regulated Vegetation Management Map ('Regulated Vegetation Map') produced by the Department of Natural Resources, Mines and Energy (DNRME);
- the Wildlife Online database which is maintained by the Department of Environment and Science (DES) under the NC Act:
- > the Environment Protection and Biodiversity Conservation Act 1999 ('the EPBC Act') Protected Matters Search Tool;
- > the Atlas of Living Australia database and mapping tools;
- > the Australian Virtual Herbarium;
- > mapping associated with the State Development Assessment Provisions;
- > mapping associated with the Queensland State Planning Policy;
- > mapping associated with the Gladstone Regional Council Planning Scheme; and
- > the Aboriginal and Torres Strait Islander Cultural Heritage Register and Database.

5.3.2 Desktop Assessment Results

5.3.2.1 Environment Protection and Biodiversity Conservation Act 1999

Due to the coarseness of the EPBC Act mapping and the fact that the alignment options are spatially close to each other there is very little differentiation in the database outputs.

Primarily the difference relates to the fact that the search area for Design Option 4 coincides with the marine and estuarine environment. There is a larger number of species that rely on these specific habitat conditions, such as sea turtles, migratory shorebirds and whales. None of these species would be significantly impacted by the proposed works.

Two flora species, *Cycas megacarpa* and *Germainia capitata*, both listed as Endangered under the EPBC Act have been returned in the results for all alignments. Given these two species have been recorded by GHD in the vicinity of the shared southern section and suitable habitat is considered to occur across the broader study area it is likely that further consideration including targeted surveys for these species would be required regardless of the design option selected.

A number of Threatened Ecological Communities (TEC) were also returned by the EPBC Act Protected Matters Search Tool (PMST) including:

- > Coastal Swamp Oak (Casuarina glauca) Forest of New South Wales and South East Queensland ecological community;
- > Littoral Rainforest and Coastal Vine Thickets of Eastern Australia; and
- > Lowland Rainforest of Subtropical Australia.

Regional Ecosystem 12.2.2, which is discussed further in Section 5.3.2.2, is consistent with the description for the Littoral Rainforest TEC. RE 12.2.2 is only mapped as occurring along the coastal dunes associated with Design Option 4.



None of the other RE returned in the desktop searches are wholly consistent with any of the other TECs noted above. However, a field survey would be required to confirm the presence or absence of these TECs within the design options.

5.3.2.2 Vegetation Management Act 1999

Pursuant to Schedule 21, Part 2, Section 5 of the *Planning Regulation 2017*, the clearing of vegetation within a road reserve is exempt clearing work for which development approval is not required under the VM Act, provided the clearing is undertaken by Council and:

- > is necessary to construct or maintain road transport infrastructure or to source construction material for roads; or
- > involves Category R or Category X vegetation.

However, for the purpose of this desktop assessment, the remnant Regional Ecosystems (RE) potentially impacted by the various design option have been identified in Table 5-1 along with short descriptions of each RE, its designation under the VM Act and any possible special values associated with the RE.

It is important to note that parts of the design options are not presently covered by road reserves and until such time as road reserves are created, approvals may be required for the clearing of vegetation in these locations.

Table 5-1 identifies in bold the most common RE within each preferred design option. It is important to note the following.

- > For Design Option 5 there is approximately:
 - 40 ha of RE that is considered to be suitable habitat for Cycas megacarpa which is listed as Endangered under the EPBC Act and the NC Act and which has been positively identified from the broader locality during surveys completed in 2015, and
 - 70 ha of RE that is considered to be suitable habitat for *Germainia capitata* which is listed as Vulnerable under the EPBC Act and the NC Act and which has been positively identified from the broader locality during surveys completed in 2015.
- > For the shared southern section there is approximately 40 ha of RE that is considered to be suitable habitat for *Germainia capitata* which is listed as Vulnerable under the EPBC Act and the NC Act and which has been positively identified from the broader locality during surveys completed in 2015.



Regional Ecosystems Table 5-1

RE	Short Description	VM Act Status¹	Special Values	Area of RE contained within 1 km buffer of design option (ha)						
				Shared Southern Section (2, 2A, 3A)	2	2A	3A	4	5	
12.12.28	Eucalyptus moluccana woodland on Mesozoic to Proterozoic igneous rocks	ОС	None	-	-	-	-	-	9.0	
12.12.21	Corymbia intermedia, E. exserta woodland on Mesozoic to Proterozoic igneous rocks	ОС	Habitat for threatened plant species including Cycas megacarpa.	-	-	-	-	-	37.39	
12.12.13	Araucarian Complex microphyll to notophyll vine forest on Mesozoic to Proterozoic igneous rocks	LC	Habitat for threatened plant species including Sarcochilus weinthalii, Corynocarpus rupestris subsp. arborescens and near threatened species including Hernandia bivalvis.	-	<0.01	-	0.58	-	-	
12.12.12	Eucalyptus tereticornis, Corymbia intermedia, E. crebra +/- Lophostemon suaveolens woodland on Mesozoic to Proterozoic igneous rocks	ОС	None	-	-	-	-	-	8.27	
12.12.11	Eucalyptus portuensis or E. acmenoides, Corymbia trachyphloia subsp. trachyphloia woodland on Mesozoic to Proterozoic igneous rocks	LC	None	-	3.25	5.28	3.69	-	26.91	
12.12.5	Corymbia citriodora subsp. variegata, Eucalyptus crebra woodland on Mesozoic to Proterozoic igneous rocks	LC	Habitat for threatened plant species including Cycas megacarpa.	-	0.02	-	3.23	-	0.02	
12.5.10	Eucalyptus latisinensis and/or Banksia aemula low open woodland on complex of remnant Tertiary surface and Tertiary sedimentary rocks	LC	None	5.04	-	-	-	-	-	

E = Endangered OC = Of Concern

LC = Least Concern

¹ Note:



RE	Short Description	VM Act Status ¹	Special Values	Area of RE contained within 1 km buffer of design option (ha)						
				Shared Southern Section (2, 2A, 3A)	2	2A	3A	4	5	
12.5.5	Eucalyptus portuensis, Corymbia intermedia open forest on remnant Tertiary surfaces. Usually deep red soils	ОС	None	8.38	0.36	0.59	1.22	-	19.47	
12.5.4 / 12.5.4a	Eucalyptus latisinensis +/- Corymbia intermedia, C. trachyphloia subsp. trachyphloia, Angophora leiocarpa, Eucalyptus exserta woodland on complex of remnant Tertiary surfaces and Cainozoic and Mesozoic sediments	LC	Habitat for threatened plant species including Macrozamia lomandroides, Germainia capitata and near threatened species including Melaleuca cheelii.	21.19	2.9	3.84	4.4	-	33.0	
12.5.2a	Corymbia intermedia, Eucalyptus tereticornis open forest on remnant Tertiary surfaces, usually near coast. Usually deep red soils	Е	Habitat for threatened plant species including Melaleuca irbyana.	5.16	-	-	-	-	5.81	
12.3.13	Closed heathland on seasonally waterlogged alluvial plains usually near coast	LC	None	0.48	-	-	-	0.5	-	
12.3.12	Eucalyptus latisinensis or E. exserta, Melaleuca viridiflora var. viridiflora woodland on alluvial plains	LC	Habitat for threatened plant species including Germainia capitata.	20.89	3.61	2.85	1.85	-	34.44	
12.3.7	Eucalyptus tereticornis, Casuarina cunninghamiana subsp. cunninghamiana +/- Melaleuca spp. fringing woodland	LC	Habitat for an extensive range of aquatic flora and fauna.	-	-	-	-	-	0.58	
12.3.6	Melaleuca quinquenervia +/- Eucalyptus tereticornis, Lophostemon suaveolens, Corymbia intermedia open forest on coastal alluvial plains	LC	Habitat for threatened fauna species including the wallum froglet Crinia tinnula.	10.1	1.79	2.34	4.84	13.7	11.96	
12.3.4	Melaleuca quinquenervia, Eucalyptus robusta woodland on coastal alluvium	ОС	Habitat for threatened fauna species including the wallum froglet Crinia tinnula.	1.9	-	-	-	-	-	
12.3.3	Eucalyptus tereticornis woodland on Quaternary alluvium	Е	Habitat for threatened plant species including Rhaponticum australe.	-	-	-	-	0.01	4.5	
12.2.11	Corymbia tessellaris +/- Eucalyptus tereticornis, C. intermedia and Livistona decora woodland on beach ridges in northern half of bioregion	LC	None	-	-	-	-	36.93	-	



RE Short Description		VM Act Status ¹	Special Values	Area of RE contained within 1 km buffer of design option (ha)						
				Shared Southern Section (2, 2A, 3A)	2	2A	3 A	4	5	
12.2.9	Banksia aemula low open woodland on dunes and sand plains. Usually deeply leached soils	LC	Habitat for near threatened plant species including Macarthuria complanata.	-	-	-	-	12.82	-	
12.2.7	Melaleuca quinquenervia or rarely M. dealbata open forest on sand plains	LC	Habitat for threatened plant species including Phaius australis, P. bernaysii and near threatened species including Durringtonia paludosa.	-	-	-	-	3.38	-	
12.2.2	Microphyll/notophyll vine forest on beach ridges	E	Habitat for threatened plant species including Acronychia littoralis and near threatened species including, Xylosma ovata and Dansiea elliptica.	-	-	-	-	8.97	-	
Non- remnant	N/A	N/A	None	4.75	10.04	9.66	0.5	-	14.64	



5.3.2.3 Nature Conservation Act 1992

5.3.2.3.1 Protected Plants - High Risk Trigger Area

All five preferred design options partly traverse land mapped as 'High risk area' pursuant to the Protected Plants Flora Survey Trigger Map. Figure 5-1 shows the mapped High risk areas, with the red lines indicatively showing Design Options 4 and 5 for context. Figure 5-1 shows that the primary constraint associated with the High risk area is in the northern portion of Design Options 2, 2A and 3. It is relevant to note that this area coincides with the known populations of *Germainia capitata* and *Cycas megacarpa* recorded by GHD.




Figure 5-1 Extract of Protected Plants Flora Survey Trigger Map

5.3.2.3.2 Conservation Significant Species

All of the preferred design options have returned records for Endangered, Vulnerable or Near Threatened species (EVNT) under the NC Act. As has been noted previously, the most consistently recorded species appear to be *Germainia capitata* and *Cycas megacarpa*, which, based on reporting completed by GHD, are confirmed in the northern portion of the broader locality. It is also relevant to note that suitable habitat for these species occurs across a broader area of the preferred design options and given the existing information it is likely that they will occur.

The largest number of EVNT species was returned for Design Option 4. Many of these are directly associated with the marine and/or intertidal environment, however, there are a number of species that were recorded in the Design Option 4 area that are also considered likely to occur across the broader locality. The species considered most likely to occur across the broader locality have been listed below along with their designation under the NC Act and the EPBC Act:

- > Powerful owl (*Ninox strenua*), Vulnerable and N/A;
- > Southern greater glider (Petauroides volans volans), Vulnerable and Vulnerable; and
- Koala (Phascolarctos cinereus), Vulnerable and Vulnerable.

Further on ground assessments would be required to determine if these species and/or likely habitat for same occurs within the impact area of the other preferred design options.

5.3.2.3.3 Native Fauna Breeding Places

Given the extensive areas of remnant vegetation and the proximity of Deepwater National Park it is likely that the broader locality supports abundant fauna breeding locations. This is likely to include:

> recognised breeding features such as nests, hollows and termitaria; and



> generalised breeding features such as waterways and ponded areas.

Field surveys would be required to more accurately determine the number and location of breeding features within each of the preferred design options.

5.3.2.3.4 Protected Areas

The relationship between protected areas and the preferred design options is summarised in Table 5-2.

Table 5-2 Protected Areas

Design Option	Protected Areas
2	The design option adjoins, but does not traverse, Deepwater National Park at the southern limit of the alignment.
2A	The design option adjoins, but does not traverse, Deepwater National Park at the northern and southern limits of the alignment.
3A	The design option traverses Deepwater National Park at the northern end of the alignment and adjoins Deepwater National Park at the southern end of the alignment.
4	The design is entirely located within Deepwater National Park and a Nature Refuge to the north.
5	The design option does not traverse or adjoin any mapped Projected Areas.

5.3.2.4 Fisheries Act 1994

Waterways, mapped by the Department of Agriculture and Fisheries (DAF), for the purpose of Waterway Barrier Works approval, traverse the broader locality. The mapped waterways traversed by each of the preferred design options are described in Table 5-3.

Table 5-3 Mapped Waterways

Design Option	Mapped Waterways				
2, 2A and 3A (Shared Southern Section)	 Four (4) Green – Low Risk Waterways Two (2) Amber – Moderate Risk Waterways. 				
2 (north)	No crossings of mapped waterways				
2A (north)	No crossings of mapped waterways				
3A (north)	No crossings of mapped waterways				
4	One (1) Red – High Risk Waterway				
5	 Five (5) Green – Low Risk Waterways One (1) Amber – Moderate Risk Waterway 				

Figure 5-2 shows the mapped waterways described in Table 5-3.






Figure 5-2 Queensland Waterways for Waterway Barrier Works Extract

5.3.2.5 State Assessment and Referral Agency – Development Assessment Mapping

5.3.2.5.1 Queensland Heritage Register

None of the preferred design options are located near any known features on the Queensland Heritage Register.

5.3.2.5.2 Unexploded Ordinance

None of the preferred design options are located within known Unexploded Ordinance zones.

5.3.2.5.3 Coastal Management District including Erosion Prone Area and Storm Tide Inundation Area

Design Option 4 is the only preferred design option that will traverse the mapped Coastal Management District (CMD) and areas mapped as Erosion Prone and Medium Storm Tide Inundation.

The shared southern section will traverse a small area of Medium Storm Tide Inundation, associated with Fullers Creek.

5.3.2.5.4 Wetland Protection Area

All of the preferred design options will traverse areas of mapped Wetland Protection Area and associated trigger areas. The extract provided in Figure 5-3 shows that Design Options 2, 2A and 3A traverse the largest area of mapped wetland and trigger area.






Figure 5-3 Extract of Wetland protection area mapping and alignment options

5.3.2.6 Environmental Protection Act 1994

Design Options 2, 2A, 3A and 5 with either traverse or immediately adjoin land that is subject to the following Environmental Authorities (EA):

- > DTMR ERA 16 Extraction and Screening (EPPR00770213); and
- > GRC ERA 63 Sewage Treatment (EPPR00770213).

The location of the land subject to the EAs is shown in Figure 5-4.



Figure 5-4 Land subject to Environmental Authorities



5.3.2.7 Aboriginal Cultural Heritage Act 2003

Based on the search results of the Aboriginal and Torres Strait Islander Cultural Heritage Register and Database, there is one known Scarred/carved tree close to the northern extent of Option 3A. There are also a larger number of artefact scatters in the broader locality.

5.3.3 Recommendations and Approval Requirements

Table 5-4 provided below summarises the key results obtained though the desktop assessment process. It is important to note that only matters that must be addressed through additional assessment and/or approval are identified in Table 5-4.

Table 5-4 Recommendations and Approval Requirements

Area of Consideration	Element Present within Site?	Approval or Further Action Required	Key Findings and recommendations
Environment Protection and Biodiversity Conservation Act 1999	Possible	Yes	 Matters of National Environmental Significance (MNES) are likely to occur in the broader locality. Field surveys are required to determine the likely occurrence of MNES and habitat for same within and adjoining areas of proposed disturbance. Once a design option has been selected and, if MNES are known or likely to be impacted by the selected design option, it is recommended that a self-assessment against the EPBC Act Significant Impact Guidelines is completed to determine if a referral to the Commonwealth Department of Environment and Energy for a decision on whether the action is a controlled action is warranted.
Nature Conservation Act 1992 Protected Plants	Yes	Yes	 All of the preferred design options partly traverse land mapped within a High Risk Trigger Area for a Protected Plants Flora Survey. At this stage it is understood that there will likely be clearing of native in the wild vegetation. A survey in accordance with the guidelines must be conducted within the areas of proposed clearing and a 100 metre buffer of the extent of clearing. If any Endangered, Vulnerable or Near Threatened flora species are detected, a clearing permit and Impact Management Plan would be required prior to clearing any native vegetation.
Fisheries Act 1994 Waterway Barrier Works	Yes	Yes	 Mapped waterways are traversed by all of the preferred design options. Any instream works (e.g. culverts, bridges) will need to comply with the Accepted development requirements for operational work that is constructing or raising waterway barrier works (ADR) for Waterway Barrier Works or will need a Development Approval for Carrying Out Operational Work.
Nature Conservation Act 1992 Species Management Program (SMP) – Fauna Breeding Places	Probable	Yes	 It is likely that the areas of native vegetation with the study area support breeding places for native wildlife. A field survey should be conducted to ascertain if there are any known or likely fauna breeding features within selected design option. Based on the desktop assessment, it is possible that a 'High Risk' SMP for EVNT fauna species would be required for works that result in the disturbance to these features.



Area of Consideration	Element Present within Site?	Approval or Further Action Required		
Nature Conservation Act 1992 Protected Estates	Yes	Yes	 Design Options 3A and 4 will involve works within a Protected Area (Deepwater National Park). Under the NC Act, the chief executive of the DES can allow use of a national park or protected area in a manner that is inconsistent with the management principles or plan. This can occur if: the basic principle for the management of national parks will be observed as far as possible (if the land is in a national park) the use will be in the public interest the use is ecologically sustainable there is no reasonable alternative to the use. If either of these design options is selected, Council would need to apply for Authority under Sections 34, 35, 38 of the NC Act. The application would need to be supported by a Submission Report, Environmental Management Plan, Survey Plans, maps and the required fee. 	
Planning Regulation 2017 GBR Wetlands	Yes	Yes	 All of the preferred design options traverse land that is mapped as Great Barrier Reef wetlands and associated trigger areas. The proposed works are likely to constitute 'High Impact Earthworks'. If these occur within wetland protection area, Development Approval for Operational Work within a Wetland Protection Area will be required. Despite the above, the works may constitute Accepted Development pursuant to Schedule 14 of the Planning Regulation. However, it would be necessary to complete a field assessment to confirm whether the works will not impact mapped or field confirmed wetlands. It is recommended that once a design option has been selected, field surveys are conducted to ascertain if mapped or field confirmed wetlands will be impacted and also determine if the proposed works completed in the vicinity of same constitute 'High Impact Earthworks'. 	
Indigenous Cultural Heritage	Possible	Possible	 A search of the Aboriginal and Torres Strait Islander cultural heritage database and register was completed. There are known items of indigenous cultural heritage within the broader locality. The proposed works will be required to comply with the Aboriginal Cultural Heritage Act 2003 Duty of Care Guidelines Gazettal Date: 16 April 2004 (DoC Guidelines). Specifically: Category 4 - Areas previously subject to Significant Ground Disturbance. This will include areas that have been subject to past disturbance (i.e. the road reserves); and Category 5 - Activities causing additional surface disturbance and new areas of disturbance. This would be associated with clearing vegetation and construction outside of the existing road reserves. For previously disturbed areas within the road reserves, appropriate measures to maintain compliance with the DoC Guideline would include recording possible discoveries via a Construction Environment Management Plan (CEMP) and notification of the recognised aboriginal party, should a known or potential find be made. For areas of new disturbance outside the existing road reserves it is recommended that Council notify the recognised aboriginal party in accordance with the DoC Guideline, and seek: Advice as to whether the area is culturally significant; If it is, agreement on how best the activity may be managed to avoid or minimise harm to any cultural heritage values – this may include completing a cultural heritage assessment and/or cultural heritage management plan. 	



Area of Consideration	Element Present within Site?	Approval or Further Action Required	Key Findings and recommendations
Environmental Authorities and Contaminated Land	Probable	Possible	 Searches of the EMR and CLR were not completed as part of this scope. Once a design option is selected, these searches should be completed. A number of parcels of land are subject to EAs. This is not likely to constrain the design options provided the proposed works do not affect the operations authorized. It is also likely that the land associated with the EA for sewerage treatment will be listed on the EMR/CLR and as such there may be implications associated with any proposed removal of fill from this land.

5.4 Land Titling and Ownership

A preliminary review of land titling matters, including land ownership, has been undertaken in relation to the design options, to inform the assessment undertaken in Chapter 6. A review of existing cadastral information was undertaken to determine land of relevance to the project. Certificates of title were obtained and reviewed for each identified lot, a copy of which is provided as **Appendix D**.

Table 5-5 provides the details of lots and easements of relevance to the project. Table 5-5 should be read in conjunction with the plans provided in **Appendix A**.

Table 5-5 Land Titling and Ownership

Real Property Description	Owner	Tenure	Easements
Lot 12 on FD638	The State of Queensland (Gladstone Regional Council as trustee)	Reserve (Water)	Easement X on SP189311 burdening the lot for electricity purposes to the benefit of Ergon Energy Corporation Limited.
Lot 7 on SP111856	Thomas Balto (Personal Representative Under Instrument 718640239)	Freehold	-
Lot 17 on FD527	Joan Pamela Hills	Freehold	Easement Y on SP189312 burdening the lot for electricity purposes to the benefit of Ergon Energy Corporation Limited.
Lot 19 on FD527	Woodkel Pty Ltd	Freehold	Easement Z on SP189313 burdening the lot for electricity purposes to the benefit of Ergon Energy Corporation Limited.
Lot 153 on NPW866	The State of Queensland (Represented by Department of National Parks, Sport and Racing)	National Park	-
Lot 20 on FD991	Gladstone Regional Council	Freehold	Easement AA on SP189314 burdening the lot for electricity purposes to the benefit of Ergon Energy Corporation Limited.
Lot 21 on SP168519	Gladstone Regional Council	Freehold	Easement AB on SP189314 burdening the lot for electricity purposes to the benefit of Ergon Energy Corporation Limited.
Lot 28 on RP619598	John Hargreaves / June Anne Hargreaves (Joint Tenants)	Freehold	-
Lot 18 on FD527	CBS Corporation Pty Ltd (Trustee Under Instrument 707097829)	Freehold	-
Lot 14 on FD784	CBS Corporation Pty Ltd (Trustee Under Instrument 707097829)	Freehold	-



Real Property Description	Owner	Tenure	Easements
Lot 13 on SP120832	Suzanne Lee Turner	Freehold	-
Lot 1 on RP620278	Traywar Pty Ltd	Freehold	-
Lot 16 on FD526	Kennith Alan D'arcy and Rita Lucia D'arcy (Joint Tenants)	Freehold	-
Lot 15 on FD526	Robert John Anstey and Annette Maree Anstey (Joint Tenants)	Freehold	-
Lot 10 on FD469	Steven Gary Czerwonka (Trustee under Instrument 716714610)	Freehold	-
Lot 1 on SP236012	CBS Corporation Pty Ltd (Trustee under Instrument 707097829)	Freehold	-
Lot 2 on SP236012	CBS Corporation Pty Ltd (Trustee under Instrument 707097829)	Freehold	-
Lot 1 on SP150900	Australian Bush Heritage Fund	Freehold	Easement E on SP150900 burdening the lot to the benefit of Miriam Vale Shire Council. Easement G on SP160548 burdening the lot to the benefit of Lot 2 on SP150900. Easement Q on SP168968 burdening the lot to the benefit of Lots 2, 3 and 4 on SP150900. Easement H on SP160548 (located in Lot 0 on SP150901) benefitting the lot
Lot 0 on SP150901	Body Corporate for Sunrise at 1770 Community Titles Scheme 32536	Freehold	Various easements outside the area of interest for the project – refer to Appendix D for further detail.

In addition to the above lots, various road reserves exist within the study area. The location of the existing road reserves is shown in **Appendix A**.

5.5 Speed Control

The proposed road designs have been prepared on the basis of Council's design requirements, applicable standards and surrounding contextual features, in order to deliver road designs that align with Council's objectives for the project. Direct consideration has not been given to speed control as part of the design process. It is acknowledged that there are locations where the road designs may be conducive to a speed of travel above the intended posted speed limit. It is therefore recommended that Council further consider any requirements for speed control as part of their ongoing investigations relating to the project.



6 Options Analysis

6.1 Stage 1 – Initial Assessment

Stage 1 provides for the initial assessment of each of the design options presented in Chapter 4 of this report, with the intent of selecting preferred design options that will be further considered as part of Stage 2 of the analysis process.

Table 6-1 documents the initial assessment undertaken.

Table 6-1 Initial Assessment

Design Commentary Shared Terrain is generally low lying with slight contours. Southern There is the potential for conflicts to exist with existing Ergon Energy assets (subject to further Section investigation). Geotechnical material is a poor foundation for road pavement. Earthworks would be reasonable however No immediate drainage concerns. Four (4) green and two (2) amber waterway crossings (for waterway barrier works). Limited external works would be required to complete the link to an adequate standard. Crossing of waterways will increase construction costs. Relatively straight connection between Deepwater/Baffle Creek and Agnes Water Potential safety concerns associated with the substantial straight section, although sufficient sight distance exists. Wholly located in land that is controlled or owned by Council, being a combination of freehold land, road reserves and state reserve land (for which Council is trustee). 1 (North) Terrain is hilly. Design passes through the existing sewerage treatment plant, which could result in interface/safety There is the potential for conflicts to exist with existing Ergon Energy assets (subject to further investigation). Geotechnical material is solid and good foundation for road pavement. Notable earthworks are likely to be required given the terrain, with the use of significant retaining structures. No immediate drainage concerns. No waterway crossings (for waterway barrier works). External works would be required to complete the link to an adequate standard, particularly along Jobson Road. Construction costs would likely be high given the earthworks and retaining structures required. Relatively straight connection between Deepwater and Agnes Water. Wholly located in Lot 21 on SP168519, which is freehold land owned by Council. 2 (North) Terrain is hilly. Alignment passes to the east of the sewerage treatment plant. Limited conflict with existing Ergon Energy assets. Geotechnical material is solid and good foundation for road pavement. Earthworks would be notable given the terrain and would require significant retaining structures. No immediate drainage concerns. No waterway crossings (for waterway barrier works). External works would be required to complete the link to an adequate standard, particularly on Jobson Road. Construction costs are likely to be significant given the earthworks and retaining structures required. Relatively straight connection between Deepwater and Agnes Water. Wholly located in Lot 21 on SP168519, which is freehold land owned by Council.



Design Commentary Option Terrain is hilly. Alignment passes to the east of the sewerage treatment plant. Limited conflict with existing Ergon Energy assets. Geotechnical material is solid and good foundation for road pavement; Earthworks would be acceptable as this alignment uses the existing terrain to reduce the need for heavy structures. No immediate drainage concerns, although there will likely be a need for a moderate cross drainage structure towards the north. No waterway crossings (for waterway barrier works). Limited external works would be required to complete the link to an adequate standard. Anderson Way appears to be the most suitable tie in point for this standard of road. Construction costs are anticipated to be acceptable. Relatively straight connection between Deepwater and Agnes Water. No significant safety concerns based on the concept design. Wholly located in Lot 21 on SP168519, which is freehold land owned by Council. 2B Terrain is hilly. (North) Alignment passes to the east of the sewerage treatment plant. Limited conflict with existing Ergon Energy assets; Geotechnical material is solid and good foundation for road pavement. Notable earthworks are likely to be required given the terrain, with the use of significant retaining structures. No immediate drainage concerns. No waterway crossings (for waterway barrier works). External works would be required to complete the link to an adequate standard, particularly on Streeter Drive. Construction costs are likely to be high given the earthworks and retaining structures required. Relatively straight connection between Deepwater and Agnes Water. Wholly located in Lot 21 on SP168519, which is freehold land owned by Council. 3 (North) Terrain is generally flat / slightly graded with the exception of a mountainous section toward the northern end of the option. Limited conflict with existing Ergon Energy assets. Geotechnical material is solid and good foundation for road pavement. Earthworks are significant given the terrain and would require significant retaining structures. No immediate drainage concerns. No waterway crossings (for waterway barrier works). Limited external works would be required to complete the link to an adequate standard. Construction costs would be high given the earthworks and retaining structures required; Extensive cutting is required near the tie in point and poses safety concerns associated with batter protection and falling rocks. The northern section of Design Option 3 will require the use of a small portion of privately owned land (Lot 28 on RP619508) to facilitate the required connection to Rocky Crossing Road. The northern section of Design Option 3 is otherwise wholly located in freehold land that is owned by Council.



Design Commentary Option Terrain is generally flat / slightly graded. (North) Limited conflict with existing Ergon Energy assets. Geotechnical material is solid and good foundation for road pavement. Earthworks are acceptable given the terrain. No immediate drainage concerns. No waterway crossings (for waterway barrier works). Limited external works would be required to complete the link to an adequate standard. Construction costs would be acceptable. No significant safety concerns based on available information and concept design. The northern section of Design Option 3A will require the use of part of Deepwater National Park to facilitate the required connection to Rocky Crossing Road. The northern section of Design Option 3A is otherwise wholly located in freehold land that is owned by Council. Terrain is undulating consistent with a coastal dune environment. No known conflicts with existing utilities. Geotechnical material is poor with sandy foundation for road pavement. Substantial earthworks are required given the terrain, with significant retaining structures. No immediate drainage concerns. One (1) red waterway crossing (for waterway barrier works). Extensive external works would be required to complete the link to an adequate standard, particularly in relation to crossing Deepwater causeway, which could require heavy structural solutions. Construction costs would be high given the earthworks and retaining structures required. The extensive cutting poses safety concerns associated with batter protection and falling rocks. The interim alignment of Design Option 4 is based on an existing access track alignment and as such does not comply with any applicable standard. Use of this interim alignment may cause safety concerns and expose Council to liability issues, noting the substantial deficiencies. Both the interim and ultimate alignments for Design Option 4 are located in land that is not owned or controlled by Council. The majority of land to which Design Option 4 relates is the Deepwater National Park, which will require specific ownership and environmental investigations. Terrain is generally flat / slightly graded to undulating. Limited conflict with existing Ergon Energy assets. Geotechnical material is expected to be poor to average foundation for road pavement. Earthworks are acceptable given the terrain. No immediate drainage concerns. Five (5) green and one (1) amber waterway crossings (for waterway barrier works). Significant external works would be required to complete the link to an adequate standard. It is recommended the intersection with Uxbridge Road / Eurimbula Road / Round Hill Road be considered for upgrading as part of the project, to ensure ongoing safety. It is likely the intersection will require full upgrading (possibly a staggered T-intersection) with land resumptions to achieve a safe outcome. Construction costs may be considerable depending on design / public consultation. Wholly located within existing road reserves or Council controlled land.

Based on the initial assessment documented in Table 6-1, it is considered that Design Options 2, 2A, 3A, 4 and 5 represent preferred design options.



6.2 Stage 2 – Multiple Criteria Analysis

As discussed in Section 6.1, Stage 1 of the options analysis has identified Options 2, 2A, 3A, 4 and 5 to be preferred options, for which further analysis is required. As discussed in Section 3.4 of this report, a Multiple Criteria Analysis (MCA) has been employed for Stage 2 of the options analysis process, relating only to the preferred options, with the intent of identifying a recommended design option.

The following criteria have been used for the MCA.

- > **Opinion of Cost (Construction) Interim** relating to the construction cost of the interim road design, with a higher score indicating a lower cost option;
- > **Opinion of Cost (Construction) Ultimate** relating to the construction cost of the ultimate road design, with a higher score indicating a lower cost option;
- > **Opinion of Cost (Maintenance) Interim** relating to the cost of maintaining the interim road, with a higher score indicating a lower cost of maintenance;
- > **Opinion of Cost (Maintenance) Ultimate** relating to the cost of maintaining the ultimate road, with a higher score indicating a lower cost of maintenance;
- > **Ownership** relating to the relationship between the road design and the ownership of the land on which it is proposed, with a higher score indicating more appropriate land ownership;
- > **Environment** relating to the impact of the road design on the environment, with a higher score indicating a lesser relative environmental impact. The environment criteria has been separated into five sub-criteria relating to impacts on regulated vegetation, protected areas, waterways, wetlands and other matters;
- > **Connection (North)** relating to the suitability of the connection of the design option to the existing road network in the north of the study area, with a higher score indicating better suitability;
- > **Connection (South)** relating to the suitability of the connection of the design option to the existing road network in the south of the study area, with a higher score indicating better suitability;
- > **Serviceability** relating to the ability of the design option to achieve Council's objective for the project, being to provide a new road connecting Agnes Water to Baffle Creek;
- > **Travel Time** relating to the time taken to travel between Agnes Water and Baffle Creek using the design option at the achievable road speed, with a higher score indicating a quicker travel time;
- Potential Flood Impact relating to the extent to which the road design may be subject to flooding (subject to further detailed investigations), with a lower score indicating greater potential extent of flooding;
- > **Additional Works** relating to the need for additional works to be undertaken on the surrounding road network to support the road design, with a lower score indicating increased additional works;
- Social Impacts relating to the impact of the road design on social matters including amenity and recreational opportunities, with a lower score indicating greater social impact;
- > Safety relating to the safety of the road design, with a higher score indicating greater relative safety; and
- > **Existing Utilities Interface** relating to the interface of the road design with existing utility infrastructure, with a lower score indicating greater potential for conflict with services.

Table 6-2 documents the MCA undertaken in relation to the preferred design options. A 1 (worst) to 10 (best) rating system has been employed. Table 6-2 should be read in conjunction with the explanatory table provided in **Appendix F**, which provides further detail in relation to the methodology used to rate each of the design options. Where possible, quantitative data stemming from the technical assessments has been used to inform the scoring of each design option in the MCA.



Table 6-2 Multiple Criteria Analysis

Criteria	Weighting		D	Design Options			
		2	2A	3A	4	5	
Opinion of Cost (Construction) – Interim	10%	2	6	6	10	2	
Opinion of Cost (Construction) – Ultimate	10%	9	9	9	2	7	
Opinion of Cost (Maintenance) – Interim	2.5%	9	9	9	10	9	
Opinion of Cost (Maintenance) – Ultimate	2.5%	6	6	6	1	4	
Ownership	10%	8	8	3	0	9	
Environment - Regulated Vegetation	2%	7	7	7	7	1	
Environment - Protected Areas	3%	8	8	3	0	10	
Environment - Waterways	3%	2	2	2	7	3	
Environment - Wetlands	2%	3	3	3	6	8	
Environment - Other	2%	5	5	5	6	7	
Connection (North)	3%	4	7	3	8	5	
Connection (South)	3%	7	7	7	5	7	
Serviceability	5%	10	10	10	10	10	
Travel Time (Interim)	5%	6	6	6	6	2	
Travel Time (Ultimate)	5%	6	6	6	9	4	
Potential Flood Impact	5%	4	4	4	8	8	
Additional Works	4%	5	7	4	3	2	
Social Impacts	8%	5	7	7	3	8	
Safety	12%	6	8	8	3	4	
Existing Utilities Interface	3%	4	6	6	9	8	
Unweighted Total	200	116	131	114	113	118	
Weighted Total	10	5.95	6.98	6.09	5.10	5.84	

Note – Table 6-2 provides a summary of the MCA undertaken. Further detail is provided in the explanatory table in **Appendix F**.

6.3 Summary

The two-stage options analysis documented in this chapter identifies that Design Option 2A is the recommended design option, on the basis of a weighted total of 6.98 out of 10. The two-stage analysis process to arrive at the recommended design option is summarised in Figure 6-1.






Figure 6-1 Analysis Process



7 Conclusion and Recommendations

This report documents the design and analysis work undertaken by Cardno in relation to the Inland Link Road connecting Agnes Water and Baffle Creek. Work undertaken by Cardno comprises:

- > Preparation of concept designs for each of the design options, as discussed in Chapter 4 and presented in **Appendix A**;
- > Preparation of preliminary cost estimates for each design option, as presented in **Appendix B**;
- > Completion of technical assessments to inform the design and analysis work, as discussed in Chapter 5;
- > Completion of a two-stage analysis process to identify five preferred design options and a recommended design option, as discussed in Chapter 6; and
- > Ongoing consultation with Council throughout the project to inform the design and analysis work.

The report identifies that Design Option 2A is the recommended design option. On the basis of the design and analysis work undertaken, it is recommended that Council:

- > Complete a detailed review of the recommended design option;
- Complete further investigations, as required, to confirm the accuracy of currently available information, noting the present limitations and the most suitable road alignment and design. These may include, but not be limited to:
 - Detailed land survey of the corridor within which the recommended design option is to be located;
 - Environmental field assessment, to confirm the findings of the desktop assessment documented in this report (Table 5-4) and confirm approval requirements;
 - Detailed flood assessment, particularly relating to the recommended design option, to confirm requirements for waterway crossings and road levels; and
 - Detailed geotechnical investigations associated with the recommended design option, to confirm the required pavement design;
- Identify any instances where speed control measures may be required as part of the recommended design option to improve safety;
- > Undertake further internal consultation to identify any additional matters of technical consideration;
- Engage with various external stakeholders (as relevant) including (but not limited to) local land holders and the broader community, local businesses and tourism operators, the Department of Natural Resources and Mines (with respect to new road reserves and other titling matters), the Department of Environment and Science (where required in relation to the Deepwater National Park), the Department of the Environment and Energy (relating to the EPBC Act) and Ergon Energy (with respect to the relationship between the new road and existing electricity infrastructure);
- > Consider the co-location of telecommunications infrastructure in the road design if appropriate; and
- Progress with the detailed design of the proposed road, when appropriate, to allow for the accurate costing of the project.

APPENDIX

A

DESIGN OPTIONS





Cardno (Qld) Pty Ltd | ABN 57 051 074 992 101 High Street

North Rockhampton, QLD 4701 Tel: 07 4924 7500 Fax: 07 4926 4375

Web: www.cardno.com.au

© Cardno Limited All Rights Reserved. This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.


GLADSTONE REGIONAL COUNCIL

AGNES WATER AND BAFFLE CREEK INLAND LINK ROAD CONCEPT DESIGN

	SCHEDULE OF DRAWINGS
DRAWING No.	DESCRIPTION
R2018071-CI-000	COVER SHEET AND DRAWING SCHEDULE
R2018071-CI-001	CONCEPTUAL ALIGNMENTS
R2018071-CI-002	TYPICAL SECTIONS AND DETAILS SHEET 1 OF 2
R2018071-CI-003	TYPICAL SECTIONS AND DETAILS SHEET 2 OF 2
R2018071-CI-010	MAUDE HILL ROAD TO YABBY ROAD ALIGNMENT MCA0
R2018071-CI-011	LONGITUDINAL SECTION ALIGNMENT MCA0 - SHEET 1 OF 3
R2018071-CI-012	LONGITUDINAL SECTION ALIGNMENT MCA0 - SHEET 2 OF 3
R2018071-CI-013	LONGITUDINAL SECTION ALIGNMENT MCA0 - SHEET 3 OF 3
R2018071-CI-020	YABBY ROAD TO JOBSON ROAD VIA SEWERAGE TREATMENT PLANT CONNECTION OPTION 1 - ALIGNMENT MC01
R2018071-CI-021	LONGITUDINAL SECTION ALIGNMENT MC01 - SHEET 1 OF 2
R2018071-CI-022	LONGITUDINAL SECTION ALIGNMENT MC01 - SHEET 2 OF 2
R2018071-CI-030	YABBY ROAD TO JOBSON ROAD EASTERN CONNECTION OPTION 2 - ALIGNMENT MC02
R2018071-CI-031	LONGITUDINAL SECTION ALIGNMENT MC02 - SHEET 1 OF 2
R2018071-CI-032	LONGITUDINAL SECTION ALIGNMENT MC02 - SHEET 2 OF 2
R2018071-CI-033	YABBY ROAD TO JOBSON ROAD EASTERN CONNECTION OPTION 2A - ALIGNMENT MC02A
R2018071-CI-034	LONGITUDINAL SECTION ALIGNMENT MC02A - SHEET 1 OF 2
R2018071-CI-035	LONGITUDINAL SECTION ALIGNMENT MC02A - SHEET 2 OF 2
R2018071-CI-036	YABBY ROAD TO JOBSON ROAD EASTERN CONNECTION OPTION 2B - ALIGNMENT MC02B
R2018071-CI-037	LONGITUDINAL SECTION ALIGNMENT MC02B - SHEET 1 OF 2
R2018071-CI-038	LONGITUDINAL SECTION ALIGNMENT MC02B - SHEET 2 OF 2
R2018071-CI-040	YABBY ROAD TO ROCKY CONNECTION ROAD OPTION 3 - ALIGNMENT MC03
R2018071-CI-041	LONGITUDINAL SECTION ALIGNMENT MC03 - SHEET 1 OF 2
R2018071-CI-042	LONGITUDINAL SECTION ALIGNMENT MC03 - SHEET 2 OF 2
R2018071-CI-043	YABBY ROAD TO ROCKY CONNECTION ROAD OPTION 3A - ALIGNMENT MC03A
R2018071-CI-044	LONGITUDINAL SECTION ALIGNMENT MC03A - SHEET 1 OF 2
R2018071-CI-045	LONGITUDINAL SECTION ALIGNMENT MOSSA - SHEET 2 OF 2
R2018071-CI-050	DEEP WATER THROUGH NATIONAL PARK OPTION 4 (INTERIM) - ALIGNMENT MC04
R2018071-CI-051	LONGITUDINAL SECTION ALIGNMENT MC04 - SHEET 1 OF 4
R2018071-CI-052	LONGITUDINAL SECTION ALIGNMENT MC04 - SHEET 2 OF 4
R2018071-CI-053	LONGITUDINAL SECTION ALIGNMENT MO04 - SHEET 2 OF 4 LONGITUDINAL SECTION ALIGNMENT MC04 - SHEET 3 OF 4
R2018071-CI-054	LONGITUDINAL SECTION ALIGNMENT MO04 - SHEET 4 OF 4
R2018071-CI-055	DEEP WATER THROUGH NATIONAL PARK OPTION 4A (ULTIMATE) - ALIGNMENT MC04A
R2018071-CI-056	LONGITUDINAL SECTION ALIGNMENT MC04A - SHEET 1 OF 4
R2018071-CI-050	LONGITUDINAL SECTION ALIGNMENT MC04A - SHEET 1 OF 4 LONGITUDINAL SECTION ALIGNMENT MC04A - SHEET 2 OF 4
R2018071-CI-058	LONGITUDINAL SECTION ALIGNMENT MC04A - SHEET 4 OF 4
R2018071-CI-059	LONGITUDINAL SECTION ALIGNMENT MC04A - SHEET 4 OF 4
R2018071-CI-060	MAUDE HILL ROAD TO UXBRIDGE ROAD OPTION 5 - ALIGNMENT MC05
R2018071-CI-061	LONGITUDINAL SECTION ALIGNMENT MC05 - SHEET 1 OF 6
R2018071-CI-062	LONGITUDINAL SECTION ALIGNMENT MC05 - SHEET 2 OF 6
R2018071-CI-063	LONGITUDINAL SECTION ALIGNMENT MOSS - SHEET 3 OF 6
R2018071-CI-064	LONGITUDINAL SECTION ALIGNMENT MOSS - SHEET 4 OF 6
R2018071-CI-065	LONGITUDINAL SECTION ALIGNMENT MOSS - SHEET 5 OF 6
R2018071-CI-066	LONGITUDINAL SECTION ALIGNMENT MC05 - SHEET 6 OF 6

NORTH

⊏						
~ueen						
Ē						
5						
200						
k. rri ujecis loenina	2	1/03/2019	CONCEPT ALIGNMENTS COMBINED	GM	CF	CF
	1	14/02/2019	OPTION 4 REALIGNED TO SUIT EX TRACK	GM	CF	CF
ı rile.	0	31/01/2019	INITIAL ISSUE	GM	CF	CF
5	Ray	Date	Description	Des	\/orif	Annd







Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au

	Drawn		Client
	GDM	29/01/2019	
R	Checked	Date	Project
	Designed	Date	
	GDM	29/01/2019	
	Verified	Date	
			Title
	Approved		

" GLADSTONE REGIONAL COUNCIL					
i ^{ect} AGNES WATER AND BAFFLE CREEK INLAND LINK ROAD	Status NOT TO BE		IMINARY CONSTRUCTION)N PURP	
CONCEPT DESIGN	Zone:	Datum:	Scale	Size	
	56	AHD	1:20,000	A1	
CONCEPTUAL ALIGNMENTS	Drawing Numbe	Drawing Number			
CONCEPTUAL ALIGNIVIENTS	l F	R2018071-CI-001			









SCALE 1:40,000 CONCEPT ALIGNMENTS COMBINED GM CF CF 31/01/2019 INITIAL ISSUE Des. Verif. Appd. Date Description



Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au

Drawn GDM	Date 29/01/2019	Client GLADSTONE F
Checked	Date	Project AGNES WATER AND
Designed	Date	INLAND LINK ROAD
GDM	29/01/2019	CONCERT DECICAL
Verified	Date	CONCEPT DESIGN
		Title
Approved		1441 DE 1111 1 DOAD 7
		MAUDE HILL ROAD T
		ALIGNMENT MCA0

:	Client GLADSTONE REGIONAL COUNCI
	Project AGNES WATER AND BAFFLE CREEK
:	INLAND LINK ROAD
:	CONCEPT DESIGN
	Title
	MAUDE HILL ROAD TO YABBY ROAD

Status	PRELIN	MINARY		
NOT TO BE U	JSED FOR CO	ONSTRUCTION	N PUI	RPO
Zone:	Datum:	Scale	Size	
56	AHD	1:20,000		A1
Drawing Number				Revisi
R2	2018071-C	CI-010		1

DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE

POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;

OPERATIONAL SPEEDS: TBC;

• DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:

GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):

TABLE 4 - PERFORMANCE CRITERIA - RURAL AREAS (ROAD) - DISTRIBUTOR; AND TABLE 7 - ACCEPTABLE SOLUTIONS - RURAL AREAS (ROAD) - DISTRIBUTOR

AUSTROADS GUIDE TO ROAD DESIGN PART 3 - GEOMETRIC DESIGN, 2017;

•• IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);

DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');

APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

DESIGNER COMMENTARY:

THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR

CONSTRUCTION; AND

- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF

THE DETAIL DESIGN PHASE:


CONCEPT ALIGNMENTS COMBINED

Description

Des. Verif. Appd.

31/01/2019 | INITIAL ISSUE

Date



© Cardno Limited All Rights Reserved.

his document is produced by Cardno Limited solely for the

benefit of and use by the client in accordance with the

erms of the retainer. Cardno Limited does not and shall no

ssume any responsibility or liability whatsoever to any third

party arising out of any use or reliance by third party on the

content of this document.

Cardno®

Cardno (Qld) Pty Ltd | ABN 57 051 074 992

101 High Street

North Rockhampton, QLD 4701

Tel: 07 4924 7500 Fax: 07 4926 4375

Web: www.cardno.com.au

Designed GDM

Verified

Approved

Client GLADSTONE REGIONAL COUNCIL

PRELIMINARY

AHD AS SHOWN

A1

NOT TO BE USED FOR CONSTRUCTION PURPOSES

R2018071-CI-011

Project AGNES WATER AND BAFFLE CREEK

ALIGNMENT MCA0 - SHEET 1 OF 3

INLAND LINK ROAD

CONCEPT DESIGN

LONGITUDINAL SECTION

29/01/2019

DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE

POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;

OPERATIONAL SPEEDS: TBC;

• DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:

GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):

TABLE 4 - PERFORMANCE CRITERIA - RURAL AREAS (ROAD) - DISTRIBUTOR; AND TABLE 7 - ACCEPTABLE SOLUTIONS - RURAL AREAS (ROAD) - DISTRIBUTOR

AUSTROADS GUIDE TO ROAD DESIGN PART 3 - GEOMETRIC DESIGN, 2017;

IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);


DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');

•• APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED

SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR
- CONSTRUCTION; AND
- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE;



MCA0 SCALE: HORIZONTAL - 1:5000 VERTICAL - 1:500

nsl						
Queensl						
a Q						
Q:\Projects\Central						
ts/C						
ojects\Cen						
.\Pr						
	1		CONCEPT ALIGNMENTS COMBINED			
File:	0	31/01/2019	INITIAL ISSUE	GM	CF	CF
CAD F	Rev.	Date	Description	Des.	Verif.	Appd.

H:	0	100	200	300	400	500m
. ,		40	20	20	40	50
V:		10 H:1:5000 V:1:5	20 00	30	40	50m @A1




Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au

GDM 29/01/2019	Client GLADSTONE REGIONAL COUNCIL				
Checked Date Designed Date GDM 29/01/2019	Project AGNES WATER AND BAFFLE CREEK INLAND LINK ROAD	Status NOT TO BE		MINARY ONSTRUCTION	I PURPOS
Verified Date	CONCEPT DESIGN Title	Zone:	Datum:	Scale AS SHOWN	Size A1
Approved	LONGITUDINAL SECTION ALIGNMENT MCA0 - SHEET 2 OF 3	Drawing Number	2018071-0	CI-012	Revision 1

- DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE
- POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;
- OPERATIONAL SPEEDS: TBC;
- DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:
- •• GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):
 - TABLE 4 PERFORMANCE CRITERIA RURAL AREAS (ROAD) DISTRIBUTOR; AND
- TABLE 7 ACCEPTABLE SOLUTIONS RURAL AREAS (ROAD) DISTRIBUTOR
 AUSTROADS GUIDE TO ROAD DESIGN PART 3 GEOMETRIC DESIGN. 2017;
- •• IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);
- DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');
- •• APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR
- CONSTRUCTION; AND
- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE;



MCAO

SCALE: HORIZONTAL - 1:5000

VERTICAL - 1:500

1		CONCEPT ALIGNMENTS COMBINED			
0	31/01/2019	INITIAL ISSUE	GM	CF	CF
Rev.	Date	Description	Des.	Verif.	Appd.

H: () 100	200	300	400	500m
V: () 10 SCALE: H:1:5000 V	20	30	40	50m @A1

© Cardno Limited All Rights Reserved.

This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.




DAF WWBW CLASSIFIED GREEN

FISHWAY, APPROXIMATE

onaping and ratair
Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au

Drawn GDM	29/01/2019	Client GLADSTONE REGIONAL COUNCIL				
Checked	Date	Project AGNES WATER AND BAFFLE CREEK	Status	PRFLI	MINARY	
Designed GDM	Date 29/01/2019	INLAND LINK ROAD	NOT TO BE		ONSTRUCTION	I PURPOSI
Verified	Date	CONCEPT DESIGN Title	Zone: 56	Datum: AHD	Scale AS SHOWN	Size A1
Approved		LONGITUDINAL SECTION	Drawing Number			Revision
		ALIGNMENT MCA0 - SHEET 3 OF 3	R	2018071-0	CI-013	1





PLAN SCALE 1:40,000

0 1 2 3 4km SCALE 1:40,000 @A1 © Cardno Limited All Rights Reserved.

This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au

	Drawn GDM	Date 29/01/2019	Cli
R			
	Checked	Date	Pro
	Designed	Date	
	GDM	29/01/2019	
	Verified	Date	
			Titl
	Approved		

019	GLADSTONE REGIONAL COUNCIL
ate	Project AGNES WATER AND BAFFLE CREEK
ate 019	INLAND LINK ROAD
ate	CONCEPT DESIGN
	Title YABBY ROAD TO JOBSON ROAD
	VIA SEWERAGE TREATMENT PLANT CONNECTION

OPTION 1 - ALIGNMENT MC01

Status	PRFI IN	/INARY		
NOT TO BE U	JSED FOR CO	NSTRUCTIO	N PUI	RPOSES
Zone:	Datum:	Scale	Size	۸.4
56	AHD	1:20,000		A1
Drawing Number				Revision
R2	2018071-C	CI-020		1

DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE

POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;

OPERATIONAL SPEEDS: TBC;

DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:

• GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):

TABLE 4 - PERFORMANCE CRITERIA - RURAL AREAS (ROAD) - DISTRIBUTOR; AND TABLE 7 - ACCEPTABLE SOLUTIONS - RURAL AREAS (ROAD) - DISTRIBUTOR

AUSTROADS GUIDE TO ROAD DESIGN PART 3 - GEOMETRIC DESIGN, 2017;

■■ IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);

DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');

APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.


DESIGNER COMMENTARY:

THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR

CONSTRUCTION; AND

- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF

THE DETAIL DESIGN PHASE.



MC01 SCALE: HORIZONTAL - 1:5000 VERTICAL - 1:500

ns						
Queensl						
entr						
ts/C						
ojeci						
Q:\Projects\Central						
	1		CONCEPT ALIGNMENTS COMBINED			
File:	0	31/01/2019	INITIAL ISSUE	GM	CF	CF
CAD	Rev.	Date	Description	Des.	Verif.	Appd.

H:	0	100	200	300	400	500m
V:		10 H:1:5000 V:1:5	20	30	40	50m @A1




Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au

GDM 29/01/2						
Checked	Project AGNES WATER AND BAFFLE CREEK	Status	PRFLI	MINARY		
Designed 29/01/2	INLAND LINK ROAD	NOT TO BE I		ONSTRUCTION	N PUF	RPOSES
/erified	Title CONCEPT DESIGN	Zone: 56	Datum: AHD	Scale AS SHOWN	Size	A1
Approved	LONGITUDINAL SECTION	Drawing Number	7 11 12	7.0 0.101111		Revision
	ALIGNMENT MC01 SHEET 1 OF 2	R2	2018071-0	CI-021		1

- DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE
- POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;
- OPERATIONAL SPEEDS: TBC;
- DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:
- GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):
 - TABLE 4 PERFORMANCE CRITERIA RURAL AREAS (ROAD) DISTRIBUTOR; AND
- TABLE 7 ACCEPTABLE SOLUTIONS RURAL AREAS (ROAD) DISTRIBUTOR AUSTROADS GUIDE TO ROAD DESIGN PART 3 - GEOMETRIC DESIGN, 2017;
- IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);
- DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');
- APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED
- SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR
- CONSTRUCTION; AND
- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE.



31/01/2019 | INITIAL ISSUE Date Description Des. Verif. Appd.

© Cardno Limited All Rights Reserved. his document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall no assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

Cardno **Shaping the Future**

Cardno (Qld) Pty Ltd | ABN 57 051 074 992 101 High Street North Rockhampton, QLD 4701 Tel: 07 4924 7500 Fax: 07 4926 4375 Web: www.cardno.com.au

Drawn	Date	Clien
GDM	29/01/2019	
Checked	Date	Proje
Designed	Date	
GDM	29/01/2019	
Verified	Date	
		Title
Approved		

GLADSTONE REGIONAL COUNCIL pject AGNES WATER AND BAFFLE CREEK **PRELIMINARY** INLAND LINK ROAD NOT TO BE USED FOR CONSTRUCTION PURPOSES CONCEPT DESIGN AHD AS SHOWN LONGITUDINAL SECTION R2018071-CI-022 ALIGNMENT MC01 SHEET 2 OF 2

A1





CONCEPT ALIGNMENTS COMBINED 31/01/2019 INITIAL ISSUE GM CF CF Des. Verif. Appd. Description

SCALE 1:40,000



Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au

Cli
Pro
Titl

ate 119	Client	GLADSTONE REGIONAL COUNC
ate	Project	AGNES WATER AND BAFFLE CREEK
ate 119		INLAND LINK ROAD
ate		CONCEPT DESIGN
	Title	YABBY ROAD TO JOBSON ROAD
		EASTERN CONNECTION
		OPTION 2 - ALIGNMENT MC02

	Status		MINARY		
	NOT TO BE USED FOR CONSTRUCTION P				
	Zone:	Datum:	Scale	Size	
	56	AHD	1:20,000		A1
	Drawing Number				
R2018071-CI-030					
	•	•	*		

DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE

POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;

OPERATIONAL SPEEDS: TBC;

• DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:

GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):

TABLE 4 - PERFORMANCE CRITERIA - RURAL AREAS (ROAD) - DISTRIBUTOR; AND

TABLE 4 - PERFORMANCE CRITERIA - RURAL AREAS (ROAD) - DISTRIBUTOR; AND TABLE 7 - ACCEPTABLE SOLUTIONS - RURAL AREAS (ROAD) - DISTRIBUTOR

AUSTROADS GUIDE TO ROAD DESIGN PART 3 - GEOMETRIC DESIGN, 2017;

SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);
 DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');

APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED

DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR
- CONSTRUCTION; AND
- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE.

VERTICAL - 1:500


Des. Verif. Appd.

CONCEPT ALIGNMENTS COMBINED

Description

31/01/2019 | INITIAL ISSUE

Date



© Cardno Limited All Rights Reserved.

his document is produced by Cardno Limited solely for the

benefit of and use by the client in accordance with the

erms of the retainer. Cardno Limited does not and shall no

ssume any responsibility or liability whatsoever to any third

party arising out of any use or reliance by third party on the

content of this document.

Cardno

Cardno (Qld) Pty Ltd | ABN 57 051 074 992

101 High Street

North Rockhampton, QLD 4701

Tel: 07 4924 7500 Fax: 07 4926 4375

Web: www.cardno.com.au

Designed GDM

Verified

Approved

Client GLADSTONE REGIONAL COUNCIL

PRELIMINARY

AHD AS SHOWN

NOT TO BE USED FOR CONSTRUCTION PURPOSES

R2018071-CI-031

Project AGNES WATER AND BAFFLE CREEK

ALIGNMENT MC02 SHEET 1 OF 2

INLAND LINK ROAD

CONCEPT DESIGN

LONGITUDINAL SECTION

29/01/2019


- DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE
- POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;
- OPERATIONAL SPEEDS: TBC;
- DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:
- GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):

 TABLE 4 PERFORMANCE CRITERIA RURAL AREAS (ROAD) DISTRIBUTO
 - TABLE 4 PERFORMANCE CRITERIA RURAL AREAS (ROAD) DISTRIBUTOR; AND TABLE 7 ACCEPTABLE SOLUTIONS RURAL AREAS (ROAD) DISTRIBUTOR
- AUSTROADS GUIDE TO ROAD DESIGN PART 3 GEOMETRIC DESIGN, 2017;
- IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);
 DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');
- DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ("DAF WWBW"

 AND
- •• APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR
- CONSTRUCTION; AND
- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE.



MC02 SCALE: HORIZONTAL - 1:5000 VERTICAL - 1:500

nsl						
Queensl						
entr						
is/C						
Q:\Projects\Central						
<u>구</u>						
	1		CONCEPT ALIGNMENTS COMBINED			
rlle.	0	31/01/2019	INITIAL ISSUE	GM	CF	CF
CAD	Rev.	Date	Description	Des.	Verif.	Appd.


H: 0	100	200	300	400	500m
V: 0 SCALE	10 : H:1:5000 V:1:5	20 00	30	40	50m @A1



Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au

Orawn GDM	Date 29/01/2019	GLADSTONE REGIONAL COUNCIL					
Checked	Date	Project AGNES WATER AND BAFFLE CREEK	Status	PRFI II	MINARY		
Designed GDM	Date 29/01/2019		NOT TO BE I		ONSTRUCTION	N PUF	RPOSES
/erified	Date	CONCEPT DESIGN Title	Zone: 56	Datum: AHD	Scale AS SHOWN	Size	A1
Approved		LONGITUDINAL SECTION	Drawing Number	1	1.10 0.10 1.11		Revision
		ALIGNMENT MC02 - SHEET 2 OF 2	R2	2018071-0	CI-032		1





SCALE 1:40,000 INITIAL ISSUE Des. Verif. Appd. Description



Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au

1/03/2019	GLADSTONE REGIONAL COUNCIL					
Date Date 1/03/2019	Project AGNES WATER AND BAFFLE CREEK INLAND LINK ROAD	Status NOT TO BE U		MINARY DNSTRUCTION	N PUR	POSES
Date	CONCEPT DESIGN Title YABBY ROAD TO JOBSON ROAD	Zone: 56	Datum: AHD	Scale 1:40,000	Size <i>F</i>	41
	EASTERN CONNECTION OPTION 2A - ALIGNMENT MC02A	Drawing Number	2018071-0	CI-033	R	Revision 0

DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE

POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;

OPERATIONAL SPEEDS: TBC;

• DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:

GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):

TABLE 4 - PERFORMANCE CRITERIA - RURAL AREAS (ROAD) - DISTRIBUTOR; AND TABLE 7 - ACCEPTABLE SOLUTIONS - RURAL AREAS (ROAD) - DISTRIBUTOR

AUSTROADS GUIDE TO ROAD DESIGN PART 3 - GEOMETRIC DESIGN, 2017;

•• IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);

DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');

•• APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

DESIGNER COMMENTARY:


INITIAL ISSUE

Description

Des. Verif. Appd.

Date

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR
- CONSTRUCTION; AND
- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE.



© Cardno Limited All Rights Reserved.

his document is produced by Cardno Limited solely for the

benefit of and use by the client in accordance with the

erms of the retainer. Cardno Limited does not and shall no

ssume any responsibility or liability whatsoever to any third

party arising out of any use or reliance by third party on the

content of this document.

Cardno[®]

Cardno (Qld) Pty Ltd | ABN 57 051 074 992 101 High Street

North Rockhampton, QLD 4701

Tel: 07 4924 7500 Fax: 07 4926 4375

Web: www.cardno.com.au

Designed GDM

Verified

Approved

Client GLADSTONE REGIONAL COUNCIL

PRELIMINARY

AHD AS SHOWN

A1

NOT TO BE USED FOR CONSTRUCTION PURPOSES

R2018071-CI-034

Project AGNES WATER AND BAFFLE CREEK

ALIGNMENT MC02A - SHEET 1 OF 2

INLAND LINK ROAD

CONCEPT DESIGN


LONGITUDINAL SECTION

1/03/2019

- DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE
- POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;
- OPERATIONAL SPEEDS: TBC;
- DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:
- GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):
 - TABLE 4 PERFORMANCE CRITERIA RURAL AREAS (ROAD) DISTRIBUTOR; AND TABLE 7 ACCEPTABLE SOLUTIONS RURAL AREAS (ROAD) DISTRIBUTOR
- AUSTROADS GUIDE TO ROAD DESIGN PART 3 GEOMETRIC DESIGN, 2017;
- •• IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);
- DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');
- •• APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR
- CONSTRUCTION; AND
- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE.



MC02A SCALE: HORIZONTAL - 1:5000 VERTICAL - 1:500

nsle						
Queensla						
Q:\Projects\Central						
ts/C						
ojeć						
<u>ڄ</u>						
) FIIE:	0		INITIAL ISSUE	GM		
3	Rev.	Date	Description	Des.	Verif.	Appd.


H: 0	100	200	300	400	500m
V: 0 SCALE	10 : H:1:5000 V:1:5	20 00	30	40	50m @A1



Cardno (Qld) Pty Ltd ABN 57 051 074 992	
101 High Street	
North Rockhampton, QLD 4701	
Tel: 07 4924 7500 Fax: 07 4926 4375	
Web: www.cardno.com.au	

Date Client GLADSTONE REGIONAL COUNCIL Client GLADSTONE REGIONAL COUNCIL	
Project AGNES WATER AND BAFFLE CREEK Status PRELIMINARY	
Date DM 1/03/2019 INLAND LINK ROAD NOT TO BE USED FOR CONSTRUCTION PUR	RPOSE
ified Date CONCEPT DESIGN Zone: Datum: Scale Size	A1
	Revision
ALIGNMENT MC02A - SHEET 2 OF 2 R2018071-CI-035	0





SCALE 1:40,000 GM INITIAL ISSUE Des. Verif. Appd. Description



Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au

1/03/2019	Client GLADSTONE REGIONAL COUNCIL				
red Date	Project AGNES WATER AND BAFFLE CREEK	Status	PRELI	MINARY	
ned Date // 1/03/2019	INLAND LINK ROAD		E USED FOR C		N PURPOSES
od Date	CONCEPT DESIGN Title YABBY ROAD TO JOBSON ROAD	Zone: 56	Datum: AHD	Scale 1:40,000	Size A1
ved	EASTERN CONNECTION	Drawing Number	er	·	Revision
	OPTION 2B - ALIGNMENT MC02B	F	R2018071-0	CI-036	0

- DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE
- POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;
- OPERATIONAL SPEEDS: TBC;
- DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:
- GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):
 - TABLE 4 PERFORMANCE CRITERIA RURAL AREAS (ROAD) DISTRIBUTOR; AND TABLE 7 ACCEPTABLE SOLUTIONS RURAL AREAS (ROAD) DISTRIBUTOR
- AUSTROADS GUIDE TO ROAD DESIGN PART 3 GEOMETRIC DESIGN, 2017;
- •• IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);
- •• DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');
- •• APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR
- CONSTRUCTION; AND

INITIAL ISSUE

Description


Date

THE DETAIL DESIGN PHASE.

- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF

VERTICAL - 1:500

Des. Verif. Appd.



© Cardno Limited All Rights Reserved.

his document is produced by Cardno Limited solely for the

benefit of and use by the client in accordance with the

erms of the retainer. Cardno Limited does not and shall no

ssume any responsibility or liability whatsoever to any third

party arising out of any use or reliance by third party on the

content of this document.

Cardno®

Cardno (Qld) Pty Ltd | ABN 57 051 074 992

101 High Street

North Rockhampton, QLD 4701

Tel: 07 4924 7500 Fax: 07 4926 4375

Web: www.cardno.com.au

Designed GDM

Verified

Approved

Client GLADSTONE REGIONAL COUNCIL

PRELIMINARY

AHD AS SHOWN

A1

NOT TO BE USED FOR CONSTRUCTION PURPOSES

R2018071-CI-037

Project AGNES WATER AND BAFFLE CREEK

ALIGNMENT MC02B - SHEET 1 OF 2

INLAND LINK ROAD

CONCEPT DESIGN

LONGITUDINAL SECTION

1/03/2019

• DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE

POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;

OPERATIONAL SPEEDS: TBC;

DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:

GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31): TABLE 4 - PERFORMANCE CRITERIA - RURAL AREAS (ROAD) - DISTRIBUTOR; AND

TABLE 7 - ACCEPTABLE SOLUTIONS - RURAL AREAS (ROAD) - DISTRIBUTOR

AUSTROADS GUIDE TO ROAD DESIGN PART 3 - GEOMETRIC DESIGN, 2017;

IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY); DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');


APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

DESIGNER COMMENTARY:

THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR

CONSTRUCTION; AND

- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE.



SCALE: HORIZONTAL - 1:5000 VERTICAL - 1:500

nsl						
Queensk						
_a.cb_coo						
ts/C						
- '- ojeci						
P. P.						
? [[]	0		INITIAL ISSUE	GM		
CAD	Rev.	Date	Description	Des.	Verif.	Appd.

H: 0	100	200	300	400	500n
V: 0 SCALE	10 : H:1:5000 V:1:5	20 500	30	40	50m @A1

© Cardno Limited All Rights Reserved. This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



Designed GDM


Verified

Approved

3 and 1 and 1
Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au

1/03/2019	Client	GLADSTONE REGIONAL COUNCIL					
Date 1/03/2019	Project	AGNES WATER AND BAFFLE CREEK INLAND LINK ROAD CONCEPT DESIGN	Status NOT TO BE		VINARY ONSTRUCTION Scale	N PU	RPOSE
Date	Title	OCHOLI I BLOIGH	56	AHD	AS SHOWN	Size	A1
		LONGITUDINAL SECTION ALIGNMENT MC02B - SHEET 2 OF 2	Drawing Number R2	2018071-0	CI-038		Revision 0





PLAN SCALE 1:40,000

CONCEPT ALIGNMENTS COMBINED GM CF CF 31/01/2019 INITIAL ISSUE Des. Verif. Appd. Date Description

SCALE 1:40,000



Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au

	Drawn GDM	Date 29/01/2019	Client
D	Checked	Date	Projec
	Designed GDM	Date 29/01/2019	
	Verified	Date	Title
	Approved		

ate 19	Client GLADSTONE REGIONAL COUNCIL
ate	Project AGNES WATER AND BAFFLE CREEK
ate 19	INLAND LINK ROAD
ate	CONCEPT DESIGN
	Title
	YABBY ROAD TO ROCKY CONNECTION ROAD
	OPTION 3 - ALIGNMENT MC03

Status	PRELIN	MINARY			
NOT TO BE U	JSED FOR CO		N PUI	RPOSE	
Zone:	Datum:	Scale	Size		
56	AHD	1:40,000		A1	
Drawing Number					
R2	2018071-C	CI-040		1	

- DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE
- POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;
- OPERATIONAL SPEEDS: TBC;
- DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:
- GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):
 - TABLE 4 PERFORMANCE CRITERIA RURAL AREAS (ROAD) DISTRIBUTOR; AND
 - TABLE 7 ACCEPTABLE SOLUTIONS RURAL AREAS (ROAD) DISTRIBUTOR
- AUSTROADS GUIDE TO ROAD DESIGN PART 3 GEOMETRIC DESIGN, 2017;
- •• IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);
- •• DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');
- •• APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR
- CONSTRUCTION; AND
- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE.

VERTICAL - 1:500


Des. Verif. Appd.

CONCEPT ALIGNMENTS COMBINED

Description

31/01/2019 | INITIAL ISSUE

Date



© Cardno Limited All Rights Reserved.

his document is produced by Cardno Limited solely for the

benefit of and use by the client in accordance with the

erms of the retainer. Cardno Limited does not and shall no

ssume any responsibility or liability whatsoever to any third

party arising out of any use or reliance by third party on the

content of this document.

Cardno®

Cardno (Qld) Pty Ltd | ABN 57 051 074 992

101 High Street

North Rockhampton, QLD 4701

Tel: 07 4924 7500 Fax: 07 4926 4375

Web: www.cardno.com.au

Designed GDM

Verified

Approved

Client GLADSTONE REGIONAL COUNCIL

PRELIMINARY

AHD AS SHOWN

NOT TO BE USED FOR CONSTRUCTION PURPOSES

R2018071-CI-041

Project AGNES WATER AND BAFFLE CREEK

ALIGNMENT MC03 - SHEET 1 OF 2

INLAND LINK ROAD

CONCEPT DESIGN

LONGITUDINAL SECTION

29/01/2019

DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE

POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;

OPERATIONAL SPEEDS: TBC;

• DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:

GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):

TABLE 4 - PERFORMANCE CRITERIA - RURAL AREAS (ROAD) - DISTRIBUTOR; AND

TABLE 7 - ACCEPTABLE SOLUTIONS - RURAL AREAS (ROAD) - DISTRIBUTOR AUSTROADS GUIDE TO ROAD DESIGN PART 3 - GEOMETRIC DESIGN, 2017;


•• IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);

DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');
 AND

•• APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR
- CONSTRUCTION; AND
- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE.



MC03 SCALE: HORIZONTAL - 1:5000 VERTICAL - 1:500

nsl						
Queensl						
entr						
ts/C						
Q:\Projects\Central						
<u>ਜ</u> ਼						
	1		CONCEPT ALIGNMENTS COMBINED			
) FIIE:	0	31/01/2019	INITIAL ISSUE	GM	CF	CF
CAD	Rev.	Date	Description	Des.	Verif.	Appd.

H: 0	1	00	200	300	400	500m
V: 0 S0	CALE: H:1:50	10 00 V:1:500	20	30	40	50m @A1



Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au

	/2019	GLADSTONE REGIONAL COUNCIL					
Checked	Date	Project AGNES WATER AND BAFFLE CREEK	Status	PRFLI	MINARY		
Designed	Date /2019	INLAND LINK ROAD	NOT TO BE		ONSTRUCTIO	N PUI	RPOSE
Verified	Date	CONCEPT DESIGN Title	Zone: 56	Datum: AHD	Scale AS SHOWN	Size	A1
Approved		LONGITUDINAL SECTION	Drawing Number		710 01101111		Revision
		ALIGNMENT MC03 - SHEET 2 OF 2	F	R2018071-	CI-042		1





SCALE 1:40,000 INITIAL ISSUE Des. Verif. Appd. Description



Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au


wn DM	1/03/2019	Client GLADSTONE REGIONAL COUN
cked	Date	Project AGNES WATER AND BAFFLE CREEK
igned DM	Date 1/03/2019	INLAND LINK ROAD
fied	Date	CONCEPT DESIGN
may and		Title
roved		YABBY ROAD TO ROCKY CONNECTION ROA OPTION 3A - ALIGNMENT MC03A

Status	PRFI IN	MINARY	
NOT TO BE	USED FOR CO		N PURPOS
Zone:	Datum:	Scale	Size
56	AHD	1:40,000	A1
Drawing Number			Revision
R2	2018071-C	CI-043	0

- DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE
- POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;
- OPERATIONAL SPEEDS: TBC;
- DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING CHIRELINES
- DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:
 GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):
 - TABLE 4 PERFORMANCE CRITERIA RURAL AREAS (ROAD) DISTRIBUTOR; AND
- TABLE 7 ACCEPTABLE SOLUTIONS RURAL AREAS (ROAD) DISTRIBUTOR AUSTROADS GUIDE TO ROAD DESIGN PART 3 GEOMETRIC DESIGN, 2017;
- •• IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);
- DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');
- AND
 ADDLICABLE CARRICORN MUNICIPAL DEVELOPMENT CLUDELINE STANK
- •• APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR
- CONSTRUCTION; AND
- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE.



MC03A SCALE: HORIZONTAL - 1:5000 VERTICAL - 1:500

0		INITIAL ISSUE	GM		
Rev.	Date	Description	Des.	Verif.	Appd.

H:	0	100	200	300	400	500m
. ,		40	20	20	40	50
V:		10 H:1:5000 V:1:5	20 00	30	40	50m @A1




Cardno (Qld) Pty Ltd ABN 57 051 074 9	92
101 High Street	
North Rockhampton, QLD 4701	
Tel: 07 4924 7500 Fax: 07 4926 4375	
Web: www.cardno.com.au	

ı	GDM 1/03/2019	GLADSTONE REGIONAL COUNCIL					
ı	Checked Date	Project AGNES WATER AND BAFFLE CREEK	Status	PRFLII	MINARY		
	Designed Date GDM 1/03/2019	INLAND LINK ROAD	NOT TO BE	USED FOR CO		N PURF	POSES
	Verified Date	CONCEPT DESIGN Title	Zone: 56	Datum: AHD	Scale AS SHOWN	Size A	\1
	Approved	LONGITUDINAL SECTION	Drawing Number			Re	Revision
		ALIGNMENT MC03A - SHEET 1 OF 2	<u> </u>	2018071-0	1-U44 		U

- DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE
- POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;
- OPERATIONAL SPEEDS: TBC;
- DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:
- GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):
 - TABLE 4 PERFORMANCE CRITERIA RURAL AREAS (ROAD) DISTRIBUTOR; AND
- TABLE 7 ACCEPTABLE SOLUTIONS RURAL AREAS (ROAD) DISTRIBUTOR
- AUSTROADS GUIDE TO ROAD DESIGN PART 3 GEOMETRIC DESIGN, 2017; IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);
- DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');
- APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR
- CONSTRUCTION; AND
- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE.



MC03A SCALE: HORIZONTAL - 1:5000 VERTICAL - 1:500

0 INITIAL ISSUE GM

H: 0	100	200	300	400	500m
V: 0 SCALE:	10 H:1:5000 V:1:5	20	30	40	50m @A1

© Cardno Limited All Rights Reserved. his document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.




Cardno (Qld) Pty Ltd ABN 57 051 074 992	
101 High Street	
North Rockhampton, QLD 4701	
Tel: 07 4924 7500 Fax: 07 4926 4375	
Web: www.cardno.com.au	

rawn GDM	1/03/2019		DSTONE REC						
hecked	Date	Project AGNE	S WATER AND BAF	FLE CREEK	Status	PRFLI	MINARY		
esigned GDM	Date 1/03/2019		D LINK ROAD		NOT TO BE		ONSTRUCTION	N PUF	RPOSES
erified	Date	Title	EPT DESIGN		Zone: 56	Datum: AHD	Scale AS SHOWN	Size	A1
pproved			ITUDINAL SECTION	ı	Drawing Number	,	7.0 0.151111		Revision
			MENT MC03A - SH		R	2018071-	CI-045		0







© Cardno Limited All Rights Reserved.

This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

Carcino

Brawn
GDM
Checked

Checked Cardno (Qld) P

Shaping the Future	Designed GDM	29/0 ⁻
Cardno (Qld) Pty Ltd ABN 57 051 074 992	Verified	
101 High Street North Rockhampton, QLD 4701	Approved	
Tel: 07 4924 7500 Fax: 07 4926 4375 Web: www.cardno.com.au		

019	GLADSTONE REGIONAL COUNCIL	
ate	Project AGNES WATER AND BAFFLE CREEK	
ate 019	INLAND LINK ROAD	
ate	CONCEPT DESIGN	
	Title	
	DEEP WATER THROUGH NATIONAL PARK	
	OPTION 4 - ALIGNMENT MC04	

Status NOT TO BE U		MINARY DNSTRUCTION	N PU	RPO\$
Zone: 56	Datum: AHD	Scale 1:40,000	Size	A1
Drawing Number				Revision
R2	2018071-C	CI-050		1

CONCEPT ALIGNMENTS COMBINED

Description

31/01/2019 INITIAL ISSUE

GM CF CF

Des. Verif. Appd.

DESIGN DETAILS: • DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD; OPERATIONAL SPEEDS: TBC; DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES: GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31): TABLE 4 - PERFORMANCE CRITERIA - RURAL AREAS (ROAD) - DISTRIBUTOR; AND TABLE 7 - ACCEPTABLE SOLUTIONS - RURAL AREAS (ROAD) - DISTRIBUTOR AUSTROADS GUIDE TO ROAD DESIGN PART 3 - GEOMETRIC DESIGN, 2017: IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY); DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW'); APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS. **DESIGNER COMMENTARY:** THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR CONSTRUCTION; AND EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE. DESIGN SURFACE EXISTING SURFACE JOIN NEATLY AND SMOOTHLY TO EXISTING SPRINGS / ROCKY POINT ROAD FORMATION. Vertical Curve Length (m) Vertical Curve Radius (m) Vertical Geometry Grade (%) Vertical Geometry Length (m) Horizontal Curve Length (m) Horizontal Curve Radius (m) DATUM RL -25.000 CUT / FILL DEPTH 0.424 0.473 0.536 0.428 0.464 0.444 0.407 0.475 0.496 0.437 0.297 0.51 0.459 0.462 0.45 0.497 0.295 0.501 0.482 0.297 0.572 0.399 0.792 TO EXISTING SURFACE EXISTING SURFACE 17.643 16.674 16.490 17.420 19.228 16.784 16.643 16.767 18.687 18.260 16.364 17.510 18.517 19.052 17.510 16.925 16.507 LEVELS DESIGN LEVELS 17.235 17.422 19.665 16.900 17.939 18.981 19.514 17.954 17.828 16.177 16.938 16.906 18.756 19.111 ROAD CENTRELINE 1896.643 1300.000 1000.000 1688.810 670.895 693.508 700.000 400.000 775.176 800.000 823.538 CONTROL LINE CHAINAGE 900.000 88.426 100.000 ROAD CENTRELINE SUPER ELEVATION MC04 SCALE: HORIZONTAL - 1:5000 " GLADSTONE REGIONAL COUNCIL **Cardno**® © Cardno Limited All Rights Reserved. roject AGNES WATER AND BAFFLE CREEK **PRELIMINARY** his document is produced by Cardno Limited solely for the Designed GDM INLAND LINK ROAD benefit of and use by the client in accordance with the NOT TO BE USED FOR CONSTRUCTION PURPOSES 29/01/2019 CONCEPT DESIGN erms of the retainer. Cardno Limited does not and shall no Cardno (Qld) Pty Ltd | ABN 57 051 074 992 101 High Street ssume any responsibility or liability whatsoever to any third AHD AS SHOWN A1 party arising out of any use or reliance by third party on the CONCEPT ALIGNMENTS COMBINED North Rockhampton, QLD 4701 content of this document. LONGITUDINAL SECTION 31/01/2019 | INITIAL ISSUE Tel: 07 4924 7500 Fax: 07 4926 4375 R2018071-CI-051 ALIGNMENT MC04 - SHEET 1 OF 5 Web: www.cardno.com.au Date Des. Verif. Appd. Description

DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE

POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;

OPERATIONAL SPEEDS: TBC;

• DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:

GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):

TABLE 4 - PERFORMANCE CRITERIA - RURAL AREAS (ROAD) - DISTRIBUTOR; AND TABLE 7 - ACCEPTABLE SOLUTIONS - RURAL AREAS (ROAD) - DISTRIBUTOR

AUSTROADS GUIDE TO ROAD DESIGN PART 3 - GEOMETRIC DESIGN, 2017;


• IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);

DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');

•• APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR
- CONSTRUCTION; AND
- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE.



MC04 SCALE: HORIZONTAL - 1:5000 VERTICAL - 1:500

nsl						
Queensl						
entral						
cts/C						
ojec						
ڄ						
9 S	1		CONCEPT ALIGNMENTS COMBINED			
) FIIE	0	31/01/2019	INITIAL ISSUE	GM	CF	CF
CAD	Rev.	Date	Description	Des.	Verif.	Appd.

H:	0	100	200	300	400	500m
V:	0 SCALE:	10 H:1:5000 V:1:5	20	30	40	50m @A1

Cardno [®] Shaping the Future
O (OU) By (U) ABN 57 054 074 000

Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au

Drawn GDM	29/01/2019	GLADSTONE REGIONAL COUNCIL					
Checked	Date	Project AGNES WATER AND BAFFLE CREEK	Status	PRFLI	MINARY		
Designed GDM	Date 29/01/2019	INLAND LINK ROAD	NOT TO BE		ONSTRUCTION	PURPOSI	
Verified	Date	CONCEPT DESIGN Title	Zone: 56	Datum: AHD	Scale SHOWN	Size A1	
Approved		LONGITUDINAL SECTION	Drawing Number		<u> </u>	Revision	
		ALIGNMENT MC04 - SHEET 2 OF 5		R2018071-CI-052			

DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE

POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;

OPERATIONAL SPEEDS: TBC;

DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:

GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):

TABLE 4 - PERFORMANCE CRITERIA - RURAL AREAS (ROAD) - DISTRIBUTOR; AND

TABLE 7 - ACCEPTABLE SOLUTIONS - RURAL AREAS (ROAD) - DISTRIBUTOR AUSTROADS GUIDE TO ROAD DESIGN PART 3 - GEOMETRIC DESIGN, 2017;

PWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);

• DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');

•• APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.


DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR

CONSTRUCTION; AND

- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF

THE DETAIL DESIGN PHASE.



MC04 SCALE: HORIZONTAL - 1:5000 VERTICAL - 1:500

Queensl						
nee						
d. NPI ojecis/Central						
5						
3						
-						
	1		CONCEPT ALIGNMENTS COMBINED			
	0	31/01/2019	INITIAL ISSUE	GM	CF	CF
)	Rev.	Date	Description	Des.	Verif.	Appd.

H: (0	100	200	300	400	500m
ŀ						
V: (10 H:1:5000 V:1:5	20	30	40	50m @A1

© Cardno Limited All Rights Reserved.

This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



Designed GDM

Verified

Approved

Cardno (Qld) Pty Ltd ABN 57 051 074 9	92
101 High Street	
North Rockhampton, QLD 4701	
Tel: 07 4924 7500 Fax: 07 4926 4375	
Web: www.cardno.com.au	

29/01/2019	GLADSTONE REGIONAL COUNCIL					
Date	Project AGNES WATER AND BAFFLE CREEK INLAND LINK ROAD CONCEPT DESIGN	Status NOT TO BE Zone:		VINARY ONSTRUCTION Scale	N PUR	RPOSE
Date	Title	56	AHD	AS SHOWN		A1
	LONGITUDINAL SECTION ALIGNMENT MC04 - SHEET 3 OF 5	Drawing Number	2018071-0	CI-053		Revision
		•			·	

DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE
NOTED:

POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;

OPERATIONAL SPEEDS: TBC;

DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:

GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):

TABLE 4 - PERFORMANCE CRITERIA - RURAL AREAS (ROAD) - DISTRIBUTOR; AND TABLE 7 - ACCEPTABLE SOLUTIONS - RURAL AREAS (ROAD) - DISTRIBUTOR

AUSTROADS GUIDE TO ROAD DESIGN PART 3 - GEOMETRIC DESIGN, 2017;

IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);

PERAPTMENT OF A CRICK II TURE AND FIGURERIES CHIRELINES FOR WATERWAY BARRIED WORKS (IDAE WATER)

PERAPTMENT OF A CRICK II TURE AND FIGURERIES CHIRELINES FOR WATERWAY BARRIED WORKS (IDAE WATER)

PERAPTMENT OF A CRICK II TURE AND FIGURERIES CHIRELINES FOR WATERWAY BARRIED WORKS (IDAE WATER)

PROPERTY OF A CRICK II TURE AND FIGURERIES CHIRELINES FOR WATERWAY BARRIED WORKS (IDAE WATER)

PROPERTY OF A CRICK II TURE AND FIGURERIES CHIRELINES FOR WATERWAY BARRIED WORKS (IDAE WATER)

PROPERTY OF A CRICK II TURE AND FIGURERIES CHIRELINES FOR WATERWAY BARRIED WORKS (IDAE WATER)

PROPERTY OF A CRICK II TURE AND FIGURERIES CHIRELINES FOR WATER WATER

•• DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');

•• APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR

CONSTRUCTION; AND

- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE.

EXISTING SURFACE TIE INTO EXISTING DAF WWBW CLASSIFIED RED DESIGN SURFACE TRACK FORMATION. FISHWAY. APPROXIMATE LOCATION ONLY. Vertical Curve Length (m) Vertical Curve Radius (m) Vertical Geometry Grade (%) Vertical Geometry Length (m) Horizontal Curve Length (m) Horizontal Curve Radius (m) DATUM RL -30.000 CUT / FILL DEPTH 0.449 0.3 0.454 0.617 0.575 TO EXISTING SURFACE EXISTING SURFACE 20.099 13.579 18.425 18.868 10.722 10.694 LEVELS DESIGN LEVELS 19.043 19.168 19.045 155 ROAD CENTRELINE 14. CONTROL LINE CHAINAGE 9488. ROAD CENTRELINE SUPER ELEVATION LHS and RHS -3%

> MC04 SCALE: HORIZONTAL - 1:5000 VERTICAL - 1:500

Queensl						
nee						
a. i. rejecter commen						
2						
	1		CONCEPT ALIGNMENTS COMBINED			
	0	31/01/2019	INITIAL ISSUE	GM	CF	CF
	Rev.	Date	Description	Des.	Verif.	Appd.


H: 0	100	200	300	400	500n
V: 0	10	20	30	40	50m
SCALE	:: H:1:5000 V:1:5	00			@A1



Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au

Drawn GDM	29/01/2019	Client GLADSTONE REGIONAL COUNCIL					
Checked	Date	Project AGNES WATER AND BAFFLE CREEK	Status	PRFL	IMINARY	<u>, </u>	
Designed GDM	Date 29/01/2019	INLAND LINK ROAD	NOT TO B		CONSTRUCTION	PURPOSE	
Verified	Date	CONCEPT DESIGN Title	Zone: 56	Datum: AHD	Scale SHOWN	Size A1	
Approved		LONGITUDINAL SECTION	Drawing Numb	er		Revision	
		ALIGNMENT MC04 - SHEET 4 OF 5		R2018071-CI-054			





PLAN SCALE 1:40,000

CONCEPT ALIGNMENTS COMBINED GM CF CF 31/01/2019 INITIAL ISSUE Des. Verif. Appd. Description

SCALE 1:40,000



0 1 (01) 5(1) 1 1 1 1 5 1 5 1 6 1 6 1 6 1	
Cardno (Qld) Pty Ltd ABN 57 051 074 992	
101 High Street	
North Rockhampton, QLD 4701	
Tel: 07 4924 7500 Fax: 07 4926 4375	
Web: www.cardno.com.au	

rawn GDM	29/01/2019	GLADSTONE REGIONAL COUNCIL	
hecked	Date	Project AGNES WATER AND BAFFLE CREEK	S
esigned GDM	Date 29/01/2019	INLAND LINK ROAD	I
erified	Date	CONCEPT DESIGN	Z
		Title	L
oproved		LONGITUDINAL SECTION	
		ALIGNMENT MC04 - SHEET 5 OF 5	

SIONAL COUNCIL							
FLE CREEK	PRELIMINARY NOT TO BE USED FOR CONSTRUCTION PURPOS						
	Zone:	Datum:	Scale	Size			
	56	AHD	AS SHOWN		A1		
1	Drawing Number				Revision		
ET 5 OF 5	R2	2018071-C	CI-055		1		

DESIGN DETAILS: DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD; OPERATIONAL SPEEDS: TBC; DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES: GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31): TABLE 4 - PERFORMANCE CRITERIA - RURAL AREAS (ROAD) - DISTRIBUTOR; AND TABLE 7 - ACCEPTABLE SOLUTIONS - RURAL AREAS (ROAD) - DISTRIBUTOR AUSTROADS GUIDE TO ROAD DESIGN PART 3 - GEOMETRIC DESIGN, 2017; IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY); DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW'); APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS. **DESIGNER COMMENTARY:** THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR CONSTRUCTION; AND - EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE. EXISTING SURFACE DESIGN SURFACE JOIN NEATLY AND SMOOTHLY TO EXISTING SPRINGS / ROCKY POINT ROAD FORMATION. 640.223m Vertical Curve Length (m) Vertical Curve Radius (m) R 9000m Vertical Geometry Grade (%) Vertical Geometry Length (m) 0.919% 5.363% -1.75% 0.212% -0.066% 200m 367.339m 432.661m Horizontal Curve Length (m) 302.848m 1184.76m 1241.186m Horizontal Curve Radius (m) R 1100m R -1100m R 1100m DATUM RL -23.000 CUT / FILL DEPTH -5.7 0-0-TO EXISTING SURFACE 0 0 EXISTING SURFACE 19.843 .712 .816 .623 18.796 LEVELS 60. DESIGN LEVELS 18.700 ROAD CENTRELINE 9 6 6 2252.453 2281.604 2300.000 392.022 400.000 CONTROL LINE CHAINAGE 89.175 1300. ROAD CENTRELINE SUPER ELEVATION LHS and RHS -3% MC04A SCALE: HORIZONTAL - 1:5000 VERTICAL - 1:500 Client GLADSTONE REGIONAL COUNCIL **Cardno**® © Cardno Limited All Rights Reserved. Project AGNES WATER AND BAFFLE CREEK his document is produced by Cardno Limited solely for the Designed GDM INLAND LINK ROAD benefit of and use by the client in accordance with the 1/03/2019 CONCEPT DESIGN erms of the retainer. Cardno Limited does not and shall no Verified Date Cardno (Qld) Pty Ltd | ABN 57 051 074 992 101 High Street ssume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the Approved North Rockhampton, QLD 4701 content of this document. LONGITUDINAL SECTION INITIAL ISSUE Tel: 07 4924 7500 Fax: 07 4926 4375 ALIGNMENT MC04A - SHEET 1 OF 4 Web: www.cardno.com.au Date Description Des. Verif. Appd.

1.48%

485.714m

60.

PRELIMINARY

AHD AS SHOWN

A1

NOT TO BE USED FOR CONSTRUCTION PURPOSES

R2018071-CI-056

• DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE

POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;

OPERATIONAL SPEEDS: TBC;

DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:

GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):

TABLE 4 - PERFORMANCE CRITERIA - RURAL AREAS (ROAD) - DISTRIBUTOR; AND TABLE 7 - ACCEPTABLE SOLUTIONS - RURAL AREAS (ROAD) - DISTRIBUTOR

AUSTROADS GUIDE TO ROAD DESIGN PART 3 - GEOMETRIC DESIGN, 2017;


•• IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);

•• DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');

APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR
- CONSTRUCTION; AND
- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE.



MC04A SCALE: HORIZONTAL - 1:5000 VERTICAL - 1:500

0		INITIAL ISSUE	GM		
Rev.	Date	Description	Des.	Verif.	Appd.

H: 0	100	200	300	400	500m
V: 0 SCALE	10 : H:1:5000 V:1:5	20	30	40	50m @A1

© Cardno Limited All Rights Reserved.

This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



Designed GDM

Verified

Approved

onaping and ration
Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au

1/03/2019	Client GLADSTONE REGIONAL COUNCIL					
Date Date	Project AGNES WATER AND BAFFLE CREEK INLAND LINK ROAD	Status		MINARY	N DUDDOG	\
1/03/2019 Date	CONCEPT DESIGN	Zone:	Datum:		Size	<u>s</u> E
	Title	56 Drawing Number	AHD	AS SHOWN	A1 Revision	
	LONGITUDINAL SECTION ALIGNMENT MC04A - SHEET 2 OF 4		R2018071-CI-057			
		•		•		_

- DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE
- POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD:
- OPERATIONAL SPEEDS: TBC;
- DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:
- GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):
- TABLE 4 PERFORMANCE CRITERIA RURAL AREAS (ROAD) DISTRIBUTOR; AND
- TABLE 7 ACCEPTABLE SOLUTIONS RURAL AREAS (ROAD) DISTRIBUTOR AUSTROADS GUIDE TO ROAD DESIGN PART 3 GEOMETRIC DESIGN, 2017;
- AUSTROADS GOIDE TO ROAD DESIGN FART 3 GEOMETRIC DESIGN, 2017;
 IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);
- DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');
- •• DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBV'
 AND
- APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR
- CONSTRUCTION; AND

INITIAL ISSUE


Description

Date

- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE.

VERTICAL - 1:500

Des. Verif. Appd.



© Cardno Limited All Rights Reserved.

his document is produced by Cardno Limited solely for the

benefit of and use by the client in accordance with the

erms of the retainer. Cardno Limited does not and shall no

ssume any responsibility or liability whatsoever to any third

party arising out of any use or reliance by third party on the

content of this document.

Client GLADSTONE REGIONAL COUNCIL

PRELIMINARY

AHD AS SHOWN

A1

0

NOT TO BE USED FOR CONSTRUCTION PURPOSES

R2018071-CI-058

roject AGNES WATER AND BAFFLE CREEK

ALIGNMENT MC04A - SHEET 3 OF 4

INLAND LINK ROAD

CONCEPT DESIGN

LONGITUDINAL SECTION

1/03/2019

1/03/2019

Date

Cardno®

Cardno (Qld) Pty Ltd | ABN 57 051 074 992 101 High Street

North Rockhampton, QLD 4701

Tel: 07 4924 7500 Fax: 07 4926 4375

Web: www.cardno.com.au

Designed GDM

Verified


Approved

- DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE

 NOTED:
- POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;
- OPERATIONAL SPEEDS: TBC;
- DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:
- GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):
 - TABLE 4 PERFORMANCE CRITERIA RURAL AREAS (ROAD) DISTRIBUTOR; AND
- •• TABLE 7 ACCEPTABLE SOLUTIONS RURAL AREAS (ROAD) DISTRIBUTOR AUSTROADS GUIDE TO ROAD DESIGN PART 3 GEOMETRIC DESIGN, 2017;
- •• IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);
- DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');
- •• APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.


DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR
- CONSTRUCTION; AND
- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE.



MC04A SCALE: HORIZONTAL - 1:5000 VERTICAL - 1:500

0		INITIAL ISSUE	GM		
Rev.	Date	Description	Des.	Verif.	Appd.



© Cardno Limited All Rights Reserved.

This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



Onaping the rattice	
Cardno (Qld) Pty Ltd ABN 57 051 074 992	
101 High Street	
North Rockhampton, QLD 4701	
Tel: 07 4924 7500 Fax: 07 4926 4375	
Web: www.cardno.com.au	

rawn GDM	1/03/2019	Client GLADSTONE REGIONAL COUNCIL					
necked	Date	Project AGNES WATER AND BAFFLE CREEK	Status	PRFLI	MINARY		
esigned GDM	Date 1/03/2019	INLAND LINK ROAD	NOT TO BE		ONSTRUCTIO	N PUI	RPOSES
erified	Date	CONCEPT DESIGN Title	Zone: 56	Datum: AHD	Scale AS SHOWN	Size	A1
pproved		LONGITUDINAL SECTION	Drawing Number		7.000.000.00		Revision
		ALIGNMENT MC04A - SHEET 4 OF 4	R2018071-CI-059				0





SCALE 1:40,000 INITIAL ISSUE Des. Verif. Appd. Description

© Cardno Limited All Rights Reserved.

This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au

1/03/2019	Client GLADSTONE REGIONAL COUNCIL	
Date	Project AGNES WATER AND BAFFLE CREEK	Status
Date 1/03/2019	INLAND LINK ROAD	NOT TO
Date	CONCEPT DESIGN Title	Zone:
	MAUDE HILL ROAD TO UXBRIDGE ROAD OPTION 5 - ALIGNMENT MC05	Drawing Nun

Status	PRFI IN	MINARY	
NOT TO BE I	USED FOR CO		N PURPOSI
Zone:	Datum:	Scale	Size
56	AHD	1:40,000	A1
Drawing Number			Revision
R2	2018071-C	CI-060	0

DESIGN DETAILS: DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD; OPERATIONAL SPEEDS: TBC; DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES: GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31): TABLE 4 - PERFORMANCE CRITERIA - RURAL AREAS (ROAD) - DISTRIBUTOR; AND TABLE 7 - ACCEPTABLE SOLUTIONS - RURAL AREAS (ROAD) - DISTRIBUTOR AUSTROADS GUIDE TO ROAD DESIGN PART 3 - GEOMETRIC DESIGN, 2017; IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY); DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW'); APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS. **DESIGNER COMMENTARY:** THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR CONSTRUCTION; AND - EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE. DAF WWBW CLASSIFIED GREEN FISHWAY. APPROXIMATE LOCATION ONLY. DAF WWBW CLASSIFIED AMBER -FISHWAY. APPROXIMATE LOCATION ONLY. JOIN NEATLY AND SMOOTHLY — TO COMMON ALIGNMENT MCA0. Vertical Curve Length (m) Vertical Curve Radius (m) Vertical Geometry Grade (%) Vertical Geometry Length (m) Horizontal Curve Length (m) Horizontal Curve Radius (m) DATUM RL -37.000 CUT / FILL DEPTH 0.45 TO EXISTING SURFACE 9 EXISTING SURFACE 8.083 LEVELS ထ ထ DESIGN LEVELS 8.533 9.134 ROAD CENTRELINE CONTROL LINE CHAINAGE 786. ROAD CENTRELINE SUPER ELEVATION

> MC05 SCALE: HORIZONTAL - 1:5000 VERTICAL - 1:500

INITIAL ISSUE

Description

Date

H: 0 100 200 300 400 5

V: 0 10 20 30 40

SCALE: H:1:5000 V:1:500

Des. Verif. Appd.

© Cardno Limited All Rights Reserved.

This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

LHS and RHS -3%

- EXISTING SURFACE

0.45

10.357

10.807

1200.000 1207.817

5.620



0.45

15.061 15.268

15.511 15.644

Cardno (Qld)) Pty Ltd ABN 57 051 074 992	
	101 High Street	
North F	Rockhampton, QLD 4701	
Tel: 07 49	24 7500 Fax: 07 4926 4375	
Web	o: www.cardno.com.au	

rawn GDM	1/03/2019	Client GLADSTONE REGIONAL COUNCIL					
necked	Date	Project AGNES WATER AND BAFFLE CREEK	Status	PRFLI	MINARY		
esigned GDM	Date 1/03/2019	INLAND LINK ROAD	NOT TO BE		ONSTRUCTIO	N PURPOSE	ΞS
erified	Date	CONCEPT DESIGN Title	Zone: 56	Datum: AHD	Scale AS SHOWN	Size A1	
pproved		LONGITUDINAL SECTION	Drawing Number			Revision	_
		ALIGNMENT MC05 - SHEET 1 OF 6		R2018071-CI-061			
	·						

DESIGN SURFACE

0.347

27.686

28.033

2900.000

29.

DAF WWBW CLASSIFIED GREEN

FISHWAY. APPROXIMATE

LOCATION ONLY.

0.291

0.45

21.558 21.790 0.29

24.002 24.021

24.293 24.471

2600.000 2617.660

DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE

POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;

OPERATIONAL SPEEDS: TBC;

• DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:

• GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):

TABLE 4 - PERFORMANCE CRITERIA - RURAL AREAS (ROAD) - DISTRIBUTOR; AND TABLE 7 - ACCEPTABLE SOLUTIONS - RURAL AREAS (ROAD) - DISTRIBUTOR

AUSTROADS GUIDE TO ROAD DESIGN PART 3 - GEOMETRIC DESIGN, 2017;


• IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);

•• DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');

• APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR
- CONSTRUCTION; AND
- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE.



MC05 SCALE: HORIZONTAL - 1:5000 VERTICAL - 1:500

ISU						
een						
a Q						
Q:\Projects\Central Queensl						
s/C						
ject						
:\Pro						
File:	0		INITIAL ISSUE	GM		
CAD	Rev.	Date	Description	Des.	Verif.	Appd.

H: <u>0</u>	100	200	300	400	500m
V: 0	10 : H:1:5000 V:1:5	20	30	40	50m @A1

© Cardno Limited All Rights Reserved.

This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



Designed GDM

Verified

Approved

onaping and ratair
Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au

1/03/2019	GLADSTONE REGIONAL COUNCIL					
Date Date 1/03/2019 Date	Project AGNES WATER AND BAFFLE CREEK INLAND LINK ROAD CONCEPT DESIGN	Status NOT TO BE Zone:		WINARY ONSTRUCTION	N PUF	RPOSE
Date	Title	56	AHD	AS SHOWN	0120	A1
	LONGITUDINAL SECTION ALIGNMENT MC05 - SHEET 2 OF 6	Drawing Number	2018071-0	CI-062		Revision 0

DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE

POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;

OPERATIONAL SPEEDS: TBC;

DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:

GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):

TABLE 4 - PERFORMANCE CRITERIA - RURAL AREAS (ROAD) - DISTRIBUTOR; AND TABLE 7 - ACCEPTABLE SOLUTIONS - RURAL AREAS (ROAD) - DISTRIBUTOR

AUSTROADS GUIDE TO ROAD DESIGN PART 3 - GEOMETRIC DESIGN, 2017;

•• IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);


•• DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');

•• APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR
- CONSTRUCTION; AND
- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE.

EXISTING SURFACE



MC05 SCALE: HORIZONTAL - 1:5000 VERTICAL - 1:500

nsl						
Queensla						
LS MC053 ojects\Central						
MC053 cts\Cent						
S N						
OT						
ا: ان						
EF's: F File:	0		INITIAL ISSUE	GM		
XREF's: CAD File	Rev.	Date	Description	Des.	Verif.	Appd.

H: <u>0</u>	100	200	300	400	500n
V: 0	10	20	30	40	50m
SCALE	: H:1:5000 V:1:5	600			@A1

© Cardno Limited All Rights Reserved.

This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.




3 and 1 and 1
Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au

wn DM	Date 1/03/2019	Client GLADSTONE REGIONAL COUNCIL					
cked	Date	Project AGNES WATER AND BAFFLE CREEK	Status	PRFLI	MINARY		
igned DM	Date 1/03/2019		NOT TO BE		ONSTRUCTION	PURPO:	SE
fied	Date	CONCEPT DESIGN Title	Zone: 56	Datum: AHD	Scale SHOWN	Size A1	
roved		LONGITUDINAL SECTION	Drawing Number			Revisi	ion
		ALIGNMENT MC05 - SHEET 3 OF 6	R	2018071-0	CI-063)

- DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE
- POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;
- OPERATIONAL SPEEDS: TBC;
- DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:
- GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):
- TABLE 4 PERFORMANCE CRITERIA RURAL AREAS (ROAD) DISTRIBUTOR; AND
- TABLE 7 ACCEPTABLE SOLUTIONS RURAL AREAS (ROAD) DISTRIBUTOR
- AUSTROADS GUIDE TO ROAD DESIGN PART 3 GEOMETRIC DESIGN, 2017;
 IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);
- DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');
- AND
- APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR
- CONSTRUCTION; AND
- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE.



MC05 SCALE: HORIZONTAL - 1:5000 VERTICAL - 1:500

2					
5					
0		INITIAL ISSUE	GM		
Rev	. Date	Description	Des.	Verif.	Appd.

H: <u>0</u>	100	200	300	400	500m
V: 0	10	20	30	40	50m
	: H:1:5000 V:1:5	500			@A1

© Cardno Limited All Rights Reserved.

This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



Designed GDM

Verified

Approved

3 and 1 and 1
Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au

Date 1/03/2019	Client GLADSTONE REGIONAL COUNCIL					
Date Date 1/03/2019	Project AGNES WATER AND BAFFLE CREEK INLAND LINK ROAD	Status NOT TO BE		WINARY ONSTRUCTION	N PURPOS	SES
Date	CONCEPT DESIGN Title	Zone: 56	Datum: AHD	Scale AS SHOWN	Size A1	
	LONGITUDINAL SECTION ALIGNMENT MC05 - SHEET 4 OF 6	Drawing Number R2018071-CI-064				on

• DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE

POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;

OPERATIONAL SPEEDS: TBC;

DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:

GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):

TABLE 4 - PERFORMANCE CRITERIA - RURAL AREAS (ROAD) - DISTRIBUTOR; AND TABLE 7 - ACCEPTABLE SOLUTIONS - RURAL AREAS (ROAD) - DISTRIBUTOR

AUSTROADS GUIDE TO ROAD DESIGN PART 3 - GEOMETRIC DESIGN, 2017;

IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);

DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');

APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.


DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR

CONSTRUCTION; AND

- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF

THE DETAIL DESIGN PHASE.



SCALE: HORIZONTAL - 1:5000 VERTICAL - 1:500

nsı						
Queensi						
a S						
d. rProjects/Central						
2						
200						
=						
	0		INITIAL ISSUE	GM		
	Rev.	Date	Description	Des.	Verif.	Appd.

H: <u>0</u>	100	200	300	400	500m
V: 0	10	20	30	40	50m
	: H:1:5000 V:1:5	500			@A1

© Cardno Limited All Rights Reserved. This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



	_
Cardno (Qld) Pty Ltd ABN 57 051 074 992	
101 High Street	
North Rockhampton, QLD 4701	
Tel: 07 4924 7500 Fax: 07 4926 4375	
Web: www.cardno.com.au	

GDM 1/03/2019	GLADSTONE REGIONAL COUNCIL					
ecked Date	Project AGNES WATER AND BAFFLE CREEK	Status	PRFLIN	JINARY		
signed Date SDM 1/03/2019	INLAND LINK ROAD	NOT TO BE	USED FOR CO		I PURI	POSES
rified Date	CONCEPT DESIGN Title	Zone: 56	Datum: AHD	Scale AS SHOWN	Size A	A 1
proved	LONGITUDINAL SECTION	Drawing Number	72	7.0 0.10 1111		Revision
	ALIGNMENT MC05 - SHEET 5 OF 6		R2018071-CI-065			
	_	•	•	•		

• DESIGN SPEED = 110KPH WITH EXCEPTION TO TIE IN GEOMETRY TO EXISTING ROAD FORMATIONS OR OTHERWISE

POSTED SPEED = TBC IF REQUIRED AS A RURAL ROAD;

OPERATIONAL SPEEDS: TBC;

DESIGN DETAILS ARE IN ACCORDANCE WITH THE FOLLOWING GUIDELINES:

GLADSTONE REGIONAL COUNCIL ROAD HIERARCHY POLICY (P-2014-31):

TABLE 4 - PERFORMANCE CRITERIA - RURAL AREAS (ROAD) - DISTRIBUTOR; AND TABLE 7 - ACCEPTABLE SOLUTIONS - RURAL AREAS (ROAD) - DISTRIBUTOR

AUSTROADS GUIDE TO ROAD DESIGN PART 3 - GEOMETRIC DESIGN, 2017;


IPWEA LOWER ORDER ROADS DESIGN MANUAL (APPLIED TO INTERIM CROSS SECTION DETAILS ONLY);

DEPARTMENT OF AGRICULTURE AND FISHERIES GUIDELINES FOR WATERWAY BARRIER WORKS ('DAF WWBW');

APPLICABLE CAPRICORN MUNICIPAL DEVELOPMENT GUIDELINE STANDARD DRAWINGS SHALL BE APPLIED SUCH AS CMDG-R-094 AND 095 FOR FLOODWAY REQUIREMENTS.

DESIGNER COMMENTARY:

- THE DESIGN DETAILS SHOWN IN THIS PACKAGE ARE CONCEPTUAL IN NATURE ONLY AND ARE NOT FOR
- CONSTRUCTION; AND
- EXISTING SERVICES HAVE BEEN IDENTIFIED TO BE IN THE VICINITY OF THESE CONCEPT ALIGNMENTS. SERVICES SUCH AS OVERHEAD POWER, TELSTRA AND WATER MAINS SHALL BE LOCATED PRIOR TO COMMENCEMENT OF THE DETAIL DESIGN PHASE.



SCALE: HORIZONTAL - 1:5000 VERTICAL - 1:500

nsk						
Queensla						
56 entra						
LS MC056 ojects\Central						
LS N oject						
F 실						
립입						
XREF's: F CAD File:	0		INITIAL ISSUE	GM		
XRE	Rev.	Date	Description	Des.	Verif.	Appd.

1: 0	100	200	300	400	500m
V: 0 SCALE	10 : H:1:5000 V:1:5	20	30	40	50m @A1

© Cardno Limited All Rights Reserved. This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



Cardno (Qld) Pty Ltd ABN 57 051 074 992
101 High Street
North Rockhampton, QLD 4701
Tel: 07 4924 7500 Fax: 07 4926 4375
Web: www.cardno.com.au

GDM 1/03/2019	Client GLADSTONE REGIONAL COUNCIL					
	Project AGNES WATER AND BAFFLE CREEK	Status	PRFI II	MINARY		
Designed Date GDM 1/03/2019		NOT TO BE		ONSTRUCTION	N PUI	RPOSES A1 Revision 0
Verified Date	CONCEPT DESIGN Title	Zone: 56	Datum: AHD	Scale AS SHOWN	Size	A1
Approved		Drawing Number	, , , , ,	710 01101111		
	LONGITUDINAL SECTION ALIGNMENT MC05 - SHEET 6 OF 6	R2018071-				

APPENDIX

B

PRELIMINARY OPINION OF COST





1 11-Mar-19

Revision

Date:

R2018071

Project Number: Project Name: Agnes Water to Baffle Creek

Road Name: Inland Road

Location: Gladstone Regional Council

Summary sheet (Engineering and Construction)

Summary sheet (Engineering and	Construction						1		
Item Number	New construction length per option (km): (Excludes existing roads used to complete this option)	General contractor setup costs(\$):	New construction costs (\$): (Including drainage and retaining structures)	MCA0 new construction cost used to complete this option (\$):	Engineering Consultancy and investigations (\$): (approx.1.5% of new construction cost)	Contingency (\$): (approx.25% of setup, new construction and design costs)	Total Option Cost (\$) Ex. GST:	Cost per km (\$):	Anticipated annual maintenance costs:
MC0A - INTERIM		\$ 392,500.00	\$ 8,387,521.81		\$ 125,812.83	\$ 2,226,458.66	\$ 11,132,293.29	\$ 1,445,752.38	\$ 167,750.44
Upgrade to MC0A - ULTIMATE UNSEALED	7.7	\$ 392,500.00	\$ 10,736,225.11		\$ 161,043.38	\$ 2,822,442.12	\$ 14,112,210.61	\$ 1,832,754.62	\$ 214,724.50
Upgrade to MC0A - ULTIMATE and seal		\$ 392,500.00	\$ 11,796,028.61		\$ 176,940.43	\$ 3,091,367.26	\$ 15,456,836.30	\$ 2,007,381.34	\$ 235,920.57
MC02 - INTERIM		\$ 392,500.00	\$ 8,436,120.10	\$ 8,387,521.81	\$ 252,354.63	\$ 4,367,124.13	\$ 21,835,620.67	\$ 1,719,340.21	\$ 336,472.84
Upgrade to MC02 - ULTIMATE UNSEALED	5.0	\$ 392,500.00	\$ 6,221,300.10	\$ 10,736,225.11	\$ 254,362.88	\$ 4,401,097.02	\$ 22,005,485.12	\$ 2,857,855.21	\$ 339,150.50
Upgrade to MC02 - ULTIMATE and seal		\$ 392,500.00	\$ 6,899,287.60	\$ 11,796,028.61	\$ 280,429.74	\$ 4,842,061.49	\$ 24,210,307.45	\$ 3,144,195.77	\$ 747,812.65
MC02A - INTERIM		\$ 392,500.00	\$ 4,976,087.23	\$ 8,387,521.81	\$ 200,454.14	\$ 3,489,140.79	\$ 17,445,703.97	\$ 1,341,977.23	\$ 267,272.18
Upgrade to MC02A - ULTIMATE UNSEALED	5.3	\$ 392,500.00	\$ 6,701,724.99	\$ 10,736,225.11	\$ 261,569.25	\$ 4,523,004.84	\$ 22,615,024.19	\$ 2,937,016.13	\$ 348,759.00
Upgrade to MC02A - ULTIMATE and seal		\$ 392,500.00	\$ 7,435,792.99	\$ 11,796,028.61	\$ 288,477.32	\$ 4,978,199.73	\$ 24,890,998.66	\$ 3,232,597.23	\$ 769,272.86
MC03A - INTERIM		\$ 392,500.00	\$ 4,810,150.43	\$ 8,387,521.81	\$ 197,965.08	\$ 3,447,034.33	\$ 17,235,171.65	\$ 1,346,497.79	\$ 263,953.44
Upgrade to MC03A - ULTIMATE UNSEALED	5.1	\$ 392,500.00	\$ 6,570,313.59	\$ 10,736,225.11	\$ 259,598.08	\$ 4,489,659.20	\$ 22,448,295.98	\$ 2,915,363.11	\$ 346,130.77
Upgrade to MC03A - ULTIMATE and seal		\$ 392,500.00	\$ 7,276,139.59	\$ 11,796,028.61	\$ 286,082.52	\$ 4,937,687.68	\$ 24,688,438.40	\$ 3,206,290.70	\$ 762,886.73
MC04 - INTERIM	10.8	\$ 392,500.00	\$ 9,972,586.26		\$ 149,588.79	\$ 2,628,668.76	\$ 13,143,343.81	\$ 1,216,976.28	\$ 199,451.73
Realign to MC04A - ULTIMATE UNSEALED	10.2	\$ 392,500.00	\$ 34,234,403.05		\$ 513,516.05	\$ 8,785,104.77	\$ 43,925,523.87	\$ 4,306,423.91	\$ 684,688.06
Realign to MC04A - ULTIMATE and seal	10.2	\$ 392,500.00	\$ 35,634,640.05		\$ 534,519.60	\$ 9,140,414.91	\$ 45,702,074.56	\$ 4,480,595.55	\$ 1,425,385.60
MC05 - INTERIM		\$ 392,500.00	\$ 16,825,454.16		\$ 252,381.81	\$ 4,367,583.99	\$ 21,837,919.96	\$ 1,277,071.34	\$ 336,509.08
Upgrade to MC05 - ULTIMATE UNSEALED	17.1	\$ 392,500.00	\$ 21,460,600.60		\$ 321,909.01	\$ 5,543,752.40	\$ 27,718,762.01	\$ 1,620,980.23	\$ 429,212.01
Upgrade to MC05 - ULTIMATE and seal		\$ 392,500.00	\$ 23,817,172.10		\$ 357,257.58	\$ 6,141,732.42	\$ 30,708,662.10	\$ 1,795,828.19	\$ 952,686.88



Project Number: R2018071

Project Name: Agnes Water to Baffle Creek

Road Name: Inland Road

Location: Gladstone Regional Council Revision 0
Date: 11-Mar-19

Work Package: General Contractor Setup Costs

	Work i dokage: General Gentiagier e	ctup o	0313			
Item Number	Description	Unit of Measure	Quantity	L	Init Rate (\$)	Amount ex GST(\$)
MRS02 Oct 14						
	PROVISION FOR TRAFFIC					
1201.01	Provision for traffic (MRS02 Oct 14)	lump sum	1	\$	25,000.00	\$ 25,000.0
1202.01	Traffic Management Plan	lump sum	1	\$	12,500.00	\$ 12,500.0
	SURVEY					
	DTM survey (Start of project)	lump sum	1	\$	75,000.00	\$ 75,000.0
	DTM survey (End of project)	lump sum	1	\$	75,000.00	\$ 75,000.0
MRS28 Jun 09						
	CONTRACTOR'S SITE FACILITIES AND CAMP					
1101.01	Contractor's site facilities (MRS28 Jun 09)	lump sum	1	\$	20,000.00	\$ 20,000.0
MRS51 Jan 15						
	ENVIRONMENTAL MANAGEMENT					
1330.01	Environmental Inspections (MRS51 Jan 15)	lump sum	1	\$	25,000.00	\$ 25,000.0
1331.01	Develop Environmental Management Plan (Construction) (MRS51 Jan 15)	lump sum	1	\$	20,000.00	\$ 20,000.0
1332.01	Implement Environmental Management Plan (Construction) (MRS51 Jan 15)	lump sum	1	\$	30,000.00	\$ 30,000.0
1333.01	Environmental Licences, Permits and Approvals	lump sum	1	\$	20,000.00	\$ 20,000.0
1375.01P	Fauna Management, if ordered (Provisional Quantity)	each	1	\$	20,000.00	\$ 20,000.0
1381.01P	Pest Control, if ordered (Provisional Quantity)	each	1	\$	20,000.00	\$ 20,000.0
	MISCELLANEOUS					
9190.01S	Preparation and submission of As Constructed drawings and asset information (ADAC submission)	lump sum	1	\$	50,000.00	\$ 50,000.0

Total for Civil Works (ex GST): \$392,500



Project Number: R2018071
Project Name: Agnes War
Road Name: Option 2 (I Agnes Water to Baffle Creek Option 2 (MC02) - Interim unsealed Gladstone Regional Council Location:

0 11-Mar-19 Revision Date:

Work Package: Civil Works (Including drainage and retaining Structures):

	work Package: Civil works (including drainage and		ng St	iuciui es).		
Item Number	Description	Unit of Measure	Quantity	Unit Rate (\$)	Amou	nt ex GST(\$)
		Measure				
1	EROSION AND SEDIMENT CONTROL:					
1.1	Check Dams, rock (Provisional Quantity)	lump sum	500	\$ 216.00	\$	108,000.00
1.2	Silt / Sediment Fence (Provisional Quantity)	m	10000	\$ 10.87	\$	108,700.00
2	DRAINAGE STRUCTURES:					
	Culverts (complete):					
	Supply and installation of concrete pipe culvert components, Class 3, 600mm diameter flush joint with					
2.1	external bands to AS4058 including excavation, bedding and backfill (complete). Cross drainage located	m	10	\$ 15,000.00	\$	150,000.00
	every 500m spacing along alignment.					
3	EARTHWORKS, PREPARATION: Clearing and grubbing, including removal of building structures, retaining structures, vegetation including					
3.1	mulching to stockpile, concrete structures, water tanks, septic tanks and capping and removal of bore	m2	86100	\$ 1.87	\$	161.007.00
0.1	equipment (Provisional Quantity as directed)		00100		Ψ	101,001.00
3.2	Stripping of topsoil (Provisional Quantity as directed)	m3	8610	\$ 6.65	\$	57,256.50
3.3	Ground surface treatment under embankment, standard	m2	25830	\$ 1.20	\$	30,996.00
3.4	Excavation and disposal of Unsuitable Material with individual excavation < 10 m3 (Provisional Quantity	m3	10	\$ 50.00	\$	500.00
	as directed) Excavation and disposal of Unsuitable Material with individual excavation > 10 m3 (Provisional Quantity					
3.5	as directed)	m3	2000	\$ 16.65	\$	33,300.00
4	EARTHWORKS, EXCAVATION:					
4.1	Road excavation, all materials	m3	39700	\$ 11.25	\$	446,625.00
4.2	Excavation of non-rippable material in road excavation, rate additional to rate for Work Item 3201	m3	2000	\$ 60.50	\$	121,000.00
	(Provisional Quantity)	-		,		,
5	EARTHWORKS, EMBANKMENT:					
5.1	Road embankment	m3	16500	\$ 6.95	\$	114,675.00
0.1	Trodd offiballitheric		10000	ψ 0.00	Ψ	,0.0.00
6	EARTHWORKS, SUBGRADE:					
6.1	Testing of existing material below subgrade level in cuttings (Provisional Quantity if ordered)	per set	295	\$ 450.00	\$	132,750.00
6.2	Subgrade treatment Type A in cuttings (Provisional Quantity if ordered)	m2	25830	\$ 1.75	\$	45,202.50
_						
7	EARTHWORKS, BACKFILL:	0	E4000	ê 70.0F	•	0.000.445.00
7.1	Backfill with general backfill material to areas of unsuitable	m3	51660	\$ 70.25	\$	3,629,115.00
8	UNBOUND PAVEMENTS:					
8.1	Base Course Type 2.1 200mm (CBR 80)	m3	6505.06	\$ 122.50	\$	796,869.48
8.2	Sub-base Course Type 2.3 300mm (CBR45)	m3	8219.55	\$ 97.50	\$	801,406.52
8.3	Geotextile under sub-base pavement	m2	39500	\$ 1.50	\$	59,250.00
9	SPRAYED BITUMINOUS SURFACING (EXCLUDING EMULSION):					
9.1	Primer seal - AMC00 @ 0.9L/m2	litre	33100		\$	-
9.2 9.3	Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site	litre m3	51480 340		\$	
9.3	Supply and spreading cover aggregate 14mm, 110 mz/ms, on job site	ПЮ	340		φ	
10	REMOVAL, DEMOLITION AND RE-ERECTION:					
10.1	Removal and re-erection of road furniture	lump sum	1	\$ 5,000.00	\$	5,000.00
11	SUPPLY OF COVER AGGREGATE:				_	
11.1	Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2	litre	25740		\$	-
11.2	Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site	m3	190		\$	-
12	LINE MARKING AND SIGNAGE:					
12.1	Spotting only for longitudinal lines	m	14710		\$	-
12.2	Linemarking (white paint complete)	m	14710		\$	-
12.3	New signs and posts (Complete)	lump sum	1	\$ 25,000.00	\$	25,000.00
12.4	New road edge guid posts (Complete)	No.	100	\$ 60.00	\$	6,000.00
13	LANDSCAPING:		00:			075 500 0
13.1	Re-spreading of stockpiled topsoil to depth of 100mm	m2	86100	\$ 3.20	\$	275,520.00
13.2	Hydromulch grass seeding.	m2	86100	\$ 0.91	\$	78,351.00
14	MISCELLANEOUS:				-	
14.1	Retaining structure - Keppel Block including excavation, footing and backfill	m2	2022.1	\$ 550.00	\$	1,112,156.10
14.3	Concrete lined invert / barrier kerb to top of retaining walls	m	390	\$ 110.00	\$	42,900.00
14.4	Construction of stockpile site	Each	10	\$ 2,500.00	\$	25,000.00
14.5	W-beam guard rail, ezy-guard posts	m	490	\$ 110.00		53,900.00
14.6	Steel beam guard rail terminal, ET2000 PLUS TL2 terminal	Each	4	\$ 3,910.00	\$	15,640.00

Total for Civil Works (ex GST): \$8,436,120



Project Number: R2018071 Project Name: Agnes War Agnes Water to Baffle Creek Option 2 (MC02) - Ultimate sealed Gladstone Regional Council Road Name: Location:

0 11-Mar-19 Revision Date:

Work Package: Civil Works (Including drainage and retaining Structures):

	Work Package: Civil Works (Including drainage and	retaini	ng Sti	ructures):		
Item Number	Description	Unit of Measure	Quantity		Amou	ınt ex GST(\$)
1 1.1	EROSION AND SEDIMENT CONTROL: Check Dams, rock (Provisional Quantity)	lump sum	500	\$ 216.00	\$	108,000.00
1.2	Silt / Sediment Fence (Provisional Quantity)	m m	10000	\$ 10.87	\$	108,700.00
	one occurrent one (Frontieria Galina)		10000	Ψ 10.07	Ψ	100,100.00
2	DRAINAGE STRUCTURES:					
	Culverts (complete):					
0.4	Supply and installation of concrete pipe culvert components, Class 3, 600mm diameter flush joint with		40	₫ 45.000.00	6	450,000,00
2.1	external bands to AS4058 including excavation, bedding and backfill (complete). Cross drainage located every 500m spacing along alignment.	m	10	\$ 15,000.00	\$	150,000.00
	over) boom spacing diong diliginions.					
3	EARTHWORKS, PREPARATION:					
	Clearing and grubbing, including removal of building structures, retaining structures, vegetation including					
3.1	mulching to stockpile, concrete structures, water tanks, septic tanks and capping and removal of bore	m2	34400	\$ 1.87	\$	64,328.00
3.2	equipment (Provisional Quantity as directed) Stripping of topsoil (Provisional Quantity as directed)	m3	17200	\$ 6.65	\$	114,380.00
3.3	Ground surface treatment under embankment, standard	m2	10320	\$ 1.20	\$	12,384.00
3.4	Excavation and disposal of Unsuitable Material with individual excavation < 10 m3 (Provisional Quantity	m3		\$ 50.00	\$	500.00
3.4	as directed)	ПБ	10	\$ 50.00	9	300.00
3.5	Excavation and disposal of Unsuitable Material with individual excavation > 10 m3 (Provisional Quantity	m3	3000	\$ 16.65	\$	49,950.00
	as directed)					
4	EARTHWORKS, EXCAVATION:					
4.1	Road excavation, all materials	m3	58500	\$ 11.25	\$	658,125.00
4.2	Excavation of non-rippable material in road excavation, rate additional to rate for Work Item 3201	m3	3000	\$ 60.50	\$	181,500.00
4.2	(Provisional Quantity)	ПЮ	3000	\$ 00.50	φ	181,500.00
	FARTINGRYO FARANIZATA					
5 5.1	EARTHWORKS, EMBANKMENT: Road embankment	m3	8000	\$ 6.95	\$	55,600.00
5.1	Nodu emparisment	ПЮ	8000	φ 0.93	φ	33,000.00
6	EARTHWORKS, SUBGRADE:					
6.1	Testing of existing material below subgrade level in cuttings (Provisional Quantity if ordered)	per set	295	\$ 450.00	\$	132,750.00
6.2	Subgrade treatment Type A in cuttings (Provisional Quantity if ordered)	m2	10320	\$ 1.75	\$	18,060.00
<u>_</u>						
7	EARTHWORKS, BACKFILL:	?	2000	\$ 70.25	6	210.750.00
7.1	Backfill with general backfill material to areas of unsuitable	m3	3000	\$ 70.25	\$	210,750.00
8	UNBOUND PAVEMENTS:					
8.1	Base Course Type 2.1 200mm (CBR 80)	m3	13924	\$ 122.50	\$	1,705,690.00
8.2	Sub-base Course Type 2.3 300mm (CBR45)	m3	23925.1	\$ 97.50	\$	2,332,699.10
8.3	Geotextile under sub-base pavement	m2	77000	\$ 1.50	\$	115,500.00
	ORDANIES DIFFININGUE SUDEA ONE (EVOLUDINO EMULCION)					
9 9.1	SPRAYED BITUMINOUS SURFACING (EXCLUDING EMULSION): Primer seal - AMC00 @ 0.9L/m2	litre	66190		\$	_
9.2	Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2	litre	102950		\$	
9.3	Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site	m3	670		\$	-
	7 7 7 7					
10					Ψ	
	REMOVAL, DEMOLITION AND RE-ERECTION:				<u> </u>	
10.1	REMOVAL, DEMOLITION AND RE-ERECTION: Removal and re-erection of road furniture	lump sum	1	\$ 5,000.00	\$	5,000.00
10.1	Removal and re-erection of road furniture	lump sum	1	\$ 5,000.00	\$	5,000.00
10.1	Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE:	·	1 51480	\$ 5,000.00	\$	5,000.00
10.1 11 11.1	Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2	litre	1 51480 370	\$ 5,000.00	\$	5,000.00
10.1 11	Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE:	·	1 51480 370	\$ 5,000.00	\$	5,000.00
10.1 11 11.1	Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2	litre		\$ 5,000.00	\$	5,000.00
10.1 11 11.1 11.2 12 12.1	Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines	litre m3	370 14710	\$ 5,000.00	\$ \$	5,000.00
10.1 11 11.1 11.2 12 12.1 12.2	Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines Linemarking (white paint complete)	litre m3 m	370		\$ \$ \$	
10.1 11 11.1 11.2 12 12.1 12.2 12.3	Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longituinal lines Linemarking (white paint complete) New signs and posts (Complete)	itre m3 m m lump sum	370 14710 14710	\$ 25,000.00	\$ \$ \$	
10.1 11 11.1 11.2 12 12.1 12.2	Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines Linemarking (white paint complete)	litre m3 m	370 14710		\$ \$ \$	
10.1 11 11.1 11.2 12 12.1 12.2 12.3 12.4	Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longituinal lines Linemarking (white paint complete) New signs and posts (Complete)	itre m3 m m lump sum	370 14710 14710	\$ 25,000.00	\$ \$ \$	
10.1 11 11.1 11.2 12 12.1 12.2 12.3	Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines Linemarking (white paint complete) New signs and posts (Complete) New road edge guid posts (Complete)	itre m3 m m lump sum	370 14710 14710	\$ 25,000.00	\$ \$ \$	
10.1 11 11.1 11.2 12 12.1 12.2 12.3 12.4	Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines Linemarking (white paint complete) New signs and posts (Complete) New road edge guid posts (Complete) LANDSCAPING:	itre m3 m m lump sum No.	370 14710 14710 1 100	\$ 25,000.00	\$ \$ \$ \$ \$	25,000.00
10.1 11 11.1 11.2 12 12.1 12.2 12.3 12.4 13 13.1 13.2	Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines Linemarking (white paint complete) New signs and posts (Complete) New road edge guid posts (Complete) LANDSCAPING: Re-spreading of stockpiled topsoil to depth of 100mm Hydromulch grass seeding.	m m lump sum No.	370 14710 14710 1 100 34400	\$ 25,000.00 \$ 60.00 \$ 3.20	\$\$ \$\$ \$\$ \$\$ \$\$	- - 25,000.00 6,000.00
10.1 11 11.1 11.2 12 12.1 12.2 12.3 12.4 13 13.1 13.2	Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines Linemarking (white paint complete) New signs and posts (Complete) New road edge guid posts (Complete) LANDSCAPING: Re-spreading of stockpiled topsoil to depth of 100mm Hydromulch grass seeding. MISCELLANEOUS:	m m lump sum No.	370 14710 14710 1 100 34400 34400	\$ 25,000.00 \$ 60.00 \$ 3.20	64 65 65 65 65 65 65 65 65 65 65 65 65 65	- - 25,000.00 6,000.00
10.1 11 11.1 11.2 12 12.1 12.2 12.3 12.4 13 13.1 13.2 14 14.1	Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines Linemarking (white paint complete) New signs and posts (Complete) New road edge guid posts (Complete) LANDSCAPING: Re-spreading of stockpiled topsoil to depth of 100mm Hydromulch grass seeding. MISCELLANEOUS: Retaining structure - Keppel Block including excavation, footing and backfill	itre m3 m m lump sum No. m2 m2 m2	370 14710 14710 1 100 34400 34400	\$ 25,000.00 \$ 60.00 \$ 3.20	(4) (4) (4) (4) (4) (4) (4) (4) (4) (4)	25,000.00 6,000.00 110,080.00 31,304.00
10.1 11 11.1 11.2 12 12.1 12.2 12.3 12.4 13 13.1 13.2 14 14.1 14.3	Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines Linemarking (white paint complete) New signs and posts (Complete) New road edge guid posts (Complete) LANDSCAPING: Re-spreading of stockpiled topsoil to depth of 100mm Hydromulch grass seeding. MISCELLANEOUS: Retaining structure - Keppel Block including excavation, footing and backfill Concrete lined invert / barrier kerb to top of retaining walls	m m m lump sum No. m2 m2 m2 m	370 14710 14710 1 100 34400 0 400	\$ 25,000.00 \$ 60.00 \$ 3.20 \$ 0.91	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	25,000.00 6,000.00 110,080.00 31,304.00
10.1 11 11.1 11.2 12 12.1 12.2 12.3 12.4 13 13.1 13.2 14 14.1	Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines Linemarking (white paint complete) New signs and posts (Complete) New road edge guid posts (Complete) LANDSCAPING: Re-spreading of stockpiled topsoil to depth of 100mm Hydromulch grass seeding. MISCELLANEOUS: Retaining structure - Keppel Block including excavation, footing and backfill	itre m3 m m lump sum No. m2 m2 m2	370 14710 14710 1 100 34400 34400	\$ 25,000.00 \$ 60.00 \$ 3.20	(4) (4) (4) (4) (4) (4) (4) (4) (4) (4)	25,000.00 6,000.00 110,080.00 31,304.00

Total for Civil Works (ex GST): \$6,221,300



Project Number: R2018071
Project Name: Agnes War
Road Name: Option 2 (I Agnes Water to Baffle Creek Option 2 (MC02) - Ultimate sealed Gladstone Regional Council Location:

Revision Date: **0** 11-Mar-19

Work Packago: Civil Works (Including drainage and retaining Structures):

Description	Measure	Quantity	Unit Rate (\$)	Am	ount ex GS
EDOCION AND CEDIMENT CONTROL.					
	lumn sum	500	\$ 216.0) \$	108,0
	•				108,7
One / Octament 1 choc (1 rovisional equantity)		10000	Ψ 10.0	Ψ	100,1
DRAINAGE STRUCTURES:					
Culverts (complete):					
Supply and installation of concrete pipe culvert components, Class 3, 600mm diameter flush joint with					
external bands to AS4058 including excavation, bedding and backfill (complete). Cross drainage located	m	10	\$ 15,000.0	\$	150,0
every 500m spacing along alignment.				_	
FARTUMORYC PREPARATION:				_	
				-	
	m2	34400	\$ 1.8	7 \$	64,3
equipment (Provisional Quantity as directed)		01100		Ψ.	0 1,0
Stripping of topsoil (Provisional Quantity as directed)	m3	17200	\$ 6.6	5 \$	114,3
Ground surface treatment under embankment, standard	m2	10320	\$ 1.2	\$	12,3
Excavation and disposal of Unsuitable Material with individual excavation < 10 m3 (Provisional Quantity	m3	10	\$ 50.0) S	5
	0		Ψ 00.0		
	m3	3000	\$ 16.6	5 \$	49,9
as directed)				-	
EARTHWORKS, EXCAVATION:	-			+	
	m3	58500	\$ 11.2	5 \$	658,1
Excavation of non-rippable material in road excavation, rate additional to rate for Work Item 3201					
(Provisional Quantity)	m3	3000	\$ 60.5) 5	181,5
Road embankment	m3	8000	\$ 6.9	5 \$	55,6
EARTHWORKS SURGRADE					
,		005	r 450.0		400
			· · · · · · · · · · · · · · · · · · ·	_	132,7
Subgrade freatment Type A in Cuttings (Provisional Quantity if ordered)	IIIZ	10320	\$ 1.7	Ф	10,0
EARTHWORKS, BACKFILL:				+	
	m3	3000	\$ 70.2	5 \$	210,7
UNBOUND PAVEMENTS:					
Base Course Type 2.1 200mm (CBR 80)	m3	13924	\$ 122.5	\$	1,705,6
	m3				2,332,6
Geotextile under sub-base pavement	m2	77000	\$ 1.5) \$	115,5
	Ea	00400	. 4.0	- 6	400.0
					129,0
					200,7 135,6
Supply and spreading cover aggregate 14min, 110 mz/ms, on job site	1110	070	φ 202.5	Jφ	133,0
REMOVAL DEMOLITION AND RE-ERECTION:				+	
	lump sum	1	\$ 5,000,0) \$	5,0
			.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		
SUPPLY OF COVER AGGREGATE:					
Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2	litre	51480	\$ 2.0	\$	102,9
Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site	m3	370	\$ 218.5	\$	80,8
		4.4=			
					7,3
		14/10		_	21,3 25.0
	terrip e erri	100	* -,		25,0
ivew road edge guid posts (Corriplete)	INU.	100	ψ 60.0	, ø	0,0
LANDSCAPING:					
	m2	34400	\$ 32) \$	110,0
					31,3
		0.400	- 0.3	Ψ	01,0
MISCELLANEOUS:			İ		
Retaining structure - Keppel Block including excavation, footing and backfill	m2	0		\$	
Tretaining structure Trepper Blook including excavation, rooting and backing					
Concrete lined invert / barrier kerb to top of retaining walls	m	400		\$	
Concrete lined invert / barrier kerb to top of retaining walls Construction of stockpile site		10	\$ 2,500.0	\$	25,0
Concrete lined invert / barrier kerb to top of retaining walls	m		\$ 2,500.0		25,0
	EROSION AND SEDIMENT CONTROL: Check Dams, rock (Provisional Quantity) Sill / Sedment Fence (Provisional Quantity) DRANAGE STRUCTURES: Culverts (complete): Supply and installation of concrete pipe culvert components, Class 3, 600mm diameter flush joint with external bands to AS4058 including excavation, bedding and backfill (complete). Cross drainage located every 500m spacing along alignment. EARTHWORKS, PREPARATION: Clearing and grubbing, including removal of building structures, retaining structures, vegetation including mulching to stockpile, concrete structures, water tanks, septic tanks and capping and removal of bore equipment (Provisional Quantity as directed) Stripping of topseol (Provisional Quantity as directed) Stripping of topseol (Provisional Quantity as directed) Stripping of topseol (Provisional Quantity as directed) Excavation and disposal of Unsultable Material with individual excavation < 10 m3 (Provisional Quantity) as directed) Excavation and disposal of Unsultable Material with individual excavation > 10 m3 (Provisional Quantity) as directed) EARTHWORKS, EXCAVATION: Road excavation, all materials Excavation of non-rippable material in road excavation, rate additional to rate for Work Item 3201 (Provisional Quantity) EARTHWORKS, EMBANKMENT: Road embankment EARTHWORKS, SUBGRADE: Testing of existing material below subgrade level in cuttings (Provisional Quantity) if ordered) EARTHWORKS, BACKFILL: Backfill with general backfill material to areas of unsultable UNBOUND PAVEMENTS: Base Course Type 2.3 300mm (CBR 80) Sub-base Course Type 2.7 30mm (CBR 80) Sub-base Course Type 2.7 30mm (CBR 80) Sub-base Course Type 2.7 30mm (CBR	EROSION AND SEDMENT CONTROL:	Pescription Unit of Measure	EROSON AND SEDMENT CONTROL: Chock Dams, rock (Provisional Quantity) DRANAGE STRUCTURES: Say Sediment Fence (Provisional Quantity) DRANAGE STRUCTURES: Supply allowed to the control of provisional quantity of the control of the	EROSION AND SEDMENT CONTROL: Check Dume, took, (Provisional Quantity) EROSION AND SEDMENT CONTROL: Check Dume, took, (Provisional Quantity) BY 210.00 \$ 210.00 \$ 10.877 \$ 3

Total for Civil Works (ex GST): \$6,899,288



Project Number: R2018071
Project Name: Agnes War
Road Name: Option 2a

Agnes Water to Baffle Creek Option 2a (MC02a) - Interim unsealed Gladstone Regional Council Revision Location: **0** 11-Mar-19 Date:

Work Package: Civil Works (Including drainage and retaining Structures):

	work Package: Civil works (including drainage and		ng Su	uctures).	
Item Number	Description	Unit of Measure	Quantity	Unit Rate (\$)	Amount ex GST(\$)
		Mousuis			
1	EROSION AND SEDIMENT CONTROL:				
1.1	Check Dams, rock (Provisional Quantity)	lump sum	530	\$ 216.00	\$ 114,480.00
1.2	Sit / Sediment Fence (Provisional Quantity)	m	10600	\$ 10.87	\$ 115,222.00
2	DRAINAGE STRUCTURES:				
_	Culverts (complete):				
	Supply and installation of concrete pipe culvert components, Class 3, 600mm diameter flush joint with				
2.1	external bands to AS4058 including excavation, bedding and backfill (complete). Cross drainage located	m	11	\$ 15,000.00	\$ 165,000.00
	every 500m spacing along alignment.				
3	EARTHWORKS, PREPARATION:				
	Clearing and grubbing, including removal of building structures, retaining structures, vegetation including				
3.1	mulching to stockpile, concrete structures, water tanks, septic tanks and capping and removal of bore	m2	92200	\$ 1.87	\$ 172,414.00
	equipment (Provisional Quantity as directed)				
3.2	Stripping of topsoil (Provisional Quantity as directed)	m3	9220	\$ 6.65	\$ 61,313.00
3.3	Ground surface treatment under embankment, standard	m2	27660	\$ 1.20	\$ 33,192.00
3.4	Excavation and disposal of Unsuitable Material with individual excavation < 10 m3 (Provisional Quantity	m3	10	\$ 50.00	\$ 500.00
	as directed) Excavation and disposal of Unsuitable Material with individual excavation > 10 m3 (Provisional Quantity				
3.5	as directed)	m3	1700	\$ 16.65	\$ 28,305.00
4	EARTHWORKS, EXCAVATION:				
4.1	Road excavation, all materials	m3	33600	\$ 11.25	\$ 378,000.00
4.2	Excavation of non-rippable material in road excavation, rate additional to rate for Work Item 3201	m3	1700	\$ 60.50	\$ 102,850.00
	(Provisional Quantity)	-		,	, , , , , , , , , , , , , , , , , , , ,
5	EARTHWORKS, EMBANKMENT:				
5.1	Road embankment	m3	20700	\$ 6.95	\$ 143,865.00
0.1	Trodd ombantinon		20,00	ψ 0.00	Ψ 110,000.00
6	EARTHWORKS, SUBGRADE:				
6.1	Testing of existing material below subgrade level in cuttings (Provisional Quantity if ordered)	per set	318	\$ 450.00	\$ 143,100.00
6.2	Subgrade treatment Type A in cuttings (Provisional Quantity if ordered)	m2	55320	\$ 1.75	\$ 96,810.00
7	EARTHWORKS, BACKFILL:				
7.1	Backfill with general backfill material to areas of unsuitable	m3	1700	\$ 70.25	\$ 119,425.00
8	UNBOUND PAVEMENTS:				
8.1	Base Course Type 2.1 200mm (CBR 80)	m3	7080.39	\$ 122.50	\$ 867,348.27
8.2	Sub-base Course Type 2.3 300mm (CBR45)	m3	14187.4		\$ 1,383,267.02
8.3	Geotextile under sub-base pavement	m2	41870	\$ 1.50	
9	SPRAYED BITUMINOUS SURFACING (EXCLUDING EMULSION):				
9.1	Primer seal - AMC00 @ 0.9L/m2	litre	35780		\$ -
9.2	Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2	litre	55650		\$ -
9.3	Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site	m3	370		\$ -
10	REMOVAL, DEMOLITION AND RE-ERECTION:				
10.1	Removal and re-erection of road furniture	lump sum	1	\$ 5,000.00	\$ 5,000.00
.5.1	,	.a.np ouill	<u> </u>	5,000.00	- 0,000.00
11	SUPPLY OF COVER AGGREGATE:				
11.1	Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2	litre	27830		\$ -
11.2	Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site	m3	200		\$ -
,-					
12	LINE MARKING AND SIGNAGE:		15000		¢
12.1 12.2	Spotting only for longitudinal lines Linemarking (white paint complete)	m m	15900 15900		\$ -
12.2	New signs and posts (Complete)	m lump sum	10000	\$ 25,000.00	
12.4	New road edge guid posts (Complete)	No.	200	\$ 25,000.00	\$ 12,000.00
. 2.4			_50	÷ 00.00	- 12,000.00
13	LANDSCAPING:				
13.1	Re-spreading of stockpiled topsoil to depth of 100mm	m2	92200	\$ 3.20	\$ 295,040.00
13.2	Hydromulch grass seeding.	m2	92200	\$ 0.91	\$ 83,902.00
14	MISCELLANEOUS:	_	004.15		
14.1	Retaining structure - Keppel Block including excavation, footing and backfill	m2	694.489		\$ 381,968.95
14.3 14.4	Concrete lined invert / barrier kerb to top of retaining walls Construction of stockpile site	m Each	300 11	\$ 110.00 \$ 2,500.00	\$ 33,000.00 \$ 27,500.00
14.4	W-beam guard rail, ezy-guard posts	m	850	\$ 2,500.00	
14.6	Steel beam guard rail terminal, ET2000 PLUS TL2 terminal	Each	8	\$ 3,910.00	
					,===::00

Total for Civil Works (ex GST): \$4,976,087



Project Number: R2018071 Project Name: Agnes War

Road Name:

Agnes Water to Baffle Creek
Option 2a (MC02a) - Ultimate unsealed
Gladstone Regional Council Location: **0** 11-Mar-19 Revision Date:

Work Package: Civil Works (Including drainage and retaining Structures):

	work Package: Civil works (including drainage and		ng Su	iuciures).		
Item Number	Description	Unit of Measure	Quantity	Unit Rate (\$)	Amo	ount ex GST(\$)
1	EROSION AND SEDIMENT CONTROL:	L	500	¢ 040.00	•	444 400 00
1.1	Check Dams, rock (Provisional Quantity) Silt / Sediment Fence (Provisional Quantity)	lump sum m	530 10600	\$ 216.00 \$ 10.87	\$	114,480.00 115,222.00
1.2	Sit / Sediment Perice (Provisional Quantity)	111	10000	\$ 10.07	Ф	115,222.00
2	DRAINAGE STRUCTURES:					
	Culverts (complete):					
	Supply and installation of concrete pipe culvert components, Class 3, 600mm diameter flush joint with					
2.1	external bands to AS4058 including excavation, bedding and backfill (complete). Cross drainage located	m	11	\$ 15,000.00	\$	165,000.00
	every 500m spacing along alignment.					
3	EARTHWORKS, PREPARATION:					
3	Clearing and grubbing, including removal of building structures, retaining structures, vegetation including					
3.1	mulching to stockpile, concrete structures, water tanks, septic tanks and capping and removal of bore	m2	42400	\$ 1.87	\$	79,288.00
	equipment (Provisional Quantity as directed)				·	
3.2	Stripping of topsoil (Provisional Quantity as directed)	m3	21200	\$ 6.65	\$	140,980.00
3.3	Ground surface treatment under embankment, standard	m2	12720	\$ 1.20	\$	15,264.00
3.4	Excavation and disposal of Unsuitable Material with individual excavation < 10 m3 (Provisional Quantity	m3	10	\$ 50.00	\$	500.00
	as directed) Excavation and disposal of Unsuitable Material with individual excavation > 10 m3 (Provisional Quantity					
3.5	as directed)	m3	2800	\$ 16.65	\$	46,620.00
4	EARTHWORKS, EXCAVATION:					
4.1	Road excavation, all materials	m3	55600	\$ 11.25	\$	625,500.00
4.2	Excavation of non-rippable material in road excavation, rate additional to rate for Work Item 3201	m3	2800	\$ 60.50	\$	169,400.00
	(Provisional Quantity)					
5	EARTHWORKS, EMBANKMENT:					
5.1	Road embankment	m3	16200	\$ 6.95	\$	112,590.00
0.1	Trodd on barninon		10200	ψ 0.00	Ψ	112,000.00
6	EARTHWORKS, SUBGRADE:					
6.1	Testing of existing material below subgrade level in cuttings (Provisional Quantity if ordered)	per set	318	\$ 450.00	\$	143,100.00
6.2	Subgrade treatment Type A in cuttings (Provisional Quantity if ordered)	m2	25440	\$ 1.75	\$	44,520.00
7	EARTHWORKS, BACKFILL:	•	0000	A 70.05	0	100 700 00
7.1	Backfill with general backfill material to areas of unsuitable	m3	2800	\$ 70.25	\$	196,700.00
8	UNBOUND PAVEMENTS:					
8.1	Base Course Type 2.1 200mm (CBR 80)	m3	15067.4	\$ 122.50	S	1,845,751.85
8.2	Sub-base Course Type 2.3 300mm (CBR45)	m3	25852.5	\$ 97.50	\$	2,520,615.14
8.3	Geotextile under sub-base pavement	m2	81620	\$ 1.50	\$	122,430.00
9	SPRAYED BITUMINOUS SURFACING (EXCLUDING EMULSION):					
9.1	Primer seal - AMC00 @ 0.9L/m2	litre	71550		\$	-
9.2	Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2	litre	111290		\$	-
9.3	Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site	m3	730		\$	-
10	REMOVAL, DEMOLITION AND RE-ERECTION:					
10.1	Removal and re-erection of road furniture	lump sum	1	\$ 5,000.00	\$	5,000.00
			<u> </u>	. 0,000.00	_	
11	SUPPLY OF COVER AGGREGATE:					
11.1	Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2	litre	55650		\$	-
11.2	Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site	m3	400		\$	-
	UNIT MADVING AND CIONAGE					
12	LINE MARKING AND SIGNAGE:	e	15000		ď	
12.1 12.2	Spotting only for longitudinal lines Linemarking (white paint complete)	m m	15900 15900		\$	-
12.3	New signs and posts (Complete)	lump sum	1	\$ 25,000.00	\$	25,000.00
12.4	New road edge guid posts (Complete)	No.	200	\$ 60.00		12,000.00
	5 3 [25.00		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
13	LANDSCAPING:					
13.1	Re-spreading of stockpiled topsoil to depth of 100mm	m2	42400	\$ 3.20	\$	135,680.00
13.2	Hydromulch grass seeding.	m2	42400	\$ 0.91	\$	38,584.00
	WOOTH ANTONIO					
14	MISCELLANEOUS:	m?	0		¢	
14.1 14.3	Retaining structure - Keppel Block including excavation, footing and backfill Concrete lined invert / barrier kerb to top of retaining walls	m2 m	240		\$	
14.3	Construction of stockpile site	Each	11	\$ 2,500.00	\$	27,500.00
14.5	W-beam guard rail, ezy-guard posts	m	620	2,000.00	\$	-
14.6	Steel beam guard rail terminal, ET2000 PLUS TL2 terminal	Each	6		\$	-

Total for Civil Works (ex GST): \$6,701,725



Project Number: R2018071 Project Name: Agnes War Agnes Water to Baffle Creek Option 2a (MC02a) - Ultimate sealed Gladstone Regional Council Road Name: Location:

0 11-Mar-19 Revision Date:

Work Package: Civil Works (Including drainage and retaining Structures):

	Work Package: Civil Works (Including drainage and	retaini	ng St	ructures):		
Item Number	Description	Unit of Measure	Quantity		Amo	ount ex GST(\$)
_						
<u>1</u> 1.1	EROSION AND SEDIMENT CONTROL: Check Dams, rock (Provisional Quantity)	lump cum	520	\$ 216.00	©	11/ /90 00
1.1	Silt / Sediment Fence (Provisional Quantity)	lump sum m	530 10600	\$ 216.00 \$ 10.87	\$	114,480.00 115,222.00
1.2	one occument choc (Frovisional equating)	- 111	10000	Ψ 10.07	Ψ	110,222.00
2	DRAINAGE STRUCTURES:					
	Culverts (complete):					
0.4	Supply and installation of concrete pipe culvert components, Class 3, 600mm diameter flush joint with			45,000,00		105 000 00
2.1	external bands to AS4058 including excavation, bedding and backfill (complete). Cross drainage located every 500m spacing along alignment.	m	11	\$ 15,000.00	\$	165,000.00
	every soom spacing along alignment.					
3	EARTHWORKS, PREPARATION:					
	Clearing and grubbing, including removal of building structures, retaining structures, vegetation including					
3.1	mulching to stockpile, concrete structures, water tanks, septic tanks and capping and removal of bore	m2	42400	\$ 1.87	\$	79,288.00
3.2	equipment (Provisional Quantity as directed) Stripping of topsoil (Provisional Quantity as directed)	m3	21200	\$ 6.65	\$	140,980.00
3.3	Ground surface treatment under embankment, standard	m2	12720	\$ 1.20	\$	15,264.00
3.4	Excavation and disposal of Unsuitable Material with individual excavation < 10 m3 (Provisional Quantity	m3	10	\$ 50.00	\$	500.00
3.4	as directed)	IIIO	10	\$ 50.00	φ	300.00
3.5	Excavation and disposal of Unsuitable Material with individual excavation > 10 m3 (Provisional Quantity	m3	2800	\$ 16.65	\$	46,620.00
	as directed)					
4	EARTHWORKS, EXCAVATION:					
4.1	Road excavation, all materials	m3	55600	\$ 11.25	\$	625,500.00
4.2	Excavation of non-rippable material in road excavation, rate additional to rate for Work Item 3201	m3	2800	\$ 60.50	\$	169,400.00
1.2	(Provisional Quantity)		2000	ψ 00.00	Ψ	100,100.00
	EARTHWORKS, EMBANKMENT:					
5 5.1	Road embankment	m3	16200	\$ 6.95	\$	112,590.00
0.1	TOOK ON SUNTON	1110	10200	ψ 0.55	Ψ	112,000.00
6	EARTHWORKS, SUBGRADE:					
6.1	Testing of existing material below subgrade level in cuttings (Provisional Quantity if ordered)	per set	318	\$ 450.00	\$	143,100.00
6.2	Subgrade treatment Type A in cuttings (Provisional Quantity if ordered)	m2	25440	\$ 1.75	\$	44,520.00
	EARTHWORKS BASKEN					
7 7.1	EARTHWORKS, BACKFILL: Backfill with general backfill material to areas of unsuitable	m3	2800	\$ 70.25	\$	196,700.00
7.1	Dackilli With general backilli material to areas of unsultable	1110	2000	Ψ 10.23	Ψ	130,700.00
8	UNBOUND PAVEMENTS:					
8.1	Base Course Type 2.1 200mm (CBR 80)	m3	15067.4	\$ 122.50	\$	1,845,751.85
8.2	Sub-base Course Type 2.3 300mm (CBR45)	m3	25852.5	\$ 97.50	\$	2,520,615.14
8.3	Geotextile under sub-base pavement	m2	81620	\$ 1.50	\$	122,430.00
9	SPRAYED BITUMINOUS SURFACING (EXCLUDING EMULSION):					
9.1	Primer seal - AMC00 @ 0.9L/m2	litre	71550	\$ 1.95	\$	139,522.50
9.2	Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2	litre	111290	\$ 1.95	\$	217,015.50
9.3	Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site	m3	730	\$ 202.50	\$	147,825.00
10	REMOVAL, DEMOLITION AND RE-ERECTION:					
10.1	Removal and re-erection of road furniture	lump sum	1	\$ 5,000.00	\$	5,000.00
11	SUPPLY OF COVER AGGREGATE:				 	
11.1	Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2	litre	55650	\$ 2.00	\$	111,300.00
11.2	Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site	m3	400	\$ 218.50	\$	87,400.00
-						
12	LINE MARKING AND SIGNAGE:					
12.1	Spotting only for longitudinal lines	m	15900	\$ 0.50	\$	7,950.00
12.2 12.3	Linemarking (white paint complete) New signs and posts (Complete)	m lump sum	15900	\$ 1.45 \$ 25,000.00		23,055.00 25,000.00
12.4	New road edge guid posts (Complete)	No.	200	\$ 25,000.00		12,000.00
				. 55.00	Ť	,000.00
13	LANDSCAPING:					_
13.1	Re-spreading of stockpiled topsoil to depth of 100mm	m2	42400	\$ 3.20	\$	135,680.00
13.2	Hydromulch grass seeding.	m2	42400	\$ 0.91	\$	38,584.00
4.4	MICCELL ANEQUE.	-	-		-	
14	MISCELLANEOUS: Retaining structure - Keppel Block including excavation, footing and backfill	m2	0		\$	
141	proteining on actain - repper block including excavation, footing and backing	1112	U			
14.1 14.3		m	240		\$	-
14.1 14.3 14.4	Concrete lined invert / barrier kerb to top of retaining walls Construction of stockpile site	m Each	240 11	\$ 2,500.00	\$	27,500.00
14.3	Concrete lined invert / barrier kerb to top of retaining walls			\$ 2,500.00		

Total for Civil Works (ex GST): \$7,435,793



Project Number: R2018071

Project Name: Road Name:

Agnes Water to Baffle Creek Option 3a (MC03a) - Interim unsealed Gladstone Regional Council Location: Revision 0 11-Mar-19 Date:

Work Package: Civil Works (Including drainage and retaining Structures):

	Work Package: Civil Works (Including drainage and	retaini	ng Sti	ructures):	
Item Number	Description	Unit of Measure	Quantity	Unit Rate (\$)	Amount ex GST(\$)
1	EROSION AND SEDIMENT CONTROL:				
1.1	Check Dams, rock (Provisional Quantity)	lump sum	510	\$ 216.00	\$ 110,160.00
1.2	Silt / Sediment Fence (Provisional Quantity)	m	10200	\$ 10.87	\$ 110,874.00
2	DRAINAGE STRUCTURES:				
	Culverts (complete): Supply and installation of concrete pipe culvert components, Class 3, 600mm diameter flush joint with				
2.1	external bands to AS4058 including excavation, bedding and backfill (complete). Cross drainage located	m	11	\$ 15,000.00	\$ 165,000.00
	every 500m spacing along alignment.			,	,
3	EARTHWORKS, PREPARATION:				
3.1	Clearing and grubbing, including removal of building structures, retaining structures, vegetation including mulching to stockpile, concrete structures, water tanks, septic tanks and capping and removal of bore	m2	90200	\$ 1.87	\$ 168,674.00
0.1	equipment (Provisional Quantity as directed)		00200	• 1.01	Ψ 100,07 1100
3.2	Stripping of topsoil (Provisional Quantity as directed)	m3	45100	\$ 6.65	\$ 299,915.00
3.3	Ground surface treatment under embankment, standard	m2	27060	\$ 1.20	\$ 32,472.00
3.4	Excavation and disposal of Unsuitable Material with individual excavation < 10 m3 (Provisional Quantity as directed)	m3	10	\$ 50.00	\$ 500.00
0.5	Excavation and disposal of Unsuitable Material with individual excavation > 10 m3 (Provisional Quantity	_	4000		A 04 005 00
3.5	as directed)	m3	1900	\$ 16.65	\$ 31,635.00
4	EARTHWORKS, EXCAVATION:	?	27400	¢ 44.05	\$ 420,750.00
4.1	Road excavation, all materials Excavation of non-rippable material in road excavation, rate additional to rate for Work Item 3201	m3	37400	\$ 11.25	
4.2	(Provisional Quantity)	m3	1900	\$ 60.50	\$ 114,950.00
5	EARTHWORKS, EMBANKMENT:				
5.1	Road embankment	m3	10100	\$ 6.95	\$ 70,195.00
6	EARTHWORKS, SUBGRADE:				
6.1	Testing of existing material below subgrade level in cuttings (Provisional Quantity if ordered)	per set	306	\$ 450.00	\$ 137,700.00
6.2	Subgrade treatment Type A in cuttings (Provisional Quantity if ordered)	m2	54120	\$ 1.75	\$ 94,710.00
7	EARTHWORKS, BACKFILL:				
7.1	Backfill with general backfill material to areas of unsuitable	m3	1900	\$ 70.25	\$ 133,475.00
8	UNBOUND PAVEMENTS:				
8.1	Base Course Type 2.1 200mm (CBR 80)	m3	6520.41	\$ 122.50	\$ 798,750.59
8.2	Sub-base Course Type 2.3 300mm (CBR45)	m3	13248.7	\$ 97.50	\$ 1,291,744.74
8.3	Geotextile under sub-base pavement	m2	40290	\$ 1.50	\$ 60,435.00
9	SPRAYED BITUMINOUS SURFACING (EXCLUDING EMULSION): Primer seal - AMC00 @ 0.9L/m2	litre	34340		\$ -
9.2	Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2	litre	53420		\$ -
9.3	Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site	m3	350		\$ -
	117 1 0 00 0 1 7				
10	REMOVAL, DEMOLITION AND RE-ERECTION:				
10.1	Removal and re-erection of road furniture	lump sum	1	\$ 5,000.00	\$ 5,000.00
11	SUPPLY OF COVER AGGREGATE:				
11.1	Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2	litre	26710		\$ -
11.2	Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site	m3	200		\$ -
12	LINE MARKING AND SIGNAGE:				
12.1	Spotting only for longitudinal lines	m m	15270		\$ -
12.2 12.3	Linemarking (white paint complete) New signs and posts (Complete)	m lump sum	15270	\$ 25,000.00	\$ -
12.4	New road edge guid posts (Complete)	No.	200	\$ 60.00	\$ 12,000.00
13	LANDSCAPING:				
13.1	Re-spreading of stockpiled topsoil to depth of 100mm	m2	90200	\$ 3.20	\$ 288,640.00
13.2	Hydromulch grass seeding.	m2	90200	\$ 0.91	\$ 82,082.00
14	MISCELLANEOUS:				
14.1	Retaining structure - Keppel Block including excavation, footing and backfill	m2	570.342	\$ 550.00	\$ 313,688.10
14.3	Concrete lined invert / barrier kerb to top of retaining walls	m	130	\$ 110.00	\$ 14,300.00
14.4	Construction of stockpile site	Each	11	\$ 2,500.00	\$ 27,500.00
14.5	W-beam guard rail, ezy-guard posts	m .	0	\$ 110.00	\$ -
14.6	Steel beam guard rail terminal, ET2000 PLUS TL2 terminal	Each	0	\$ 3,910.00	\$ -

Total for Civil Works (ex GST): \$4,810,150



Project Number: R2018071 Project Name: Agnes War

Road Name:

Agnes Water to Baffle Creek Option 3a (MC3a) - Ultimate unsealed Gladstone Regional Council Location: **0** 11-Mar-19 Revision Date:

Work Package: Civil Works (Including drainage and retaining Structures):

	Work Package: Civil Works (Including drainage and	retaini	ng Sti	ructures):	
Item Number	Description	Unit of Measure	Quantity		Amount ex GST(\$)
<u>1</u> 1.1	EROSION AND SEDIMENT CONTROL: Check Dams, rock (Provisional Quantity)	lump sum	510	\$ 216.00	\$ 110,160.00
1.2	Silt / Sediment Fence (Provisional Quantity)	m m	10200	\$ 10.87	\$ 110,160.00
	Sitt Southern Stock (Tortolonal Adams))		10200	Ψ 10.01	Ψ 110,011.00
2	DRAINAGE STRUCTURES:				
	Culverts (complete):				
2.1	Supply and installation of concrete pipe culvert components, Class 3, 600mm diameter flush joint with external bands to AS4058 including excavation, bedding and backfill (complete). Cross drainage located	m	11	\$ 15,000.00	\$ 165,000.00
2.1	every 500m spacing along alignment.	""		Ψ 15,000.00	Ψ 105,000.00
3	EARTHWORKS, PREPARATION:				
3.1	Clearing and grubbing, including removal of building structures, retaining structures, vegetation including	m2	41100	\$ 1.87	\$ 76,857.00
3.1	mulching to stockpile, concrete structures, water tanks, septic tanks and capping and removal of bore equipment (Provisional Quantity as directed)	1112	41100	φ 1.0 <i>1</i>	\$ 70,007.00
3.2	Stripping of topsoil (Provisional Quantity as directed)	m3	20550	\$ 6.65	\$ 136,657.50
3.3	Ground surface treatment under embankment, standard	m2	12330	\$ 1.20	\$ 14,796.00
3.4	Excavation and disposal of Unsuitable Material with individual excavation < 10 m3 (Provisional Quantity	m3	10	\$ 50.00	\$ 500.00
	as directed) Excavation and disposal of Unsuitable Material with individual excavation > 10 m3 (Provisional Quantity				
3.5	as directed)	m3	3200	\$ 16.65	\$ 53,280.00
4	EARTHWORKS, EXCAVATION:				
4.1	Road excavation, all materials	m3	63200	\$ 11.25	\$ 711,000.00
4.2	Excavation of non-rippable material in road excavation, rate additional to rate for Work Item 3201 (Provisional Quantity)	m3	3200	\$ 60.50	\$ 193,600.00
	(in the state of t				
5	EARTHWORKS, EMBANKMENT:				
5.1	Road embankment	m3	8100	\$ 6.95	\$ 56,295.00
•	FARTHWORKS SURGRADE.				
6 6.1	EARTHWORKS, SUBGRADE: Testing of existing material below subgrade level in cuttings (Provisional Quantity if ordered)	per set	306	\$ 450.00	\$ 137,700.00
6.2	Subgrade treatment Type A in cuttings (Provisional Quantity if ordered)	m2	24660	\$ 1.75	\$ 43,155.00
					, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
7	EARTHWORKS, BACKFILL:				
7.1	Backfill with general backfill material to areas of unsuitable	m3	3200	\$ 70.25	\$ 224,800.00
8	UNBOUND PAVEMENTS:				
8.1	Base Course Type 2.1 200mm (CBR 80)	m3	14442.8	\$ 122.50	\$ 1,769,241.53
8.2	Sub-base Course Type 2.3 300mm (CBR45)	m3	24719.7	\$ 97.50	\$ 2,410,166.56
8.3	Geotextile under sub-base pavement	m2	78540	\$ 1.50	\$ 117,810.00
9	SPRAYED BITUMINOUS SURFACING (EXCLUDING EMULSION):	Ea	00000		¢
9.1 9.2	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2	litre litre	68680 106830		
9.3	Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site	m3	700		\$ -
***	этру жи эргээлий тэм эдд эдэгэ жий, хам жий ха				·
10	REMOVAL, DEMOLITION AND RE-ERECTION:				
10.1	Removal and re-erection of road furniture	lump sum	1	\$ 5,000.00	\$ 5,000.00
11	SUPPLY OF COVER AGGREGATE:				
11 11.1	Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2	litre	53420		\$ -
11.2	Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site	m3	390		\$ -
12	LINE MARKING AND SIGNAGE:				
12.1	Spotting only for longitudinal lines	m	15270		\$
12.2 12.3	Linemarking (white paint complete) New signs and posts (Complete)	m lump sum	15270	\$ 25,000.00	\$ - \$ 25,000.00
12.4	New road edge guid posts (Complete)	No.	200	\$ 25,000.00	\$ 12,000.00
	5 5 . · · · · · · · · · · · · · · · · ·				
13	LANDSCAPING:				
13.1	Re-spreading of stockpiled topsoil to depth of 100mm	m2	41100	\$ 3.20	\$ 131,520.00
13.2	Hydromulch grass seeding.	m2	41100	\$ 0.91	\$ 37,401.00
14	MISCELLANEOUS:				
14.1	Retaining structure - Keppel Block including excavation, footing and backfill	m2			\$ -
14.3	Concrete lined invert / barrier kerb to top of retaining walls	m	140		\$ -
14.4	Construction of stockpile site	Each	11	\$ 2,500.00	\$ 27,500.00
14.5	W-beam guard rail, ezy-guard posts	m	0		\$ -
14.6	Steel beam guard rail terminal, ET2000 PLUS TL2 terminal	Each	0		\$ -

Total for Civil Works (ex GST): \$6,570,314



Project Number: R2018071 Project Name: Agnes War Agnes Water to Baffle Creek Option 3a (MC3a) - Ultimate sealed Gladstone Regional Council Road Name: Location:

0 11-Mar-19 Revision Date:

Work Package: Civil Works (Including drainage and retaining Structures):

		Work Package: Civil Works (Including drainage and	retaini	ng Sti	ructures):		
PROSEIN AND SEDMENT CONTROL:	Item Number		Unit of			Amo	ount ex GST(\$)
1.1 Check Dame, rock (Provisional Quantity)							
1.2 SIL/Sediment From Provision Quantity			lump cum	E10	¢ 216.00	¢	110 160 00
Content Complete						_	110,160.00
Columna (complete):	1.2	Only deditional onder (1 Toylolohar adamaty)		10200	Ψ 10.07	Ψ	110,014.00
Supply and installation of concrete pipe cubert components, Class 3, 6000m diameter liable joint with element launch to A45008 pictures operation, bodding and backfull (comprehe), Cross drainage located every 500m appears along alignment. Supply and installation of concrete pipe cubert components of the componen	2	DRAINAGE STRUCTURES:					
### 2.1 elemental bards to AS4088 reclusing excavation, bedding and backfill (complete), Cross drainings broated ### 11. \$ 15,000.00 \$ 165,00 \$ 165		Culverts (complete):					
Service Some special galangement Service						_	
BARTHWORKS, PREPARATION:	2.1		m	11	\$ 15,000.00	\$	165,000.00
Conting and gubbing, including servolves, operations tractures, weather tanks, spelt banks and capping and removal of bore insulpment (Provisional Quartity) is directed) 3.2		every 500m spacing along alignment.					
Clearing and grubbing, including enrowal of building structures, relations appropriated in mulciling to stockley, concrete services, water trans, especiatives and capping and removal of bore experiment (Provisional Cuantity) as directed)	3	EARTHWORKS, PREPARATION:					
Regipment (Provisional Cuarriety as directeds)		Clearing and grubbing, including removal of building structures, retaining structures, vegetation including					
3.2 Stripping of topical (Provisional Quartety as directed)	3.1		m2	41100	\$ 1.87	\$	76,857.00
3.3 Ground surface treatment under enhankment, standard Excavation and disposal of Unsulable Material with individual excavation < 10 m3 (Provisional Quantity m3 10 5 50.00	2.2		m2	20550	Ф 6.6E	ď	120 057 50
3.4 Ecavarian and disposal of Unsuitable Malerial with individual excavation < 10 m3 (Provisional Quantity) m3 10 \$ 5,000 \$ 5						-	14,796.00
3.4 Be afferched Security							
### A generation of non-ripopable material in road excavation, rate additional to rate for Work Item 3201 m3 3200 \$ 11.25 \$ 711.00 ### A generation of non-ripopable material in road excavation, rate additional to rate for Work Item 3201 m3 3200 \$ 60.50 \$ 133,60 ### A generation of non-ripopable material in road excavation, rate additional to rate for Work Item 3201 m3 3200 \$ 60.50 \$ 133,60 ### A generation of non-ripopable material in road excavation, rate additional to rate for Work Item 3201 m3 3200 \$ 60.50 \$ 58,29 ### A generation of non-ripopable material in road excavation, rate additional to rate for Work Item 3201 m3 3200 \$ 60.50 \$ 58,29 ### A generation of the state of the	3.4		m3	10	\$ 50.00	\$	500.00
### BARTHWORKS, EXCAVATION: ### Condexionation, and materials ### Condexionation, and materials ### Condexionation, and materials ### Condexionation (an institute of the materials) ### Condexionation (and institute of the materials) ### Condexio	3.5		m3	3200	\$ 16.65	\$	53,280.00
4.1 Road excavation, all materials Excavation of non-ripoptible material in road excavation, rate additional to rate for Work Item 3201 m3 3200 \$ 60.50 \$ 193.60 \$ 19	0.0	as directed)	1110	0200	Ψ 10.00	9	00,200.00
4.1 Road excavation, all materials Excavation of non-ripoptible material in road excavation, rate additional to rate for Work Item 3201 m3 3200 \$ 60.50 \$ 193.60 \$ 19		EARTHWORKS EVOAVATION.					
A 2 Exavarition of non-rippable material in road excavation, rate additional to rate for Work Item 3201 m3 3200 \$ 60.50 \$ 193.60			m3	63200	¢ 11.25	\$	711 000 00
### A.2 (Provisional Quantity)						-	
Section	4.2		m3	3200	\$ 60.50	\$	193,600.00
Section							
B							
6.1 Testing of existing material below subgrade level in cuttings (Provisional Quantity if ordered) per set 306 \$ 450.00 \$ 137.70 6.2 Subgrade treatment Type A in cuttings (Provisional Quantity if ordered) m2 24660 \$ 1.75 \$ 43,15 7	5.1	Road embankment	m3	8100	\$ 6.95	\$	56,295.00
6.1 Testing of existing material below subgrade level in cuttings (Provisional Quantity if ordered)	6	EARTHWORKS SURCEADE:					
6.2 Subgrade treatment Type A in cuttings (Provisional Quantity if ordered)		·	ner set	306	\$ 450.00	\$	137,700.00
T			_			\$	43,155.00
Removal_pendinge	-	3-7					
B	7	EARTHWORKS, BACKFILL:					
Base Course Type 2.1 200mm (CBR 80)	7.1	Backfill with general backfill material to areas of unsuitable	m3	3200	\$ 70.25	\$	224,800.00
Base Course Type 2.1 200mm (CBR 80)							
8.2 Sub-base Course Type 2.3 300mm (CBR45)			m2	14442.0	¢ 400.50	ď.	1 760 044 50
8.3 Geotextile under sub-base pavement						\$	2,410,166.56
SPRAYED BITUMINOUS SURFACING (EXCLUDING EMULSION): 9.1					•	_	117,810.00
9.1 Primer seal - AMC00 @ 0.9L/m2 litre							,
Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2	9	SPRAYED BITUMINOUS SURFACING (EXCLUDING EMULSION):					
9.3 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site 10 REMOVAL, DEMOLITION AND RE-ERECTION: 10.1 Removal and re-erection of road furniture 10.1 Lump sum 10.1 Supply OF COVER AGGREGATE: 11.1 Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 11.2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site 11.2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site 11.2 LINE MARKING AND SIGNAGE: 11.2 Linemarking only for longitudinal lines 11.2 Linemarking (white paint complete) 11.2 Linemarking (white paint complete) 11.3 New signs and posts (Complete) 11.4 New road edge guid posts (Complete) 11.4 New road edge guid posts (Complete) 11.5 LANDSCAPING: 11.1 Re-spreading of stockpiled topsoil to depth of 100mm 11.5 LANDSCAPING: 11.6 MISCELLANEOUS: 11.7 Semoval and re-erection of road furniture 11.8 Land Spotting structure - Keppel Block including excavation, footing and backfill 11.4 Retaining structure - Keppel Block including was a post of the pretaining walls 11.4 Construction of stockpile site 11.4 Construction of stockpile site 11.5 Supply and spreading on site of road furniture 11.6 Supply and spreading of stockpile site 11.7 Supply and spreading structure - Keppel Block including excavation, footing and backfill 11.6 Supply and spreading structure - Keppel Block including excavation, footing and backfill 11.6 Construction of stockpile site 11.7 Supply and spreading structure - Keppel Block including excavation, footing and backfill 11.8 Construction of stockpile site 11.9 Supply and spreading structure - Keppel Block including excavation, footing and backfill 11.8 Supply and spreading structure - Keppel Block including excavation, footing and backfill 11.8 Supply and spreading structure - Keppel Block including excavation, footing and backfill 11.8 Supply and spreading structure - Keppel Block including excavation, footing and backfill 11.7 Supply and spreading structure - Keppel Block including excavation, footing and backfill 11.8 Supply and sprea							133,926.00
10 REMOVAL, DEMOLITION AND RE-ERECTION: 10.1 Removal and re-erection of road furniture 1 \$ 5,000.00 \$ 5,000 \$ 5,000 \$ 1 \$ 5,000.00 \$ 5,000 \$ 5,000 \$ 1 \$ 5,000.00 \$ 5,000 \$ 1 \$ 5,000.00 \$ 5,000 \$ 1 \$ 5,000.00 \$ 5,000 \$ 1 \$ 5,000.00 \$ 5,000 \$ 1 \$ 5,000.00 \$ 5,000 \$ 1 \$ 5,000.00 \$ 5,000 \$ 1 \$ 5,000.00 \$ 5,000 \$ 1,000.00						-	208,318.50
10.1 Removal and re-erection of road furniture lump sum 1 \$ 5,000.00 \$ 5,000	9.3	Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site	m3	700	\$ 202.50	\$	141,750.00
10.1 Removal and re-erection of road furniture lump sum 1 \$ 5,000.00 \$ 5,000	10	REMOVAL DEMOLITION AND RE-ERECTION:					
11 SUPPLY OF COVER AGGREGATE:			lump sum	1	\$ 5,000.00	\$	5,000.00
11.1 Seal (2nd Coat) - PMB (\$0.7\$) @ 0.7L/m2 litre 53420 \$ 2.00 \$ 106,84						Ľ	
11.2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site m3 390 \$ 218.50 \$ 85.21							-
12 LINE MARKING AND SIGNAGE:						\$	106,840.00
12.1 Spotting only for longitudinal lines m 15270 \$ 0.50 \$ 7,63 12.2 Linemarking (white paint complete) m 15270 \$ 1.45 \$ 22,14 12.3 New signs and posts (Complete) lump sum 1 \$ 25,000.00 \$ 25,000 \$ 5,000 \$ 25,000 \$ 60.00 \$ 12,00 13 LANDSCAPING: No. 200 \$ 60.00 \$ 12,00 13.1 Re-spreading of stockpiled topsoil to depth of 100mm m2 41100 \$ 3.20 \$ 131,52 13.2 Hydromulch grass seeding. m2 41100 \$ 0.91 \$ 37,40 14 MISCELLANEOUS: 14.1 Retaining structure - Keppel Block including excavation, footing and backfill m2 \$ \$ 14.3 Concrete lined invert / barrier kerb to top of retaining walls m 140 \$ \$ 14.4 Construction of stockpile site Each 11 \$ 2,500.00	11.2	Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site	m3	390	\$ 218.50	\$	85,215.00
12.1 Spotting only for longitudinal lines m 15270 \$ 0.50 \$ 7,63 12.2	12	I INE MARKING AND SIGNAGE:				-	
12.2 Linemarking (white paint complete) m 15270 \$ 1.45 \$ 22,14 12.3 New signs and posts (Complete) lump sum 1 \$ 25,000.00 \$ 25,000 12.4 New road edge guid posts (Complete) No. 200 \$ 60.00 \$ 12,000 13 LANDSCAPING:			m	15270	\$ 0.50	\$	7,635.00
12.3 New signs and posts (Complete) lump sum 1 \$ 25,000.00 \$ 25,000 \$ 12,40 New road edge guid posts (Complete) No. 200 \$ 60.00 \$ 12,000 \$ 12,000 \$ 12,000 \$ 13,100						_	22,141.50
12.4 New road edge guid posts (Complete) No. 200 \$ 60.00 \$ 12,00 13 LANDSCAPING: 13.1 Re-spreading of stockpiled topsoil to depth of 100mm m2 41100 \$ 3.20 \$ 131,52 13.2 Hydromulch grass seeding. m2 41100 \$ 0.91 \$ 37,40 14 MISCELLANEOUS: m2 41100 \$ 0.91 \$				1			25,000.00
13.1 Re-spreading of stockpiled topsoil to depth of 100mm m2 41100 \$ 3.20 \$ 131,52 13.2 Hydromulch grass seeding. m2 41100 \$ 0.91 \$ 37,40 14.1 Retaining structure - Keppel Block including excavation, footing and backfill m2 \$ \$ 14.3 Concrete lined invert / barrier kerb to top of retaining walls m 140 \$ \$ 14.4 Construction of stockpile site Each 11 \$ 2,500.00 \$ 27,500	12.4		No.	200	\$ 60.00	\$	12,000.00
13.1 Re-spreading of stockpiled topsoil to depth of 100mm m2 41100 \$ 3.20 \$ 131,52 13.2 Hydromulch grass seeding. m2 41100 \$ 0.91 \$ 37,40 14.1 Retaining structure - Keppel Block including excavation, footing and backfill m2 \$ \$ 14.3 Concrete lined invert / barrier kerb to top of retaining walls m 140 \$ \$ 14.4 Construction of stockpile site Each 11 \$ 2,500.00 \$ 27,500							
13.2 Hydromulch grass seeding.				41400	¢ 222	6	121 500 00
14 MISCELLANEOUS: ## Construction of stockpile site ## Page 14.1 ## Page 14.2 \$ Concrete lined invert / barrier kerb to top of retaining walls ## May 14.0 \$ Construction of stockpile site ## Page 14.2						_	131,520.00 37,401.00
14.1 Retaining structure - Keppel Block including excavation, footing and backfill m2 \$ 14.3 Concrete lined invert / barrier kerb to top of retaining walls m 14.0 \$ 14.4 Construction of stockpile site Each 11 \$ 2,500.00 \$	13.2	priyaromaion grass seeding.	IIIZ	41100	ψ 0.91	φ	37,401.00
14.1 Retaining structure - Keppel Block including excavation, footing and backfill m2 \$ 14.3 Concrete lined invert / barrier kerb to top of retaining walls m 14.0 \$ 14.4 Construction of stockpile site Each 11 \$ 2,500.00 \$	14	MISCELLANEOUS:					
14.3 Concrete lined invert / barrier kerb to top of retaining walls m 140 \$ 14.4 Construction of stockpile site Each 11 \$ 2,500.00 \$ 27,50			m2			\$	-
	14.3	Concrete lined invert / barrier kerb to top of retaining walls				_	-
14.5 IW-beam guard rail, ezv-guard posts					\$ 2,500.00		27,500.00
14.6 Steel beam guard rail terminal, ET2000 PLUS TL2 terminal Each 0 \$	14.5	W-beam guard rail, ezy-guard posts	m	0		\$	-

Total for Civil Works (ex GST): \$7,276,140



Project Number: R2018071 Project Name: Agnes War Agnes Water to Baffle Creek
Option 4 (MC04) - Interim unsealed
Gladstone Regional Council Road Name: Location:

Revision Date: **0** 11-Mar-19

Work Package: Civil Works (Including drainage and retaining Structures):

Item Number	Description	Unit of	Quantity	Unit Rate (\$)	Am	ount ex GST(
nem vumber	Description	Measure	Quartity	Omit Nate (3)	A111	Juin ex Gory.
1	EROSION AND SEDIMENT CONTROL:					
1.1	Check Dams, rock (Provisional Quantity)	lump sum	1080	\$ 216.00	\$	233,280.0
1.2	Silt / Sediment Fence (Provisional Quantity)	m	21600	\$ 10.87	_	234,792.0
··-	()			, , , , ,	Ť	
2	DRAINAGE STRUCTURES:					
	Culverts (complete):					
	Supply and installation of concrete pipe culvert components, Class 3, 600mm diameter flush joint with					
2.1	external bands to AS4058 including excavation, bedding and backfill (complete). Cross drainage located	m	22	\$ 15,000.00	\$	330,000.0
	every 500m spacing along alignment.				+	
	Other:					
2.2	DAF Red classification floodway crossings	Each	1	\$ 400,000.00	\$	400,000.0
	, ,					•
3	EARTHWORKS, PREPARATION:					
	Clearing and grubbing, including removal of building structures, retaining structures, vegetation including					
3.1	mulching to stockpile, concrete structures, water tanks, septic tanks and capping and removal of bore	m2	179500	\$ 1.87	\$	335,665.0
3.2	equipment (Provisional Quantity as directed) Stripping of topsoil (Provisional Quantity as directed)	m3	89750	\$ 6.65	\$	596,837.5
3.3	Ground surface treatment under embankment, standard	m2	53850	\$ 1.20		64,620.0
	Excavation and disposal of Unsuitable Material with individual excavation < 10 m3 (Provisional Quantity					
3.4	as directed)	m3	10	\$ 50.00	\$	500.0
3.5	Excavation and disposal of Unsuitable Material with individual excavation > 10 m3 (Provisional Quantity	m3	2000	\$ 16.65	\$	33,300.0
	as directed)			*	Ť	,
4	EARTHWORKS, EXCAVATION:				+	
4.1	Road excavation, all materials	m3	39900	\$ 11.25	\$	448,875.0
	Excavation of non-rippable material in road excavation, rate additional to rate for Work Item 3201					
4.2	(Provisional Quantity)	m3	2000	\$ 60.50	\$	121,000.0
5	EARTHWORKS, EMBANKMENT:					
5.1	Road embankment	m3	31700	\$ 6.95	\$	220,315.0
6	 EARTHWORKS.SUBGRADE:				-	
6.1	Testing of existing material below subgrade level in cuttings (Provisional Quantity if ordered)	per set	647	\$ 450.00	\$	291,150.0
6.2	Subgrade treatment Type A in cuttings (Provisional Quantity if ordered)	m2	107700	\$ 1.75		188,475.0
					Ť	,
7	EARTHWORKS, BACKFILL:					
7.1	Backfill with general backfill material to areas of unsuitable	m3	2000	\$ 70.25	\$	140,500.0
8	UNBOUND PAVEMENTS:		110011	A 400.50		1 750 001 0
8.1	Base Course Type 2.1 200mm (CBR 80)	m3	14304.4	\$ 122.50 \$ 97.50		1,752,294.6 2,786,418.5
8.2 8.3	Sub-base Course Type 2.3 300mm (CBR45) Geotextile under sub-base pavement	m3 m2	28578.7 85320	\$ 97.50 \$ 1.50		127,980.0
0.0	Social and the same same partitions		00020	Ψ 1.00	<u> </u>	121,000.0
9	SPRAYED BITUMINOUS SURFACING (EXCLUDING EMULSION):					
9.1	Primer seal - AMC00 @ 0.9L/m2	litre	72740		\$	-
9.2	Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2	litre	113140		\$	-
9.3	Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site	m3	740		\$	-
40	REMOVAL, DEMOLITION AND RE-ERECTION:					
10 10.1	Removal, Democition and Re-ERECTION: Removal and re-erection of road furniture	lump sum	-1	\$ 5,000.00	\$	5,000.0
10.1	Removal and re-election of road furniture	iump sum		\$ 5,000.00	φ	5,000.0
11	SUPPLY OF COVER AGGREGATE:				1	
11.1	Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2	litre	56570		\$	-
11.2	Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site	m3	410		\$	-
12	LINE MARKING AND SIGNAGE:					
12.1	Spotting only for longitudinal lines	m	32330		\$	-
12.2 12.3	Linemarking (white paint complete) New signs and posts (Complete)	m lump sum	32330	\$ 25,000.00	\$	25,000.0
12.4	New road edge guid posts (Complete)	No.	300	\$ 25,000.00		18,000.0
			550	50.00	Ψ	.0,000.0
13	LANDSCAPING:				L	
13.1	Re-spreading of stockpiled topsoil to depth of 100mm	m2	179500	\$ 3.20		574,400.0
13.2	Hydromulch grass seeding.	m2	179500	\$ 0.91	\$	163,345.0
14	MISCELLANEOUS:		004			F00 0
	Retaining structure - Keppel Block including excavation, footing and backfill	m2	961.561	\$ 550.00		528,858.5 39.600.0
14.1	Congrete lined invest / barrier kerb to top of retaining walls					
14.3	Concrete lined invert / barrier kerb to top of retaining walls Construction of stockoile site	m Fach	360	\$ 110.00 \$ 2,500.00		
	Concrete lined invert / barrier kerb to top of retaining walls Construction of stockpile site W-beam guard rail, ezy-guard posts	Each m	22 1700	\$ 110.00 \$ 2,500.00 \$ 110.00	\$	55,000.0 187,000.0

Total for Civil Works (ex GST): \$9,972,586



Project Number: R2018071 Project Name: Agnes War

Road Name:

Agnes Water to Baffle Creek Option 4A (MC04A) - Ultimate unsealed Gladstone Regional Council Revision Date: Location: **0** 11-Mar-19

Work Package: Civil Works (Including drainage and retaining Structures):

Item Number	Description	Unit of	Quantity	Unit Rate (\$)	Am	ount ex GST(
item number	Description	Measure	Quantity	Unit Kate (3)	AIII	ouin ex GST(3
1	EROSION AND SEDIMENT CONTROL:	L	4000	r 040.00	Φ.	200 200 0
1.1 1.2	Check Dams, rock (Provisional Quantity) Silt / Sediment Fence (Provisional Quantity)	lump sum	1020 20400	\$ 216.00 \$ 10.87	_	220,320.0
1.2	Sitt/ Sediment Perice (Provisional Quantity)	m	20400	\$ 10.67	Þ	221,740.0
2	DRAINAGE STRUCTURES:					
	Culverts (complete):					
	Supply and installation of concrete pipe culvert components, Class 3, 600mm diameter flush joint with					
2.1	external bands to AS4058 including excavation, bedding and backfill (complete). Cross drainage located	m	21	\$ 15,000.00	\$	315,000.0
	every 500m spacing along alignment.					
	Other:			A 400 000 00	0	100.000.0
2.2	DAF Red classification floodway crossings	Each	1	\$ 400,000.00	\$	400,000.0
3	EARTHWORKS, PREPARATION:				1	
	Clearing and grubbing, including removal of building structures, retaining structures, vegetation including					
3.1	mulching to stockpile, concrete structures, water tanks, septic tanks and capping and removal of bore	m2	78100	\$ 1.87	\$	146,047.0
	equipment (Provisional Quantity as directed)					
3.2	Stripping of topsoil (Provisional Quantity as directed)	m3	39050	\$ 6.65		259,682.5
3.3	Ground surface treatment under embankment, standard	m2	23430	\$ 1.20	\$	28,116.0
3.4	Excavation and disposal of Unsuitable Material with individual excavation < 10 m3 (Provisional Quantity as directed)	m3	10	\$ 50.00	\$	500.0
	Excavation and disposal of Unsuitable Material with individual excavation > 10 m3 (Provisional Quantity				+	
3.5	as directed)	m3	20600	\$ 16.65	\$	342,990.0
4	EARTHWORKS, EXCAVATION:					
4.1	Road excavation, all materials	m3	411700	\$ 11.25	\$	4,631,625.0
4.2	Excavation of non-rippable material in road excavation, rate additional to rate for Work Item 3201	m3	20600	\$ 60.50	\$	1,246,300.0
	(Provisional Quantity)					
5	EARTHWORKS, EMBANKMENT:					
5.1	Road embankment	m3	65000	\$ 6.95	\$	451,750.0
6	EARTHWORKS, SUBGRADE:					
6.1	Testing of existing material below subgrade level in cuttings (Provisional Quantity if ordered)	per set	608	\$ 450.00		273,600.0
6.2	Subgrade treatment Type A in cuttings (Provisional Quantity if ordered)	m2	46860	\$ 1.75	\$	82,005.0
	FARTHWORKS DASKELL					
7 7.1	EARTHWORKS, BACKFILL: Backfill with general backfill material to areas of unsuitable	m3	20600	\$ 70.25	\$	1,447,150.0
7.1	Dackilli willingerieral backilli material to areas of disolitable	1110	20000	Ψ 70.23	Ψ	1,447,130.0
8	UNBOUND PAVEMENTS:					
8.1	Base Course Type 2.1 200mm (CBR 80)	m3	29192.8	\$ 122.50	\$	3,576,115.0
8.2	Sub-base Course Type 2.3 300mm (CBR45)	m3	49389	\$ 97.50	\$	4,815,429.9
8.3	Geotextile under sub-base pavement	m2	157080	\$ 1.50	\$	235,620.0
9	SPRAYED BITUMINOUS SURFACING (EXCLUDING EMULSION):	P.	100010		•	
9.1 9.2	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2	litre	136640 212550		\$	-
9.3	Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site	litre m3	1390		\$	
9.5	Supply and spreading cover aggregate 14mm, 110 mz/mb, on job site	1110	1330		Ψ	
10	REMOVAL, DEMOLITION AND RE-ERECTION:					
10.1	Removal and re-erection of road furniture	lump sum	1	\$ 5,000.00	\$	5,000.0
11	SUPPLY OF COVER AGGREGATE:					
11.1	Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2	litre	106280		\$	-
11.2	Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site	m3	760		\$	-
12	LINE MARKING AND SIGNAGE:					
12.1	Spotting only for longitudinal lines	m	30370		\$	
12.2	Linemarking (white paint complete)	m	30370		\$	_
12.3	New signs and posts (Complete)	lump sum	1	\$ 25,000.00		25,000.0
12.4	New road edge guid posts (Complete)	No.	300	\$ 60.00		18,000.0
-						
13	LANDSCAPING:				1_	
13.1	Re-spreading of stockpiled topsoil to depth of 100mm	m2	78100	\$ 3.20		249,920.0
13.2	Hydromulch grass seeding.	m2	78100	\$ 0.91	\$	71,071.0
	MISCELLANEOUS:	-	-		1	
14					+	
14 14.1		m2	25915 7	\$ 550.00	25	14.253 613 5
14.1	Retaining structure - Keppel Block including excavation, footing and backfill	m2 m	25915.7 3680	\$ 550.00 \$ 110.00		
		m2 m Each	25915.7 3680 21	\$ 550.00 \$ 110.00 \$ 2,500.00	\$	14,253,613.5 404,800.0 52,500.0
14.1 14.3	Retaining structure - Keppel Block including excavation, footing and backfill Concrete lined invert / barrier kerb to top of retaining walls	m	3680	\$ 110.00	\$	404,800.0

Total for Civil Works (ex GST): \$34,234,403



Project Number: R2018071 Project Name: Agnes War Agnes Water to Baffle Creek Option 4A (MC04A) - Ultimate sealed Gladstone Regional Council Road Name: Location:

0 11-Mar-19 Revision Date:

Work Package: Civil Works (Including drainage and retaining Structures):

	work Package: Civil works (including drainage and		ng Su	ructures).		
Item Number	Description	Unit of Measure	Quantity	Unit Rate (\$)	Am	ount ex GST(\$)
1	EROSION AND SEDIMENT CONTROL:					
1.1	Check Dams, rock (Provisional Quantity)	lump sum	1020	\$ 216.00	\$	220,320.00
1.2	Silt / Sediment Fence (Provisional Quantity)	m	20400	\$ 10.87	\$	221,748.00
2	DRAINAGE STRUCTURES:					
	Culverts (complete):					
	Supply and installation of concrete pipe culvert components, Class 3, 600mm diameter flush joint with					
2.1	external bands to AS4058 including excavation, bedding and backfill (complete). Cross drainage located	m	21	\$ 15,000.00	\$	315,000.00
	every 500m spacing along alignment.					
	Other:					
2.2	DAF Red classification floodway crossings	Each	1	\$ 400,000.00	\$	400,000.00
3	EARTHWORKS, PREPARATION:					
<u> </u>	Clearing and grubbing, including removal of building structures, retaining structures, vegetation including					
3.1	mulching to stockpile, concrete structures, water tanks, septic tanks and capping and removal of bore	m2	78100	\$ 1.87	\$	146,047.00
	equipment (Provisional Quantity as directed)				_	,
3.2	Stripping of topsoil (Provisional Quantity as directed)	m3	39050	\$ 6.65	\$	259,682.50
3.3	Ground surface treatment under embankment, standard	m2	23430	\$ 1.20	\$	28,116.00
3.4	Excavation and disposal of Unsuitable Material with individual excavation < 10 m3 (Provisional Quantity	m3	10	\$ 50.00	\$	500.00
0.4	as directed)	1110	10	ψ 00.00	Ψ	000.00
3.5	Excavation and disposal of Unsuitable Material with individual excavation > 10 m3 (Provisional Quantity	m3	20600	\$ 16.65	\$	342,990.00
	as directed)					
4	EARTHWORKS, EXCAVATION:					
4.1	Road excavation, all materials	m2	411700	\$ 11.25	\$	4,631,625.00
	Excavation of non-rippable material in road excavation, rate additional to rate for Work Item 3201	m3				
4.2	(Provisional Quantity)	m3	20600	\$ 60.50	\$	1,246,300.00
5	EARTHWORKS, EMBANKMENT:					
5.1	Road embankment	m3	65000	\$ 6.95	\$	451,750.00
6	EARTHWORKS, SUBGRADE:					
6.1	Testing of existing material below subgrade level in cuttings (Provisional Quantity if ordered)	per set	608	\$ 450.00	\$	273,600.00
6.2	Subgrade treatment Type A in cuttings (Provisional Quantity if ordered)	m2	46860	\$ 1.75	\$	82,005.00
	EARTHWORKS BASKER!					
7	EARTHWORKS, BACKFILL:	m2	20600	¢ 70.05	ď	1 117 150 00
7.1	Backfill with general backfill material to areas of unsuitable	m3	20600	\$ 70.25	Þ	1,447,150.00
8	UNBOUND PAVEMENTS:					
8.1	Base Course Type 2.1 200mm (CBR 80)	m3	29192.8	\$ 122.50	\$	3,576,115.06
8.2	Sub-base Course Type 2.3 300mm (CBR45)	m3	49389	\$ 97.50	\$	4,815,429.94
8.3	Geotextile under sub-base pavement	m2	157080	\$ 1.50	_	235,620.00
9	SPRAYED BITUMINOUS SURFACING (EXCLUDING EMULSION):					
9.1	Primer seal - AMC00 @ 0.9L/m2	litre	136640	\$ 1.95	\$	266,448.00
9.2	Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2	litre	212550	\$ 1.95	\$	414,472.50
9.3	Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site	m3	1390	\$ 202.50	\$	281,475.00
10 10.1	REMOVAL, DEMOLITION AND RE-ERECTION:	L		\$ 5,000.00	•	5,000,00
10.1	Removal and re-erection of road furniture	lump sum	1	\$ 5,000.00	Þ	5,000.00
11	SUPPLY OF COVER AGGREGATE:					
11.1	Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2	litre	106280	\$ 2.00	\$	212,560.00
11.2	Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site	m3	760	\$ 218.50	\$	166,060.00
	and the state of t		. 50	. 2.5.00		,
12	LINE MARKING AND SIGNAGE:					
12.1	Spotting only for longitudinal lines	m	30370	\$ 0.50	\$	15,185.00
12.2	Linemarking (white paint complete)	m	30370	\$ 1.45		44,036.50
12.3	New signs and posts (Complete)	lump sum	1	\$ 25,000.00	\$	25,000.00
12.4	New road edge guid posts (Complete)	No.	300	\$ 60.00	\$	18,000.00
,_	LANDOGARING				↓	
13	LANDSCAPING:		70400		^	040.000.00
13.1	Re-spreading of stockpiled topsoil to depth of 100mm	m2	78100	\$ 3.20	\$	249,920.00
13.2	Hydromulch grass seeding.	m2	78100	\$ 0.91	Ф	71,071.00
14	MISCELLANEOUS:				\vdash	
14.1	Retaining structure - Keppel Block including excavation, footing and backfill	m2	25915.7	\$ 550.00	\$	14,253,613.55
14.3	Concrete lined invert / barrier kerb to top of retaining walls	m	3680	\$ 110.00	\$	404,800.00
14.4	Construction of stockpile site	Each	21	\$ 2,500.00		52,500.00
14.5	W-beam guard rail, ezy-guard posts	m	3120	\$ 110.00	_	343,200.00
14.6	Steel beam guard rail terminal, ET2000 PLUS TL2 terminal	Each	30	\$ 3,910.00		117,300.00

Total for Civil Works (ex GST): \$35,634,640



Project Number: R2018071
Project Name: Agnes War
Road Name: Option 5 (I Agnes Water to Baffle Creek
Option 5 (MC05) - Interim unsealed
Gladstone Regional Council Location:

Revision Date: **0** 11-Mar-19

Work Package: Civil Works (Including drainage and retaining Structures):

	Work Package: Civil Works (Including drainage and	retaini	ng Stı	ructures):		
Item Number	Description	Unit of Measure	Quantity	Unit Rate (\$)	Amount ex G	ST(\$)
1	EROSION AND SEDIMENT CONTROL:					
1.1	Check Dams, rock (Provisional Quantity)	lump sum	1710	\$ 216.00	\$ 369,36	60.00
1.2	Silt / Sediment Fence (Provisional Quantity)	m	34200	\$ 10.87	\$ 371,75	
2	DRAINAGE STRUCTURES:					
	Culverts (complete): Supply and installation of concrete pipe culvert components, Class 3, 600mm diameter flush joint with					
2.1	external bands to AS4058 including excavation, bedding and backfill (complete). Cross drainage located every 500m spacing along alignment.	m	35	\$ 15,000.00	\$ 525,00	00.00
	Other:					
2.2	DAF Green classification floodway crossings	Each	5	\$ 100,000.00	\$ 500,00	00.00
2.3	DAF Amber classification floodway crossings	Each	1	\$ 250,000.00	\$ 250,00	00.00
	EARTHMORKS PREPARATION.					
3	EARTHWORKS, PREPARATION: Clearing and grubbing, including removal of building structures, retaining structures, vegetation including					
3.1	mulching to stockpile, concrete structures, water tanks, septic tanks and capping and removal of bore	m2	295300	\$ 1.87	\$ 552,21	11.00
	equipment (Provisional Quantity as directed)					
3.2	Stripping of topsoil (Provisional Quantity as directed)	m3	147650	\$ 6.65	\$ 981,87	
3.3	Ground surface treatment under embankment, standard Excavation and disposal of Unsuitable Material with individual excavation < 10 m3 (Provisional Quantity	m2	88590	\$ 1.20	\$ 106,30	08.00
3.4	as directed)	m3	10	\$ 50.00	\$ 50	00.00
3.5	Excavation and disposal of Unsuitable Material with individual excavation > 10 m3 (Provisional Quantity	m3	4400	\$ 16.65	\$ 73,26	en nn
3.5	as directed)	IIIS	4400	\$ 10.00	\$ 73,26	00.00
4	EARTHWORKS EVOAVATION:					
4.1	EARTHWORKS, EXCAVATION: Road excavation, all materials	m3	86500	\$ 11.25	\$ 973,12	25.00
	Excavation of non-rippable material in road excavation, rate additional to rate for Work Item 3201					
4.2	(Provisional Quantity)	m3	4400	\$ 60.50	\$ 266,20	00.00
5	EARTHWORKS, EMBANKMENT:					
5.1	Road embankment	m3	57000	\$ 6.95	\$ 396,15	50.00
				* ****	, , , ,	
6	EARTHWORKS, SUBGRADE:					
6.1	Testing of existing material below subgrade level in cuttings (Provisional Quantity if ordered)	per set	1024	\$ 450.00	\$ 460,80	
6.2	Subgrade treatment Type A in cuttings (Provisional Quantity if ordered)	m2	177180	\$ 1.75	\$ 310,06	65.00
7	EARTHWORKS, BACKFILL:					
7.1	Backfill with general backfill material to areas of unsuitable	m3	4400	\$ 70.25	\$ 309,10	00.00
8	UNBOUND PAVEMENTS:	0	050740	¢ 400.50	© 0.400.44	10.00
8.1 8.2	Base Course Type 2.1 200mm (CBR 80) Sub-base Course Type 2.3 300mm (CBR45)	m3 m3	25374.8 47477.9	\$ 122.50 \$ 97.50	\$ 3,108,41 \$ 4,629,09	
8.3	Geotextile under sub-base pavement	m2	135090	\$ 1.50	\$ 202,63	
				•		
9	SPRAYED BITUMINOUS SURFACING (EXCLUDING EMULSION):					
9.1	Primer seal - AMC00 @ 0.9L/m2	litre	115110		\$	-
9.2 9.3	Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site	litre m3	179050 1170		\$	-
9.5	Supply and spreading cover aggregate 14mm, 110 mz/ms, on job site	1110	1170		Ą	
10	REMOVAL, DEMOLITION AND RE-ERECTION:					
10.1	Removal and re-erection of road furniture	lump sum	1	\$ 5,000.00	\$ 5,00	00.00
44	SURDI V OF COVER ACCRECATE.					
11 11.1	SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2	litre	89530		\$	_
11.2	Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site	m3	640		\$	-
12	LINE MARKING AND SIGNAGE:					
12.1	Spotting only for longitudinal lines	m	51160		\$	-
12.2 12.3	Linemarking (white paint complete) New signs and posts (Complete)	m lump sum	51160	\$ 25,000.00	\$ 25,00	-
12.4	New road edge guid posts (Complete)	No.	400	\$ 25,000.00		00.00
13	LANDSCAPING:	_	005555			00.00
13.1	Re-spreading of stockpiled topsoil to depth of 100mm	m2	295300	\$ 3.20 \$ 0.91	\$ 944,96 \$ 268,72	
13.2	Hydromulch grass seeding.	m2	295300	φ 0.91	\$ 268,72	۷۵.00
14	MISCELLANEOUS:					
14.1	Retaining structure - Keppel Block including excavation, footing and backfill	m2	1331.48	\$ 550.00	\$ 732,31	
14.3	Concrete lined invert / barrier kerb to top of retaining walls	m	530	\$ 110.00		00.00
14.4	Construction of stockpile site	Each	35	\$ 2,500.00	\$ 87,50	
14.5 14.6	W-beam guard rail, ezy-guard posts Steel beam guard rail terminal, ET2000 PLUS TL2 terminal	m Each	1960 20	\$ 110.00 \$ 3,910.00	\$ 215,60	00.00
14.0	oteet beath guard fall tellfillial, ETZ000 FLOS TLZ tellfillial	⊏dUII	∠U	ψ 3,810.00	ψ /0,20	UU.UU



Project Number: R2018071 Project Name: Agnes War Agnes Water to Baffle Creek Option 5 (MC05) - Ultimate sealed Gladstone Regional Council Road Name: Location:

Revision Date: **0** 11-Mar-19

Work Package: Civil Works (Including drainage and retaining Structures):

Item Number	Description	Unit of	Quantity	Unit Rate (\$)	Am	ount ex GST(
	T	Measure	,			
1	EROSION AND SEDIMENT CONTROL:				\vdash	
1.1	Check Dams, rock (Provisional Quantity)	lump sum	1710	\$ 216.00	\$	369,360.0
1.2	Silt / Sediment Fence (Provisional Quantity)	m	34200	\$ 10.87	\$	371,754.0
	, "					
2	DRAINAGE STRUCTURES:					
	Culverts (complete):				<u> </u>	
	Supply and installation of concrete pipe culvert components, Class 3, 600mm diameter flush joint with					
2.1	external bands to AS4058 including excavation, bedding and backfill (complete). Cross drainage located	m	35	\$ 15,000.00	\$	525,000.0
	every 500m spacing along alignment.				+	
	Other:				 	
2.2	DAF Green classification floodway crossings	Each	5	\$ 100,000.00	\$	500,000.0
2.3	DAF Amber classification floodway crossings	Each	1	\$ 250,000.00	\$	250,000.0
3	EARTHWORKS, PREPARATION:				<u> </u>	
0.4	Clearing and grubbing, including removal of building structures, retaining structures, vegetation including		100100			004 507 6
3.1	mulching to stockpile, concrete structures, water tanks, septic tanks and capping and removal of bore equipment (Provisional Quantity as directed)	m2	120100	\$ 1.87	\$	224,587.0
3.2	Stripping of topsoil (Provisional Quantity as directed)	m3	60050	\$ 6.65	\$	399,332.5
3.3	Ground surface treatment under embankment, standard	m2	36030	\$ 1.20	\$	43,236.0
	Excavation and disposal of Unsuitable Material with individual excavation < 10 m3 (Provisional Quantity					
3.4	as directed)	m3	10	\$ 50.00	\$	500.0
3.5	Excavation and disposal of Unsuitable Material with individual excavation > 10 m3 (Provisional Quantity	m3	7600	\$ 16.65	\$	126,540.0
0.0	as directed)	1110	7000	ψ 10.00	Ψ	120,040.0
					₩	
4	EARTHWORKS, EXCAVATION:	0	450400	£ 44.05		4 000 005 0
4.1	Road excavation, all materials Excavation of non-rippable material in road excavation, rate additional to rate for Work Item 3201	m3	150100	\$ 11.25		1,688,625.0
4.2	(Provisional Quantity)	m3	7600	\$ 60.50	\$	459,800.0
					1	
5	EARTHWORKS, EMBANKMENT:					
5.1	Road embankment	m3	42900	\$ 6.95	\$	298,155.0
6	EARTHWORKS, SUBGRADE:				<u> </u>	
6.1	Testing of existing material below subgrade level in cuttings (Provisional Quantity if ordered)	per set	1024	\$ 450.00	\$	460,800.0
6.2	Subgrade treatment Type A in cuttings (Provisional Quantity if ordered)	m2	72060	\$ 1.75	\$	126,105.0
7	EARTHWORKS, BACKFILL:				₩	
7.1	Backfill with general backfill material to areas of unsuitable	m3	7600	\$ 70.25	\$	533,900.0
7.1	Dackfill with general backfill material to areas of disolitable	1110	7000	Ψ 70.23	Ψ	333,300.0
8	UNBOUND PAVEMENTS:				1	
8.1	Base Course Type 2.1 200mm (CBR 80)	m3	48943.1	\$ 122.50	\$	5,995,532.3
8.2	Sub-base Course Type 2.3 300mm (CBR45)	m3	82638.5	\$ 97.50	\$	8,057,252.7
8.3	Geotextile under sub-base pavement	m2	263340	\$ 1.50	\$	395,010.0
					<u> </u>	
9	SPRAYED BITUMINOUS SURFACING (EXCLUDING EMULSION):				<u> </u>	
9.1	Primer seal - AMC00 @ 0.9L/m2	litre	230210		\$	-
9.2	Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2	litre	358100		\$	
9.3	Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site	m3	2330		Э	
10	REMOVAL, DEMOLITION AND RE-ERECTION:				+	
10.1	Removal and re-erection of road furniture	lump sum	1	\$ 5,000.00	\$	5,000.0
				7 0,000.00	Ť	-,
11	SUPPLY OF COVER AGGREGATE:					
11.1	Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2	litre	179050		\$	-
11.2	Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site	m3	1280		\$	-
					<u> </u>	
12	LINE MARKING AND SIGNAGE:				Ļ	
12.1	Spotting only for longitudinal lines	m	51160		\$	
12.2	Linemarking (white paint complete)	m lump cum	51160	¢ 25,000,00	\$	25,000,0
12.3 12.4	New signs and posts (Complete) New road edge guid posts (Complete)	lump sum No.	400	\$ 25,000.00 \$ 60.00	\$	25,000.0 24,000.0
14.4	Trow road dago guid posts (complete)	140.	-100	w 60.00	Ψ	۷4,000.۱
13	LANDSCAPING:				t	
13.1	Re-spreading of stockpiled topsoil to depth of 100mm	m2	120100	\$ 3.20	\$	384,320.0
13.2	Hydromulch grass seeding.	m2	120100	\$ 0.91	\$	109,291.0
14	MISCELLANEOUS:					
14.1	Retaining structure - Keppel Block including excavation, footing and backfill	m2	0		\$	-
14.3	Concrete lined invert / barrier kerb to top of retaining walls	m	520		\$	-
14.4	Construction of stockpile site	Each	35	\$ 2,500.00	_	87,500.0
14.5	W-beam guard rail, ezy-guard posts	m Each	1640 16		\$	-
14.6	Steel beam guard rail terminal, ET2000 PLUS TL2 terminal					



Project Number: R2018071 Project Name: Agnes War Agnes Water to Baffle Creek Option 5 (MC05) - Ultimate sealed Gladstone Regional Council Road Name: Location:

Revision Date: **0** 11-Mar-19

Work Package: Civil Works (Including drainage and retaining Structures):

Item Number	Description	Unit of	Quantity	Unit Rate (\$)	Amo	ount ex GST(
	T	Measure	,			
1	EROSION AND SEDIMENT CONTROL:					
1.1	Check Dams, rock (Provisional Quantity)	lump sum	1710	\$ 216.00	\$	369,360.0
1.2	Silt / Sediment Fence (Provisional Quantity)	m	34200	\$ 10.87	\$	371,754.0
2	DRAINAGE STRUCTURES:					
	Culverts (complete):					
	Supply and installation of concrete pipe culvert components, Class 3, 600mm diameter flush joint with					
2.1	external bands to AS4058 including excavation, bedding and backfill (complete). Cross drainage located	m	35	\$ 15,000.00	\$	525,000.0
	every 500m spacing along alignment.					
0.0	Other:	F	_	£ 400,000,00	•	500,000,0
2.2	DAF Green classification floodway crossings DAF Amber classification floodway crossings	Each	5 1	\$ 100,000.00 \$ 250,000.00	Ď.	500,000.0 250,000.0
2.3	DAF Amber classification floodway crossings	Each		\$ 250,000.00	Ф	250,000.0
3	EARTHWORKS, PREPARATION:				1	
	Clearing and grubbing, including removal of building structures, retaining structures, vegetation including					
3.1	mulching to stockpile, concrete structures, water tanks, septic tanks and capping and removal of bore	m2	120100	\$ 1.87	\$	224,587.0
	equipment (Provisional Quantity as directed)					
3.2	Stripping of topsoil (Provisional Quantity as directed)	m3	60050	\$ 6.65	\$	399,332.5
3.3	Ground surface treatment under embankment, standard	m2	36030	\$ 1.20	\$	43,236.0
3.4	Excavation and disposal of Unsuitable Material with individual excavation < 10 m3 (Provisional Quantity	m3	10	\$ 50.00	\$	500.0
0	as directed)	1110		ψ 00.00	Ψ	000.0
3.5	Excavation and disposal of Unsuitable Material with individual excavation > 10 m3 (Provisional Quantity	m3	7600	\$ 16.65	\$	126,540.0
	as directed)					
4	EARTHWORKS, EXCAVATION:					
4.1	Road excavation, all materials	m3	150100	\$ 11.25	\$	1,688,625.0
	Excavation of non-rippable material in road excavation, rate additional to rate for Work Item 3201					
4.2	(Provisional Quantity)	m3	7600	\$ 60.50	\$	459,800.0
5	EARTHWORKS, EMBANKMENT:					
5.1	Road embankment	m3	42900	\$ 6.95	\$	298,155.0
6	EARTHWORKS, SUBGRADE:					
6.1	Testing of existing material below subgrade level in cuttings (Provisional Quantity if ordered)	per set	1024	\$ 450.00	\$	460,800.0
6.2	Subgrade treatment Type A in cuttings (Provisional Quantity if ordered)	m2	72060	\$ 1.75	\$	126,105.0
-	FARTHWORKS RACKELL.				-	
7 7.1	EARTHWORKS, BACKFILL:	m3	7600	\$ 70.25	\$	E33 000 0
7.1	Backfill with general backfill material to areas of unsuitable	1113	7600	\$ 70.25	ф	533,900.0
8	UNBOUND PAVEMENTS:					
8.1	Base Course Type 2.1 200mm (CBR 80)	m3	48943.1	\$ 122.50	S	5,995,532.3
8.2	Sub-base Course Type 2.3 300mm (CBR45)	m3	82638.5	\$ 97.50	\$	8,057,252.7
8.3	Geotextile under sub-base pavement	m2	263340	\$ 1.50	\$	395,010.0
						-
9	SPRAYED BITUMINOUS SURFACING (EXCLUDING EMULSION):					
9.1	Primer seal - AMC00 @ 0.9L/m2	litre	230210	\$ 1.95	\$	448,909.5
9.2	Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2	litre	358100	\$ 1.95	\$	698,295.0
9.3	Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site	m3	2330	\$ 202.50	\$	471,825.0
10	REMOVAL, DEMOLITION AND RE-ERECTION:					
10.1	Removal and re-erection of road furniture	lump sum	1	\$ 5,000.00	\$	5,000.0
44	OURRE V OF COVER A CORFOATE					
11	SUPPLY OF COVER AGGREGATE:	P.	170050	A 0.00	0	050 100 0
11.1 11.2	Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site	litre m3	179050 1280	\$ 2.00 \$ 218.50	\$	358,100.0 279,680.0
11.2	Supply and spreading cover aggregate Tomin, 200 m2/m3, on job site	IIIS	1200	\$ 210.50	ф	279,000.0
12	LINE MARKING AND SIGNAGE:	1	1		1	
12.1	Spotting only for longitudinal lines	m	51160	\$ 0.50	\$	25,580.0
12.2	Linemarking (white paint complete)	m	51160	\$ 1.45	_	74,182.0
12.3	New signs and posts (Complete)	lump sum	1	\$ 25,000.00		25,000.0
12.4	New road edge guid posts (Complete)	No.	400	\$ 60.00		24,000.0
13	LANDSCAPING:					
13.1	Re-spreading of stockpiled topsoil to depth of 100mm	m2	120100	\$ 3.20	\$	384,320.0
13.2	Hydromulch grass seeding.	m2	120100	\$ 0.91	\$	109,291.0
14	MISCELLANEOUS:					
14.1	Retaining structure - Keppel Block including excavation, footing and backfill	m2	0		\$	-
14.3	Concrete lined invert / barrier kerb to top of retaining walls	m	520		\$	
14.4	Construction of stockpile site	Each	35	\$ 2,500.00	\$	87,500.0
	W-beam guard rail, ezy-guard posts	m	1640		\$	-
14.5 14.6	Steel beam guard rail terminal, ET2000 PLUS TL2 terminal	Each	16		\$	

Total for Civil Works (ex GST): \$23,817,172



Project Number: R2018071
Project Name: Agnes Wate
Road Name: Option A (I Agnes Water to Baffle Creek
Option A (MCA0) - Interim unsealed Location: **Gladstone Regional Council**

0 11-Mar-19 Revision Date:

Work Package: Civil Works (Including drainage and retaining Structures):

	Work Package: Civil Works (Including drainage and					
Item Number	Description	Unit of Measure	Quantity	Unit Rate (\$)	Am	ount ex GST(
1	EROSION AND SEDIMENT CONTROL:					
1.1	Check Dams, rock (Provisional Quantity)	lump sum	770	\$ 216.0	0 \$	166,320.0
1.2	Silt / Sediment Fence (Provisional Quantity)	m	15400	\$ 10.8	_	167,398.0
				, ,,,,	· · ·	,
2	DRAINAGE STRUCTURES:					
_	Culverts (complete):	1			\neg	
	Supply and installation of concrete pipe culvert components, Class 3, 600mm diameter flush joint with	Ì			\neg	
2.1	external bands to AS4058 including excavation, bedding and backfill (complete). Cross drainage	m	16	\$ 15,000.0	0 \$	240,000.0
	located every 500m spacing along alignment.					
	Other:					
2.2	DAF Green classification floodway crossings	Each	4	\$ 100,000.0	0 \$	400,000.0
2.3	DAF Amber classification floodway crossings	Each	2	\$ 250,000.0	0 \$	500,000.0
3	EARTHWORKS, PREPARATION:					
	Clearing and grubbing, including removal of building structures, retaining structures, vegetation	1				
3.1	including mulching to stockpile, concrete structures, water tanks, septic tanks and capping and	m2	142100	\$ 1.8	7 \$	265,727.0
	removal of bore equipment (Provisional Quantity as directed)					
3.2	Stripping of topsoil (Provisional Quantity as directed)	m3	71050	\$ 6.6	5 \$	472,482.5
3.3	Ground surface treatment under embankment, standard	m2	42630	\$ 1.2	0 \$	51,156.0
3.4	Excavation and disposal of Unsuitable Material with individual excavation < 10 m3 (Provisional	m3	10	\$ 50.0	0 \$	500.0
J. 4	Quantity as directed)	1113	10	Ψ 50.0	υ φ	500.0
3.5	Excavation and disposal of Unsuitable Material with individual excavation > 10 m3 (Provisional	m3	2900	\$ 16.6	5 \$	48,285.0
0.0	Quantity as directed)	1110	2500	\$ 10.0	Ψ	70,200.0
4	EARTHWORKS, EXCAVATION:					
4.1	Road excavation, all materials	m3	57400	\$ 11.2	5 \$	645,750.0
4.2	Excavation of non-rippable material in road excavation, rate additional to rate for Work Item 3201	m3	2900	\$ 60.5	0 \$	175,450.0
	(Provisional Quantity)	0	2000	Ψ σσ.σ	Ψ	170,100.0
5	EARTHWORKS, EMBANKMENT:					
5.1	Road embankment	m3	22510.4	\$ 6.9	5 \$	156,447.3
6	EARTHWORKS, SUBGRADE:					
6.1	Testing of existing material below subgrade level in cuttings (Provisional Quantity if ordered)	per set	460	\$ 450.0	0 \$	207,000.0
6.2	Subgrade treatment Type A in cuttings (Provisional Quantity if ordered)	m2	85260	\$ 1.7	5 \$	149,205.0
7	EARTHWORKS, BACKFILL:					
7.1	Backfill with general backfill material to areas of unsuitable	m3	2900	\$ 70.2	5 \$	203,725.0
8	UNBOUND PAVEMENTS:					
8.1	Base Course Type 2.1 200mm (CBR 80)	m3	10000	\$ 122.5	0 \$	1,225,000.0
8.2	Sub-base Course Type 2.3 300mm (CBR45)	m3	20160	\$ 97.5	0 \$	1,965,600.0
8.3	Geotextile under sub-base pavement	m2	60830	\$ 1.5	0 \$	91,245.0
9	SPRAYED BITUMINOUS SURFACING (EXCLUDING EMULSION):					
9.1	Primer seal - AMC00 @ 0.9L/m2	litre	51670		\$	-
9.2	Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2	litre	80370		\$	-
9.3	Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site	m3	530		\$	-
10	REMOVAL, DEMOLITION AND RE-ERECTION:	1				
10.1	Removal and re-erection of road furniture	lump sum	1	\$ 5,000.0	0 \$	5,000.0
11	SUPPLY OF COVER AGGREGATE:					
11.1	Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2	litre	40190		\$	-
11.2	Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site	m3	290		\$	-
	Cupping and optionaling corror aggregator forming 200 mizimo, or job one		200			
12	LINE MARKING AND SIGNAGE:	1			+-	
12.1	Spotting only for longitudinal lines	m	22970		\$	-
12.2	Linemarking (white paint complete)	1			\$	
12.3	New signs and posts (Complete)	m lump sum	22970	\$ 25,000.0		25,000.
			200			12,000.
12.4	New road edge guid posts (Complete)	No.	200	\$ 60.0	υÞ	12,000.
40	LANDSCAPING:	 	-	 	+	
13		w-0	140400	• •	0 0	454 700
13.1	Re-spreading of stockpiled topsoil to depth of 100mm	m2	142100	\$ 3.2		454,720.
13.2	Hydromulch grass seeding.	m2	142100	\$ 0.9	1 \$	129,311.
		ļ			—	
14	MISCELLANEOUS:	ļ		ļ	—	
	Retaining structure - Keppel Block including excavation, footing and backfill	m2	780	\$ 550.0		429,000
14.1		m	230	\$ 110.0	0 \$	25,300
14.1 14.3	Concrete lined invert / barrier kerb to top of retaining walls					
	Concrete lined invert / barrier kerb to top of retaining walls Construction of stockpile site	Each	16	\$ 2,500.0	0 \$	40,000
14.3			16 880	\$ 2,500.0 \$ 110.0		40,000 96,800



Project Number: R2018071
Project Name: Agnes Wate
Road Name: Option A (I Agnes Water to Baffle Creek
Option A (MCA0) - Ultimate unsealed
Gladstone Regional Council

Revision **0** 11-Mar-19 Location: Date:

Work Package: Civil Works (Including drainage and retaining Structures):

Item Number	Work Package: Civil Works (Including drainage and	Unit of					
Item Number	Description	Measure	Quantity		Unit Rate (\$)	Amo	ount ex GST(
1	EROSION AND SEDIMENT CONTROL:						
1.1	Check Dams, rock (Provisional Quantity)	lump sum	770	\$	216.00	\$	166,320.0
1.2	Silt / Sediment Fence (Provisional Quantity)	m	15400	\$	10.87	\$	167,398.0
2	DRAINAGE STRUCTURES:						
	Culverts (complete):						
	Supply and installation of concrete pipe culvert components, Class 3, 600mm diameter flush joint with						
2.1	external bands to AS4058 including excavation, bedding and backfill (complete). Cross drainage	m	16	\$	15,000.00	\$	240,000.0
	located every 500m spacing along alignment.						
	Other:						
2.2	DAF Green classification floodway crossings	Each	4	\$	100,000.00	\$	400,000.
2.3	DAF Amber classification floodway crossings	Each	2	\$	250,000.00	\$	500,000.
3	EARTHWORKS, PREPARATION:						
	Clearing and grubbing, including removal of building structures, retaining structures, vegetation						
3.1	including mulching to stockpile, concrete structures, water tanks, septic tanks and capping and	m2	67100	\$	1.87	\$	125,477.
	removal of bore equipment (Provisional Quantity as directed)						
3.2	Stripping of topsoil (Provisional Quantity as directed)	m3	33550	\$	6.65	\$	223,107.
3.3	Ground surface treatment under embankment, standard	m2	20130	\$	1.20	\$	24,156.
	Excavation and disposal of Unsuitable Material with individual excavation < 10 m3 (Provisional						
3.4	Quantity as directed)	m3	10	\$	50.00	\$	500.
2.5	Excavation and disposal of Unsuitable Material with individual excavation > 10 m3 (Provisional	m-O	4500	¢	46.05	0	74.005
3.5	Quantity as directed)	m3	4500	\$	16.65	\$	74,925.0
4	EARTHWORKS, EXCAVATION:						
4.1	Road excavation, all materials	m3	89400	\$	11.25	\$	1,005,750.0
4.0	Excavation of non-rippable material in road excavation, rate additional to rate for Work Item 3201	0	4500		00.50	6	070.050
4.2	(Provisional Quantity)	m3	4500	\$	60.50	\$	272,250.0
5	EARTHWORKS, EMBANKMENT:						
5.1	Road embankment	m3	13900	\$	6.95	\$	96,605.0
6	EARTHWORKS, SUBGRADE:						
6.1	Testing of existing material below subgrade level in cuttings (Provisional Quantity if ordered)	per set	460	\$	450.00	\$	207,000.0
6.2	Subgrade treatment Type A in cuttings (Provisional Quantity if ordered)	m2	40260	\$	1.75	\$	70,455.0
	g			Ť		Ť	,
7	EARTHWORKS, BACKFILL:			1			
7.1	Backfill with general backfill material to areas of unsuitable	m3	4500	\$	70.25	S	316,125.0
***	Data in manyonoral basis in material to areas of a basis by		.000	Ψ	70.20	Ÿ	010,120.
8	UNBOUND PAVEMENTS:						
8.1	Base Course Type 2.1 200mm (CBR 80)	m3	21855.364	\$	122.50	S	2,677,282.0
8.2	Sub-base Course Type 2.3 300mm (CBR45)	m3	37263.831	\$	97.50	\$	3,633,223.5
8.3	Geotextile under sub-base pavement	m2	118580	\$	1.50		177,870.0
0.3	Geotextile dilder sub-base pavernent	IIIZ	110000	φ	1.50	φ	177,070.
9							
	SPDAYED DITUMINOUS SUDEACING (EYCLUDING EMULSION).		-	-			
	SPRAYED BITUMINOUS SURFACING (EXCLUDING EMULSION):	Etro	400000			Φ.	
9.1	Primer seal - AMC00 @ 0.9L/m2	litre	103330			\$ 6	-
9.1 9.2	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2	litre	160730			\$	-
9.1	Primer seal - AMC00 @ 0.9L/m2					\$ \$	-
9.1 9.2 9.3	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.75) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site	litre	160730			_	-
9.1 9.2 9.3	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site REMOVAL, DEMOLITION AND RE-ERECTION:	litre m3	160730			_	-
9.1 9.2 9.3	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.75) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site	litre	160730	\$	5,000.00	_	5,000.0
9.1 9.2 9.3 10 10.1	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site REMOVAL, DEMOLITION AND RE-ERECTION: Removal and re-erection of road furniture	litre m3	160730	\$	5,000.00	_	5,000.0
9.1 9.2 9.3 10 10.1	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site REMOVAL, DEMOLITION AND RE-ERECTION: Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE:	litre m3 lump sum	160730 1050	\$	5,000.00	_	5,000.
9.1 9.2 9.3 10 10.1	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site REMOVAL, DEMOLITION AND RE-ERECTION: Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2	litre m3 lump sum	160730 1050 1 1	\$	5,000.00	\$	-
9.1 9.2 9.3 10 10.1	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site REMOVAL, DEMOLITION AND RE-ERECTION: Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE:	litre m3 lump sum	160730 1050	\$	5,000.00	_	-
9.1 9.2 9.3 10 10.1 11.1 11.2	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site REMOVAL, DEMOLITION AND RE-ERECTION: Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site	litre m3 lump sum	160730 1050 1 1 80370	\$	5,000.00	\$	-
9.1 9.2 9.3 10 10.1 11 11.1 11.2	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site REMOVAL, DEMOLITION AND RE-ERECTION: Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE:	litre m3 lump sum	160730 1050 1 1 80370 580	\$	5,000.00	\$	-
9.1 9.2 9.3 10 10.1 11.1 11.2	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site REMOVAL, DEMOLITION AND RE-ERECTION: Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines	litre m3 lump sum	160730 1050 1 1 80370	\$	5,000.00	\$	-
9.1 9.2 9.3 10 10.1 11 11.1 11.2 12 12.1 12.2	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site REMOVAL, DEMOLITION AND RE-ERECTION: Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines Linemarking (white paint complete)	litre m3 lump sum litre m3	160730 1050 1 1 80370 580	\$		\$ \$ \$	-
9.1 9.2 9.3 10 10.1 11 11.1 11.2 12 12.1	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site REMOVAL, DEMOLITION AND RE-ERECTION: Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines	litre m3 lump sum litre m3	160730 1050 1 1 80370 580	\$	5,000.00	\$ \$	-
9.1 9.2 9.3 10 10.1 11 11.1 11.2 12 12.1 12.2	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site REMOVAL, DEMOLITION AND RE-ERECTION: Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines Linemarking (white paint complete)	litre m3 lump sum litre m3 m m	160730 1050 1 1 80370 580			\$ \$ \$	- - - 25,000.
9.1 9.2 9.3 10 10.1 11 11.2 12 12.1 12.2 12.3	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site REMOVAL, DEMOLITION AND RE-ERECTION: Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines Linemarking (white paint complete) New signs and posts (Complete) New road edge guid posts (Complete)	litre m3 lump sum litre m3 m m lump sum	160730 1050 1 1 1 80370 580 22970 22970	\$	25,000.00	\$ \$ \$	- - 25,000.
9.1 9.2 9.3 10 10.1 11 11.2 12 12.1 12.2 12.3	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site REMOVAL, DEMOLITION AND RE-ERECTION: Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines Linemarking (white paint complete) New signs and posts (Complete)	litre m3 lump sum litre m3 m m lump sum	160730 1050 1 1 1 80370 580 22970 22970	\$	25,000.00	\$ \$ \$	- - - 25,000.
9.1 9.2 9.3 10 10.1 11 11.1 11.2 12 12.1 12.2 12.3 12.4	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site REMOVAL, DEMOLITION AND RE-ERECTION: Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines Linemarking (white paint complete) New signs and posts (Complete) New road edge guid posts (Complete)	litre m3 lump sum litre m3 m m lump sum	160730 1050 1 1 1 80370 580 22970 22970	\$	25,000.00	\$ \$ \$	25,000. 12,000.
9.1 9.2 9.3 10 10.1 11 11.1 11.2 12 12.1 12.2 12.3 12.4	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site REMOVAL, DEMOLITION AND RE-ERECTION: Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines Linemarking (white paint complete) New signs and posts (Complete) New road edge guid posts (Complete) LANDSCAPING:	litre m3 lump sum litre m3 m m lump sum No.	160730 1050 1 1 80370 580 22970 22970 1 200	\$	25,000.00 60.00	\$ \$ \$	25,000 12,000 214,720
9.1 9.2 9.3 10 10.1 11 11.1 11.2 12 12.1 12.2 12.3 12.4	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site REMOVAL, DEMOLITION AND RE-ERECTION: Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines Linemarking (white paint complete) New signs and posts (Complete) New road edge guid posts (Complete) LANDSCAPING: Re-spreading of stockpiled topsoil to depth of 100mm	litre m3 lump sum litre m3 litre m3 litre m3 m lump sum lump sum m lump sum No.	160730 1050 1 1 80370 580 22970 1 200	\$ \$	25,000.00 60.00	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	25,000 12,000 214,720
9.1 9.2 9.3 10 10.1 11 11.1 11.2 12 12.1 12.2 12.3 12.4 13 13.1 13.2	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site REMOVAL, DEMOLITION AND RE-ERECTION: Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines Linemarking (white paint complete) New signs and posts (Complete) New road edge guid posts (Complete) LANDSCAPING: Re-spreading of stockpiled topsoil to depth of 100mm Hydromulch grass seeding.	litre m3 lump sum litre m3 litre m3 litre m3 m lump sum lump sum m lump sum No.	160730 1050 1 1 80370 580 22970 1 200	\$ \$	25,000.00 60.00	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	25,000 12,000 214,720
9.1 9.2 9.3 10 10.1 11 11.1 11.2 12 12.1 12.2 12.3 12.4 13 13.1 13.2	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site REMOVAL, DEMOLITION AND RE-ERECTION: Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal flines Linemarking (white paint complete) New signs and posts (Complete) New road edge guid posts (Complete) LANDSCAPING: Re-spreading of stockpiled topsoil to depth of 100mm Hydromulch grass seeding.	litre m3 lump sum litre m3 m m lump sum No.	160730 1050 1 1 80370 580 22970 22970 1 200 67100	\$ \$	25,000.00 60.00	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	25,000. 12,000.
9.1 9.2 9.3 10 10.1 11 11.1 11.2 12 12.1 12.2 12.3 12.4 13 13.1 13.2	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site REMOVAL, DEMOLITION AND RE-ERECTION: Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines Linemarking (white paint complete) New signs and posts (Complete) New road edge guid posts (Complete) LANDSCAPING: Re-spreading of stockpiled topsoil to depth of 100mm Hydromulch grass seeding. MISCELLANEOUS: Retaining structure - Keppel Block including excavation, footing and backfill	litre m3 lump sum litre m3 litre m3 litre m3 m lump sum No. m2 m2 m2 m2	160730 1050 1 1 80370 580 22970 1 200 67100 67100	\$ \$	25,000.00 60.00	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	25,000. 12,000.
9.1 9.2 9.3 10 10.1 11 11.1 11.2 12.1 12.2 12.3 12.4 13.1 13.1 13.2 14.1 14.3	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site REMOVAL, DEMOLITION AND RE-ERECTION: Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines Linemarking (white paint complete) New signs and posts (Complete) New road edge guid posts (Complete) LANDSCAPING: Re-spreading of stockpiled topsoil to depth of 100mm Hydromulch grass seeding. MISCELLANEOUS: Retaining structure - Keppel Block including excavation, footing and backfill Concrete lined invert / barrier kerb to top of retaining walls	litre m3 lump sum litre m3 m m lump sum No. m2 m2 m2 m	160730 1050 1 1 80370 580 22970 1 200 67100 67100	\$ \$ \$	25,000.00 60.00 3.20 0.91	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	25,000,1 12,000,1 214,720,0 61,061,1
9.1 9.2 9.3 10 10.1 11 11.1 11.2 12 12.1 12.2 12.3 12.4 13 13.1 13.2	Primer seal - AMC00 @ 0.9L/m2 Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2 Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site REMOVAL, DEMOLITION AND RE-ERECTION: Removal and re-erection of road furniture SUPPLY OF COVER AGGREGATE: Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2 Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site LINE MARKING AND SIGNAGE: Spotting only for longitudinal lines Linemarking (white paint complete) New signs and posts (Complete) New road edge guid posts (Complete) LANDSCAPING: Re-spreading of stockpiled topsoil to depth of 100mm Hydromulch grass seeding. MISCELLANEOUS: Retaining structure - Keppel Block including excavation, footing and backfill	litre m3 lump sum litre m3 litre m3 litre m3 m lump sum No. m2 m2 m2 m2	160730 1050 1 1 80370 580 22970 1 200 67100 67100	\$ \$	25,000.00 60.00	\$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$ \$	5,000.1

Total for Civil Works (ex GST): \$10,736,225



Project Number: R2018071
Project Name: Agnes Wate
Road Name: Option A (I Agnes Water to Baffle Creek Option A (MCA0) - Ultimate sealed Gladstone Regional Council Location:

Revision **0** 11-Mar-19 Date:

Work Package: Civil Works (Including drainage and retaining Structures):

	Work Package: Civil Works (Including drainage and	Unit of					
Item Number	Description	Measure	Quantity		Unit Rate (\$)	Amo	ount ex GST(
1	EROSION AND SEDIMENT CONTROL:						
1.1	Check Dams, rock (Provisional Quantity)	lump sum	770	\$	216.00	\$	166,320.0
1.2	Silt / Sediment Fence (Provisional Quantity)	m	15400	\$	10.87	\$	167,398.0
2	DRAINAGE STRUCTURES:						
	Culverts (complete):						
	Supply and installation of concrete pipe culvert components, Class 3, 600mm diameter flush joint with	n					
2.1	external bands to AS4058 including excavation, bedding and backfill (complete). Cross drainage	m	16	\$	15,000.00	\$	240,000.0
	located every 500m spacing along alignment.						
	Other:						
2.2	DAF Green classification floodway crossings	Each	4	\$	100,000.00	\$	400,000.
2.3	DAF Amber classification floodway crossings	Each	2	\$	250,000.00	\$	500,000.
3	EARTHWORKS, PREPARATION:						
	Clearing and grubbing, including removal of building structures, retaining structures, vegetation						
3.1	including mulching to stockpile, concrete structures, water tanks, septic tanks and capping and	m2	67100	\$	1.87	\$	125,477.
	removal of bore equipment (Provisional Quantity as directed)						
3.2	Stripping of topsoil (Provisional Quantity as directed)	m3	33550	\$	6.65	\$	223,107.
3.3	Ground surface treatment under embankment, standard	m2	20130	\$	1.20	\$	24,156.
	Excavation and disposal of Unsuitable Material with individual excavation < 10 m3 (Provisional						
3.4	Quantity as directed)	m3	10	\$	50.00	\$	500.
0 -	Excavation and disposal of Unsuitable Material with individual excavation > 10 m3 (Provisional	<u> </u>	45			_	
3.5	Quantity as directed)	m3	4500	\$	16.65	\$	74,925.
4	EARTHWORKS, EXCAVATION:	1		1		t	
4.1	Road excavation, all materials	m3	89400	\$	11.25	\$	1,005,750.0
	Excavation of non-rippable material in road excavation, rate additional to rate for Work Item 3201						
4.2	(Provisional Quantity)	m3	4500	\$	60.50	\$	272,250.0
	(110VISIONAL Quality)	1		1			
5	EARTHWORKS, EMBANKMENT:	1		1			
5.1	Road embankment	m3	13900	\$	6.95	\$	96,605.0
0.1	TOUG CHIBANATION	1110	10000	Ψ	0.00	Ψ	50,000.0
6	EARTHWORKS, SUBGRADE:	+	<u> </u>				
6.1	Testing of existing material below subgrade level in cuttings (Provisional Quantity if ordered)	por cot	460	\$	450.00	¢.	207,000.0
		per set				φ	
6.2	Subgrade treatment Type A in cuttings (Provisional Quantity if ordered)	m2	40260	\$	1.75	\$	70,455.0
	EARTHWORKS BASKETT	1	ļ	-			
7	EARTHWORKS, BACKFILL:	_	4500		70.05		010 105
7.1	Backfill with general backfill material to areas of unsuitable	m3	4500	\$	70.25	\$	316,125.0
8	UNBOUND PAVEMENTS:						
8.1	Base Course Type 2.1 200mm (CBR 80)	m3	21855.364		122.50	\$	2,677,282.0
8.2	Sub-base Course Type 2.3 300mm (CBR45)	m3	37263.831	\$	97.50	\$	3,633,223.
8.3	Geotextile under sub-base pavement	m2	118580	\$	1.50	\$	177,870.0
9	SPRAYED BITUMINOUS SURFACING (EXCLUDING EMULSION):						
9.1	Primer seal - AMC00 @ 0.9L/m2	litre	103330	\$	1.95	\$	201,493.
9.2	Seal (1st Coat) - PMB (S0.7S) @ 1.4L/m2	litre	160730	\$	1.95	\$	313,423.
9.3	Supply and spreading cover aggregate 14mm, 110 m2/m3, on job site	m3	1050	\$	202.50	\$	212,625.
10	REMOVAL, DEMOLITION AND RE-ERECTION:						
10.1	Removal and re-erection of road furniture	lump sum	1	\$	5,000.00	\$	5,000.
							.,
11	SUPPLY OF COVER AGGREGATE:						
11.1	Seal (2nd Coat) - PMB (S0.7S) @ 0.7L/m2	litre	80370	\$	2.00	\$	160,740.
11.2	Supply and spreading cover aggregate 10mm, 200 m2/m3, on job site	m3	580	\$	218.50	\$	126,730.
	Tapan and an analysis and an a		000	*	2.0.00	Ÿ	.20,.00.
12	LINE MARKING AND SIGNAGE:	+	†				
12.1			22970	¢	0.50	2	11,485.
	Spotting only for longitudinal lines	m		\$		\$	
12.2	Linemarking (white paint complete)	m human auma	22970	\$	1.45		33,306.
12.3	New signs and posts (Complete)	lump sum	7	\$	25,000.00	\$	25,000.
12.4	New road edge guid posts (Complete)	No.	200	\$	60.00	\$	12,000.
40	L ANDOGA PINIO	 	 	1			
13	LANDSCAPING:		07105				011 ====
13.1	Re-spreading of stockpiled topsoil to depth of 100mm	m2	67100	\$	3.20	\$	214,720.
	Hydromulch grass seeding.	m2	67100	\$	0.91	\$	61,061
13.2	1						
			1	1			
14	MISCELLANEOUS:						
	MISCELLANEOUS: Retaining structure - Keppel Block including excavation, footing and backfill	m2	0			\$	
14		m2 m	0 240			\$	-
14 14.1	Retaining structure - Keppel Block including excavation, footing and backfill			\$	2,500.00	\$	40,000.
14 14.1 14.3	Retaining structure - Keppel Block including excavation, footing and backfill Concrete fined invert / barrier kerb to top of retaining walls	m	240	\$	2,500.00	_	40,000.

Total for Civil Works (ex GST): \$11,796,029

APPENDIX

C

GEOTECHNICAL REPORT



Our Ref: 2128E.P.959 Contact: Poka Kilaverave

7th February 2019

Cardno QLD Pty Ltd Locked Bag 4006 Fortitude Valley 4006

Attention: Gerry Moore

Email: gerry.moore@cardno.com.au

Dear Gerry,

2128E.P.958 – Proposed Inland Link Road Connecting
Agnes Water and Baffle Creek – Geotechnical Investigation and Factual Report

Introduction

Construction Sciences Pty Ltd (CS) was commissioned by Cardno QLD Pty Ltd to undertake ground investigations for the proposed link road connecting Agnes Water and Baffle Creek. Approximate locations for the boreholes were provided by Cardno QLD Pty Ltd. Figure 1 below shows the actual locations undertaken as part of this investigation.



Figure 1 Overall Site Location Plan


Based on the scope of works as provided in our proposal with Ref No. 2128E.Q.114 dated 13th December 2018, the following was undertaken as part of the fieldwork from the 23rd to 25th January 2019, for general geotechnical assessment purposes;

- 23 No. boreholes utilising a Landcruiser Mounter Drill Rig with 100mm auger to a depth of 1.0m below the existing surface or prior auger refusal on competent rock. Borehole BHA19 was omitted due to access issues.
- Logging of the encountered soil profile was in accordance with AS1726:2017 "Geotechnical Site Investigations" with sampling of each subgrade materials at generally between 0.3m to 1m intervals.
- Dynamic Cone Penetrometer Soundings (DCPs) at each borehole location to a maximum depth of 1.0m below subgrade level to determine the consistency of subsurface strata and determine Insitu CBR by DCP (Q114B).

Ground and Groundwater Conditions


The ground surface conditions varied across the proposed alignments with alluvial and residual soils encountered. In areas of low relief, colluvium and alluvial soils comprising of sands silts and clays were encountered, while areas of high relief comprised predominantly of gravel composition trending onto rock. The borehole logs provides a detailed description of the strata encountered at each test location and are considered to be consistent with the geological mapping.

An extract of the "Miriam Vale Special Sheet 9249 and Part 9250 & 9349" of the 1:100 000 geological series published by the Geological Survey of Queensland (GSQ), Department of Mines and Energy, Queensland is provided for information purposes only.



Coherent and autoclastic rhyolite; domes and cryptodomes

Submerged rock platform



No groundwater was encountered in any of the boreholes during the investigation. However, it is possible that seepage could occur through the alluvial soils and along the soil/rock interface during and after periods of wet weather. In areas where soils of high silt composition were encountered (ML), these subsoils would have potential to become swampy under saturated conditions.

For details of the strata encountered at each test location, the logs are included at the end of this letter report.

In Situ Test Results

Dynamic Cone Penetrometer soundings (DCPs) we conducted at the location of each borehole to a maximum depth of 1.0m below subgrade level to determine the consistency of subsurface strata and determine Insitu CBR by DCP (Q114B). The test reports are available for review at the rear of this letter report.

We trust this satisfies your present requirements. Should you have any further enquiries regarding this please do not hesitate to contact us to discuss.


Poka Kilaverave Geotechnical Engineer

For and on behalf of

Construction Sciences Pty Ltd

Enclosed: Site Plans, Borehole Logs, Insitu CBR Test Results





Agnes Water to Baffle Creek (Northern Section)





Agnes Water to Baffle Creek (Southern Section)

PAGE 1 OF 1

<u></u>	Construction
==	Sciences

						PROJECT NAME Proposaed Inland Link Road PROJECT LOCATION COnnecting Agnes Water to Baffle Creek		
					COMPLETED 23/1/19 R.L.			
					onstruction Sciences Pty Ltd SLO			
					HOL			
			100mm		LOG			
NOT	ES	_GP	S Co-ordin		66J, E: 387375,N: 7306726			
				_				
- 1	Water	RL (m)	(m) https://deach.com/deac	Classification Symbol	Material Description		Samples Tests Remarks	Additional Observations
AUGER					Clayey Sandy GRAVEL (FILL) fine to medium grained a plasticity fines, fine to coarse grained sand, dry, very de Sandy CLAY (RESIDUAL) medium plasticity, red/brown sand, dry, very stiff.	nse.		
			0.5					
			1.0		red/brown mottle yellow/brown.			
			1. <u>5</u>		BOREHOLE TERMINATED AT 1.0m			



ABN: 74 128 806 735

Address:

101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 Fax: 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

Client: CONSTRUCTION SCIENCES - RTON

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

Project: General Testing - Engineering

Location: North Rockhampton

Supplied To: n/a

Area Description:

Report Number: 2128/R/44313-1

2135/P/415 Project Number:

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Page 1 of 23 Report Date / Page: 5/02/2019

Test Procedures Q114B

Sample Number 2128/S/78949

Sampling Method

24/01/2019

Date Sampled Sampled By

Nicole Bella & Mark Walters

Date Tested

24/01/2019

Moisture Condition

Material Description

Dry

Clayey Sandy Gravel - Sandy Clay


Sample Location

Bore Hole No.

Depth (m) Seated @ 0.5m

Material Source

Material Type



Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



PAGE 1 OF 1

<u></u> _	Construction
==	Sciences

				D Pty Lto 2128E.	1 P.959				
DR EQ HO	ILLI UIPI LE S	NG CO MENT SIZE	ONTRAC Quick	ctor <u>c</u>	onstruction Sciences Pty Ltd				
Method	Water			Graphic Log Classification Symbol	Material Desc	ription	Samples Tests Remarks	Additional Observations	
AUGER			0.5 	SP	SAND (ALLUVIUM) fine to coarse grained sa coarse grained gravel, negligible to low plasticular moist. BOREHOLE TERMINATED AT 1.0m	and, brown/grey, trace of fine to city fines, dry, dense.			



ABN: 74 128 806 735

Address: 101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 Fax: 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

CONSTRUCTION SCIENCES - RTON Client:

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

Project: General Testing - Engineering

Location: North Rockhampton

Supplied To: n/a

Area Description:

Report Number: 2128/R/44313-1

Project Number: 2135/P/415

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Page 2 of 23 Report Date / Page: 5/02/2019

Sample Location

Test Procedures Q114B

Sample Number 2128/S/78950

Sampling Method

Date Sampled 24/01/2019

Sampled By

Material Description

15 - 293 mm

Nicole Bella & Mark Walters

Date Tested Moisture Condition

24/01/2019

13

Dry to Moist

Sand

Bore Hole No.

Depth (m)

Seated @ 0.45m


Material Source -

Material Type

Equivalent California Bearing Ratio Layer Breakdown and Results						
Layer Limits (mm)	Equivalent CBR					

	. •
293 - 353 mm	6
353 - 527 mm	12
527 - 758 mm	14
758 - 1009 mm	13





Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



PAGE 1 OF 1

<u></u>	Construction
==	Sciences

CLIENT Cardno QLD Pty Ltd PROJECT NUMBER 2128E.P.959 DATE STARTED 23/1/19 COMPLETED 23/1/19 DRILLING CONTRACTOR Construction Sciences Pty Ltd EQUIPMENT Quickdrill HOLE SIZE 100mm NOTES GPS Co-ordinates: 56J, E: 387687,N: 7309039										
						COMPLETED 23/1/19 onstruction Sciences Pty Ltd	R.L. SURFACESLOPE _90°		DATUM	
							LOGGED BY M.Walters		CHECKED BY P.Kilaverave	
Method	Water	RL (m)		Graphic Log	Classification Symbol	Material Desc	ription	Samples Tests Remarks	Additional Observations	
AUGER N	<u> </u>		0.5 1.0 2.0 2.5 3.0 4.0		SC CL/CI	Clayey SAND (ALLUVIUM) fine to coarse grafines, dry, very dense. Gravelly Sandy CLAY (RESIDUAL) low to medium grained sub-angular gravel, fine to divery stiff to hard. dry, hard. BOREHOLE TERMINATED AT 1.0m	edium plasticity, red/brown, fine to			



ABN: 74 128 806 735

Address:

101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 Fax: 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

Client: CONSTRUCTION SCIENCES - RTON

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

Project: General Testing - Engineering

Location: North Rockhampton

Supplied To: n/a

Area Description:

Report Number: 2128/R/44313-1

> Project Number: 2135/P/415

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Page 3 of 23 Report Date / Page: 5/02/2019

Test Procedures Q114B Sample Location

Sample Number 2128/S/78951 Bore Hole No. 3

Sampling Method Depth (m)


Date Sampled

24/01/2019

Sampled By Nicole Bella & Mark Walters

Date Tested 24/01/2019 Material Source Moisture Condition Material Type Dry

Material Description Clayey Sand



Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



PAGE 1 OF 1

<u></u> _	Construction
==	Sciences

CLI	EN	Г <u>Ca</u>	rdno QLD F	ty Ltd		PROJECT NAME Proposaed Inland Link Road		
PR	OJE	CT N	JMBER _2	128E.F	2.959	PROJECT LOCATION _C	Onnecting Agr	es Water to Baffle Creek
DR	LLI	NG CO	ONTRACTO	R _C	COMPLETED 23/1/19 construction Sciences Pty Ltd	SLOPE 90°		
EQ	UIP	MENT	Quickdril					
			100mm			LOGGED BY M.Walters		CHECKED BY P.Kilaverave
NO	TES	GP	S Co-ordina	ates: 5	6J, E: 387957,N: 7311080			
Method	Water	RL (m)	(m) ytdad Graphic Log	Classification Symbol	Material Descriptio		Samples Tests Remarks	Additional Observations
GER			-[.0]	GC	brown/grey, low plasticity fines, fine to coarse grain	ned angular gravel, pale ned sand, cobbles present, dry,		
AUGER N			,,,	GC	Clayey Sandy GRAVEL (FILL) fine to coarse grain brown/grey, low plasticity fines, fine to coarse grain very dense. Silty SAND (RESIDUAL) fine to medium grained so low plasticity fines, dry, very dense. becoming fine to coarse grained sand. BOREHOLE TERMINATED AT 1.0m	ned sand, cobbles present, dry,		
			5.0					



ABN: 74 128 806 735

Address:

101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 Fax: 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

CONSTRUCTION SCIENCES - RTON Client:

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

Project: General Testing - Engineering

Location: North Rockhampton

Supplied To: n/a

Area Description:

Report Number: 2128/R/44313-1

Project Number: 2135/P/415

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Page 4 of 23 Report Date / Page: 5/02/2019

Sample Location

Test Procedures Q114B

Sample Number 2128/S/78952

Sampling Method

24/01/2019

Date Sampled Sampled By

Nicole Bella & Mark Walters

Date Tested

24/01/2019

Silty Sand

Moisture Condition Material Description Dry

Bore Hole No. Depth (m)


Seated @ 0.2m

Material Source -

Material Type

Equivalent California Bearing Ratio Layer
Breakdown and Results

breakdown and Results					
Layer Limits (mm)	Equivalent CBR				
6 - 7 mm	>60				
7 - 8 mm	>60				
8 - 14 mm	>60				
14 - 14 mm					



Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



PAGE 1 OF 1

<u></u>	Construction
==	Sciences

	CLIENT Cardno QLD Pty Ltd PROJECT NUMBER 2128E.P.959							
D# DF EC	ATE S RILLI QUIPI DLE S	STAR NG C MENT SIZE	TED _23/ ONTRACT · _Quickd 100mm	1/19 F OR _C	construction Sciences Pty Ltd	R.L. SURFACE DATUM SLOPE 90° BEARING HOLE LOCATION As Marked on Site Plan in Appendix A LOGGED BY M.Walters CHECKED BY P.Kilaverave		
Method	Water	RL (m)	Depth (m) Daphic Log	Classification Symbol	Material Descript	ion	Samples Tests Remarks	Additional Observations
BONETICLE / IEST PTI ZIZOE: T. 393 LOGS: GF3 GINT AGS INVENTION OF THE PROPERTY OF THE PROPERT			1.0 2.0 2.5 3.0 4.0 4.5	0	Clayey Sandy GRAVEL (FILL) fine to coarse grabrown/grey, low plasticity fines, fine to coarse gravery dense. SAND (RESIDUAL) fine to coarse grained sand grained angular gravel, dry to moist, very dense. becoming moist. BOREHOLE TERMINATED AT 0.9m	ained sand, cobbles present, dry, , pale brown, with fine to medium		



ABN: 74 128 806 735

Address:

101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 Fax: 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

CONSTRUCTION SCIENCES - RTON Client:

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

Project: General Testing - Engineering

Location: North Rockhampton

Supplied To: n/a

Area Description:

Report Number: 2128/R/44313-1

> Project Number: 2135/P/415

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Page 5 of 23 Report Date / Page: 5/02/2019

Seated @ 0.3m

Test Procedures Q114B

Sample Number 2128/S/78953

Sampling Method

Date Sampled 24/01/2019

Sampled By

Material Description

Nicole Bella & Mark Walters

24/01/2019 Date Tested Moisture Condition Dry to Moist Depth (m)

Bore Hole No.

Sample Location


Material Source

Material Type

Equivalent California Bearing	Ratio	Laver
Equivalent Galilottila Deating	Natio	Layer

Sand

Breakdown	and Results
Layer Limits (mm)	Equivalent CBR
11 - 67 mm	19
67 - 100 mm	20
100 - 106 mm	40
106 - 119 mm	>60
119 - 122 mm	>60



Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



PAGE 1 OF 1

<u></u>	Construction
==	Sciences

	Cardno QLD Pty L	_td E.P.959				
DATE STA DRILLING EQUIPMEN HOLE SIZE	RTED 23/1/19 CONTRACTOR _ IT _Quickdrill = _100mm	COMPLETED 23/1/19 Construction Sciences Pty Ltd	R.L. SURFACE DATUM			
NOTES (uppic Log	: 56J, E: 388237,N: 7313238 Material Desc	ription	Samples Tests Remarks	Additional Observations	
AUGER	0.5 CI	low plasticity fines, dry to moist, very dense.				
	1.5 	BOREHOLE TERMINATED AT 1.0m				



ABN: 74 128 806 735

Address: 101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 Fax: 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

Client: CONSTRUCTION SCIENCES - RTON

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

Project: General Testing - Engineering

Location: North Rockhampton

Supplied To: n/a

Area Description:

Report Number: 2128/R/44313-1

2135/P/415 Project Number:

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Page 6 of 23 Report Date / Page: 5/02/2019

Test Procedures Q114B Sample Location

Sample Number 2128/S/78954

Sampling Method

Material Description

Date Sampled

24/01/2019

Sampled By Nicole Bella & Mark Walters

Date Tested 24/01/2019 Moisture Condition Dry to Moist


Silty Sand - Sandy Clay

Bore Hole No. 6

Depth (m)

Material Source

Material Type



Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



PAGE 1 OF 1

<u></u>	Construction
==	Sciences

CLIENT _Cardno QLD Pty Ltd PROJECT NUMBER _2128E.P.959							PROJECT NAME Propo		es Water to Baffle Creek
						COMPLETED 24/1/19 R.			
						onstruction Sciences Pty Ltd SL			
						но			
			100mr			LC			
NOTI	ES	_GP	S Co-o			6J, E: 388540,N: 7314024			
	water	RL (m)	Depth (m)		Symbol	Material Description		Samples Tests Remarks	Additional Observations
AUGER			0.5		Z/MI	Sandy Clayey SILT (COLLUVIUM) low to medium pla medium grained sand, dry to moist, dense. Sandy CLAY (ALLUVIUM) medium plasticity, pale gremedium grained sand, dry to moist, very stiff.			
+			1.0			BOREHOLE TERMINATED AT 1.0m			
			1.5 						



ABN: 74 128 806 735

Address:

101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 Fax: 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

Client: CONSTRUCTION SCIENCES - RTON

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

General Testing - Engineering Project:

Location: North Rockhampton

Supplied To: n/a

Area Description:

Report Number: 2128/R/44313-1

Project Number: 2135/P/415

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Page 7 of 23 Report Date / Page: 5/02/2019

Q114B Sample Location Test Procedures

Sample Number 2128/S/78955 Bore Hole No. 7


Sampling Method Depth (m)

Date Sampled 24/01/2019

Sampled By Nicole Bella & Mark Walters

Date Tested 24/01/2019 Material Source Moisture Condition Material Type Dry to Moist

Material Description Sandy Clayey Silt - Sandy Clay



Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



PAGE 1 OF 1

<u></u>	Construction
==	Sciences

						PROJECT NAME Propo		k Road es Water to Baffle Creek
					COMPLETED 24/1/19 F			
					onstruction Sciences Pty Ltd S			
					H			
					L			
					6J, E: 388409,N: 7314457			
Method	Water	RL (m)	(w) updad Graphic Log	Classification Symbol	Material Description		Samples Tests Remarks	Additional Observations
AUGER			0.5 1.5 	CL ML	Gravelly Sandy CLAY (FILL) low plasticity, pale grey grained saub-angular gravel, fine to coarse grained Sandy SILT (COLLUVIUM) low plasticity, grey, fine to moist, dense. Clayey SILT (COLLUVIUM) low plasticity, grey, trace sand, dry to moist, stiff. BOREHOLE TERMINATED AT 1.0m	sand, dry, very stiff. o medium grained sand, dry		



ABN:

74 128 806 735

Address: 101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 Fax: 07 4926 1286

Bore Hole No.

Depth (m)

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

Client: CONSTRUCTION SCIENCES - RTON

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

Project: General Testing - Engineering

Location: North Rockhampton

Supplied To: n/a

Area Description:

Report Number: 2128/R/44313-1

Project Number: 2135/P/415

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Page 8 of 23 Report Date / Page: 5/02/2019

8

Test Procedures Q114B Sample Location

Sample Number 2128/S/78956

Sampling Method

Material Description

Date Sampled


24/01/2019

Sampled By Nicole Bella & Mark Walters


24/01/2019 Date Tested Moisture Condition

Material Source

Material Type Dry - Dry to Moist Gravelly Sandy Clay - Sandy Silt - Clayey Silt



Dieakdowii	and results
Layer Limits (mm)	Equivalent CBR
6 - 49 mm	40
49 - 148 mm	8
148 - 231 mm	35
231 - 300 mm	50
300 - 349 mm	50
349 - 357 mm	>60



Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



PAGE 1 OF 1

<u></u>	Construction
7	Sciences

			ardno (P.959				
DA DR EQ HO	TE S	STAR NG CO MENT SIZE	ONTRA Quid	24/1/ ACTO ckdrill	19 R _Co	COMPLETED _24/1/19 onstruction Sciences Pty Ltd	R.L. SURFACESLOPE _90°HOLE LOCATION _As Mai	BEARING Plan in Appendix A		
Method	Water		Depth (m)	Graphic Log	Classification Symbol	6J, E: 388850,N: 7314257 Material Descrip	otion	Samples Tests Remarks	Additional Observations	
AUGER			0.5 0.5 1.0 1.5 2.0 2.5 3.0 4.0 4.5		CI	Sandy SILT (COLLUVIUM) low plasticity, grey, moist, very dense. Sandy CLAY (ALLUVIUM) medium plasticity, grained sand, moist (at plastic limit), stiff, trace gravel. BOREHOLE TERMINATED AT 1.0m	rey mottle brown, fine to medium			



ABN: 74 128 806 735

Address: 101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 Fax: 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

CONSTRUCTION SCIENCES - RTON Client:

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

Project: General Testing - Engineering

Location: North Rockhampton

Supplied To: n/a

Area Description:

Report Number: 2128/R/44313-1

> Project Number: 2135/P/415

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Page 9 of 23 Report Date / Page: 5/02/2019

Test Procedures Q114B

Sample Number 2128/S/78957

Sampling Method

Material Description

Sampled By

24/01/2019

Date Sampled

Date Tested 24/01/2019 Moisture Condition Moist

Nicole Bella & Mark Walters

Sandy Clay

Bore Hole No.

Depth (m)

Sample Location


Seated @ 0.5m

Material Source

Material Type

E	Equivalent California Bearing Ratio	Layer
	Breakdown and Results	

Layer Limits (mm)	Equivalent CBR
17 - 157 mm	13
157 - 303 mm	14



Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



BOREHOLE NUMBER BH10 PAGE 1 OF 1

<u></u>	Construction
==	Sciences

CLIEN	IT _C	ardno	QLD F	ty Ltd		PROJECT NAME _F	Proposaed Inland L	ink Road
PROJ	ECT N	IUMBE	R _21	28E.F	P.959	PROJECT LOCATIO	ON COnnecting Ag	nes Water to Baffle Creek
DATE	STAF	RTED	24/1/	19	COMPLETED 24/1/19	R.L. SURFACE		DATUM
DRILI	ING C	ONTR	ACTO	R _Cc	onstruction Sciences Pty Ltd	SLOPE _90°		BEARING
		T Qu				HOLE LOCATION _A	s Marked on Site P	lan in Appendix A
HOLE	SIZE	100r	nm			LOGGED BY M.Wal	ters	CHECKED BY P.Kilaverave
NOTE	S _G	PS Co	-ordina	ates: 5	6J, E: 389340,N: 7313827			
Method	RL (m)		Graphic Log	Classification Symbol	Material Descr	•	Samples Tests Remarks	Additional Observations
AUGER		0 <u>.5</u>		ML	Sandy Clayey SILT (COLLUVIUM) low plastic grained sand, dry to moist, dense. moist (below plastic limit), medium dens very dense.			
		1.0			,			
		1.5 			BOREHOLE TERMINATED AT 1.0m			



ABN: 74 128 806 735

Address: 101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 Fax: 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

CONSTRUCTION SCIENCES - RTON Client:

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

Project: General Testing - Engineering

Location: North Rockhampton

Supplied To: n/a

Area Description:

Report Number: 2128/R/44313-1

> Project Number: 2135/P/415

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Sample Location

10

Page 10 of 23 Report Date / Page: 5/02/2019

Seated @ 0.45m

Test Procedures Q114B Bore Hole No.

Sample Number 2128/S/78958

Sampling Method

Date Sampled 24/01/2019

Sampled By

Nicole Bella & Mark Walters

Date Tested 24/01/2019 Moisture Condition Dry to Moist

Depth (m)

Material Source -Material Type

Material Description Sandy Clayey Silt

Material Description	Sandy Clayey Sill	
Equivalent California Breakdown	a Bearing Ratio Layer and Results	DYNAMIC CONE PENETROMETER TEST PLOT
Layer Limits (mm)	Equivalent CBR	
17 - 151 mm	10	30 -
151 - 245 mm	45	60 -
245 - 251 mm	40	90 -
251 - 254 mm	>60	120 - 150 - 210 - 240 - 270 - 0 5 10 15 20 25 30 Hammer Blows

Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



PAGE 1 OF 1

<u></u>	Construction
==	Sciences

		Ca Ca	rdno QLD F	Pty Ltd		PROJECT NAME Prop	oosaed Inland L	ink Road	
PR	OJE	CT N	UMBER _2	128E.F	2.959	PROJECT LOCATION _	COnnecting A	gnes Water to Baffle Creek	
DA [·]	TE S	STAR	TED _24/1/	19	COMPLETED 24/1/19	R.L. SURFACE	R.L. SURFACE		
DR	ILLII	NG C	ONTRACTO	R _C	onstruction Sciences Pty Ltd			BEARING	
			Quickdril					Plan in Appendix A	
			100mm			LOGGED BY M.Walters	1	CHECKED BY P.Kilaverave	
NO	TES	GP	S Co-ordina	ates: 5	6J, E: 389401,N: 7314341				
Method	Water	RL (m)	Depth (m) Qraphic Log	Classification Symbol	Material Desc	ription	Samples Tests Remarks	Additional Observations	
AUGER M	M N	(m)	1.5 2.0 2.5 3.5	ML O	Sandy SILT (COLLUVIUM) low plasticity, gramoist, dense. BOREHOLE TERMINATED AT 1.0m	ey, fine to medium grained sand,			



ABN: 74 128 806 735

Address:

101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 **Fax:** 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

Client: CONSTRUCTION SCIENCES - RTON

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

Project: General Testing - Engineering

Location: North Rockhampton

Supplied To: n/a

Area Description:

Report Number: 2128/R/44313-1

Project Number: 2135/P/415

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Report Date / Page: 5/02/2019 Page 11 of 23

11

Test Procedures Q114B Sample Location

Sample Number 2128/S/78959

Sampling Method

2120/0//0000

camping monea

Date Sampled 24/01/2019

Sampled By Date Tested Nicole Bella & Mark Walters

Moisture Condition

24/01/2019

loisture Condition Mois

Moist

Material Source -

Material Type

Bore Hole No.

Depth (m)

Material Description Sandy Silt

Equivalent California Breakdown	Bearing Ratio Layer and Results	DYNAMIC CONE PENETROMETER TEST PLOT	
Layer Limits (mm)	Equivalent CBR	10	
4 - 91 mm	60	20 -	
91 - 103 mm	>60	30	
103 - 107 mm	>60	_ 40 -	
107 - 108 mm	>60	DC Benetration (mm) 50 - 60 - 70 - 70 - 70 - 70 - 70 - 70 - 7	
		년 60 -	
		20 - 10 - 10 - 10 - 10 - 10 - 10 - 10 -	
		80 -	
		90	\dashv
		100	
		110 -	
		0 5 10 15 20 25 3	,
		Hammer Blows	

Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.

Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



PAGE 1 OF 1

<u></u>	Construction
==	Sciences

CLI	ENT	_Ca	rdno	QLD F	Pty Ltd		PROJECT NAME Propo	saed Inland Li	nk Road
PR	OJE	CT NI	JMBE	R _21	128E.F	2.959	PROJECT LOCATION _	COnnecting Ag	nes Water to Baffle Creek
						COMPLETED 23/1/19			DATUM
									DATUM
						onstruction Sciences Pty Ltd			BEARING
				ickdrill			_ HOLE LOCATION AS MA	rked on Site Pi	an in Appendix A
			100n				LOGGED BY _M.Waiters_		CHECKED BY P.Kilaverave
NO	IES	_GP	S Co.	-oraina	ates: 5	6J, E: 389486,N: 7314942			
Method	Water	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Descrip		Samples Tests Remarks	Additional Observations
AUGER			-		ML	Sandy SILT (COLLUVIUM) low plasticity, pale of sand, dry, very dense.	grey, fine to medium grained		
			0 <u>.5</u>		ML	Sandy SILT (COLLUVIUM) low plasticity, pale of dry to moist, very dense.	grey, fine to coarse grained sand,		
			1.0						
			- -			BOREHOLE TERMINATED AT 1.0m			
			1 <u>.5</u>	-					
			- - -						
			2.0						
			- - -	-					
			2 <u>.5</u>						
			- -						
			3 <u>.0</u>						
			- -						
			3 <u>.5</u> –						
			- - -						
			4 <u>.0</u> -						
			4 <u>.5</u>						



ABN: 74 128 806 735

Address: 101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 Fax: 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

CONSTRUCTION SCIENCES - RTON Client:

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

Project: General Testing - Engineering

Location: North Rockhampton

Supplied To: n/a

Area Description:

Report Number: 2128/R/44313-1

Project Number: 2135/P/415

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

12

Page 12 of 23 Report Date / Page: 5/02/2019

Test Procedures Q114B Sample Location

Sample Number 2128/S/78960

Sampling Method

Date Sampled

24/01/2019

Sandy Silt

Sampled By

Material Description

Nicole Bella & Mark Walters

Date Tested Moisture Condition

24/01/2019

Moist

Material Source


Material Type

Bore Hole No.

Depth (m)

_	
	Equivalent California Bearing Ratio Layer
	Equivalent Gamerina Boaring Matte Eayer
	Dan all all and an all Dan and La

Breakdown and Results					
Layer Limits (mm)	Equivalent CBR				
5 - 108 mm	40				
108 - 206 mm	30				
206 - 281 mm	40				
281 - 462 mm	30				
462 - 514 mm	30				
514 - 526 mm	>60				



Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



PAGE 1 OF 1

<u></u>	Construction
==	Sciences

					P.959 COMPLETED 23/1/19			nes Water to Baffle Creek
					onstruction Sciences Pty Ltd			
			Quickdril					lan in Appendix A
			100mm					
NOT	ES	GP	S Co-ordin	ates: 5	6J, E: 389679,N: 7316050			
- 1	Water	RL (m)	(m) htdəd Graphic Log	Classification Symbol	Material Description		Samples Tests Remarks	Additional Observations
AUGER				ML	Sandy SILT (COLLUVIUM) low plasticity, pale grey trace of fine grained sub-angular gravel, dry, density	e.		
			0.5	ML	Sandy SILT (COLLUVIUM) low plasticity, pale grey dry to moist, very dense.	y, fine to coarse grained sand,		
			1.0		BOREHOLE TERMINATED AT 1.0m			
			1.5					
			2.0					
			2.5					
			3.0					
			<u> </u>					
			3. <u>5</u>					
			4.0					
			4.5					
			5.0					



ABN: 74 128 806 735

Address:

101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 **Fax:** 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

Client: CONSTRUCTION SCIENCES - RTON

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

Project: General Testing - Engineering

Location: North Rockhampton

Supplied To: n/a

Area Description:

Report Number: 2128/R/44313-1

Project Number: 2135/P/415

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Report Date / Page: 5/02/2019 Page 13 of 23

13

Test Procedures Q114B Sample Location

Sample Number 2128/S/78961

Sampling Method

24/01/2019

Date Sampled

Sampled By


Nicole Bella & Mark Walters

Date Tested 24/01/2019 Moisture Condition Dry - Moist Depth (m)

Material Source -

Bore Hole No.

Material Type



Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.

Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



PAGE 1 OF 1

<u></u>	Construction
==	Sciences

					P.959			nk Road nes Water to Baffle Creek
					COMPLETED 24/1/19	R.L. SURFACE		DATUM
					onstruction Sciences Pty Ltd			
					,			
		100						
NOTE	s _0	SPS C	o-ordina	ates: 5	6J, E: 389300,N: 7316126			
Method	RL (m		Graphic Log	Classification Symbol	Material Descriptio	n	Samples Tests Remarks	Additional Observations
		0.		GC GC SM	Sandy Clayey GRAVEL (FILL) fine to coarse gragey, fine to coarse grained sand, with cobbles, d Clayey Sandy GRAVEL (RESIDUAL) fine to med pale grey, low plasticity fines, fine to coarse grained Silty SAND (RESIDUAL) fine to coarse grained sa plasticity fines, with fine to medium grained sub-adense. Sandy CLAY (RESIDUAL) low plasticity, pale grey dry to moist, hard.	ry, very dense. ium grained sub-angular gravel, ed sand, dry, very dense. and, pale grey, negligible to low ngular gravel, moist, very		
		1.0						
		1.1 2.1 3.1 4.1 4.1	5		BOREHOLE TERMINATED AT 1.0m			



ABN: 74 128 806 735

Address:

101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 Fax: 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

CONSTRUCTION SCIENCES - RTON Client:

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

Project: General Testing - Engineering

Location: North Rockhampton

Supplied To: n/a

Area Description:

Report Number: 2128/R/44313-1

Project Number: 2135/P/415

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Page 14 of 23 Report Date / Page: 5/02/2019

Test Procedures Q114B Sample Location

Sample Number 2128/S/78962 Bore Hole No. 14


Sampling Method Depth (m) Seated @ 0.35m

Date Sampled 24/01/2019

Sampled By Nicole Bella & Mark Walters

24/01/2019 Material Source -Date Tested Moisture Condition Material Type Moist

Material Description Silty Sand



Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



PAGE 1 OF 1

<u></u>	Construction
==	Sciences

						P.959	PROJECT NAME Proposaed Inland Link Road PROJECT LOCATION COnnecting Agnes Water to Baffle Creek		
						COMPLETED 24/1/19	R.L. SURFACE		DATUM
						onstruction Sciences Pty Ltd			
			100n						
NO.	TES	GP	S Co-	ordina	ates: 5	6J, E: 389661,N: 7316421			
Method	Water	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description		Samples Tests Remarks	Additional Observations
AUGER			0.5 1.0 1.5 2.0 3.5 4.0 4.5 - 4.		GC ML	Sandy Clayey GRAVEL (FILL) fine to coarse grain brown, fine to coarse grained sand, low plasticity for Gravelly Sandy SILT (RESIDUAL) low plasticity, pgravel, fine to medium grained sand, dry, dense. BOREHOLE TERMINATED AT 0.35m - AUGER F	ines, with cobbles, dry. ale grey, fine to coarse grained		



ABN: 74 128 806 735

Address:

101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 Fax: 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

Client: CONSTRUCTION SCIENCES - RTON

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

Project: General Testing - Engineering

Location: North Rockhampton

Supplied To: n/a

Area Description:

Report Number: 2128/R/44313-1

Project Number: 2135/P/415

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Page 15 of 23 Report Date / Page: 5/02/2019

Test Procedures Q114B Sample Location

Sample Number 2128/S/78963 Bore Hole No. 15

Sampling Method Depth (m) Seated @ 0.15m


Date Sampled Sampled By Nicole Bella & Mark Walters

24/01/2019

Date Tested 24/01/2019 Material Source

Moisture Condition Material Type Dry

Material Description Gravelly Sandy Silt



Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



PAGE 1 OF 1

<u></u>	Construction
==	Sciences

CLIENT Cardno QLD Pty Ltd PROJECT NAME Proposaed Inland Link Road						nk Road			
PR	OJE	CT N	JMBE	R _2	2128E.P.959 PROJECT LOCATION COnnecting Agnes Water to Baffle Creek				
DR	ILLII	NG CO	ONTR	АСТО	R _Cc	COMPLETED 24/1/19 construction Sciences Pty Ltd	SLOPE 90° BEARING		BEARING
EQUIPMENT Quickdrill HOLE LOCATION As HOLE SIZE 100mm LOGGED BY M.Walte									CHECKED BY P.Kilaverave
NOTES GPS Co-ordinates: 56J, E: 389786,N: 7316804									
Method	Water	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Descriptio	n	Samples Tests Remarks	Additional Observations
AUGER			_		GW	Sandy GRAVEL (FILL) fine to coarse grained gra grained sand, with cobbles, trace of negligible pla	vel, brown, fine to coarse sticity clay, dry, dense.		
AL			0 <u>.5</u>		CL	Sandy CLAY trace Gravel (RESIDUAL) low plasti grained sand, trace fine grained sub-angular grav	city, brown, fine to coarse el, moist, stiff.		
			-		SC	Gravelly Clayey SAND (RESIDUAL) fine to coars medium grained sub-angular gravel, low plasticity	fines, dry to moist, very dense.		
			1.0 			BOREHOLE TERMINATED AT 0.8m - AUGER R	EFUSAL ON BEDROCK		
			+. <u>5</u> - - - 5.0						



ABN: 74 128 806 735

Address:

101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 Fax: 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

Client: CONSTRUCTION SCIENCES - RTON

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

General Testing - Engineering Project:

Location: North Rockhampton

Supplied To: n/a

Area Description:

Report Number: 2128/R/44313-1

Project Number: 2135/P/415

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Page 16 of 23 Report Date / Page: 5/02/2019

Q114B Sample Location Test Procedures

Sample Number 2128/S/78964 Bore Hole No.

Sampling Method

Material Description

498 - 512 mm

Date Sampled 24/01/2019

Sampled By Nicole Bella & Mark Walters

Date Tested 24/01/2019 Moisture Condition Dry to Moist


Sandy Clay - Gravelly Clayey Sand

16


Depth (m) Seated @ 0.2m

Material Source

Material Type







Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128





PAGE 1 OF 1

<u></u> _	Construction
==	Sciences

			rdno C						
						P.959			nes Water to Baffle Creek
						COMPLETED _24/1/19			
						onstruction Sciences Pty Ltd			BEARING
			Quid 100m						
						6J, E: 389595,N: 7317023	LOGGED BT _W.Walters_		CHECKED BT _F.Nilaverave
			0 00 (Jianie		00, 2. 000000,11. 1011020			
Method	Water	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Descript		Samples Tests Remarks	Additional Observations
AUGER			1. <u>0</u>		SM	Gravelly Silty SAND (RESIDUAL) fine to coarse coarse grained gravel, low plasticity fines, dry, v BOREHOLE TERMINATED AT 0.5m - AUGER	ery dense.		



ABN: 74 128 806 735

Address:

101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 Fax: 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

CONSTRUCTION SCIENCES - RTON Client:

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

Project: General Testing - Engineering

Location: North Rockhampton

Supplied To: n/a

Area Description:

Report Number: 2128/R/44313-1

> Project Number: 2135/P/415

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Page 17 of 23 Report Date / Page: 5/02/2019

Test Procedures Q114B Sample Location

Sample Number 2128/S/78965 Bore Hole No. 17

Sampling Method Depth (m)

Date Sampled 24/01/2019

Sampled By Nicole Bella & Mark Walters

Date Tested 24/01/2019 Material Source -Moisture Condition Material Type Dry

Material Description Gravelly Silty Sand

Equivalent California Breakdown	a Bearing Ratio Layer and Results	DYNAMIC CONE PENETROMETER TEST PLOT
Layer Limits (mm)	Equivalent CBR	
2 - 6 mm	>60	2 -
6 - 7 mm	>60	
7 - 13 mm	>60	4 -
13 - 13 mm		DCP Penetration (mm)
		90 8 - 10 -
		12 -
		14 - 0 2 4 6 8 10 12 Hammer Blows

Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



PAGE 1 OF 1

<u></u>	Construction
==	Sciences

CLI	CLIENT Cardno QLD Pty Ltd					F	PROJECT NAME Proposaed Inland Link Road					
PROJECT NUMBER 2128E.P.959 PROJECT LOCATION COnnecting Agnes Water to Baffle Creek												
DRILLING CONTRACTOR Construction Sciences Pty Ltd							OPE 90°					
	EQUIPMENT Quickdrill I											
HOLE SIZE 100mm							IN.Waiters		CHECKED BY _F	2.Kilaverave		
NOTES GPS Co-ordinates: 56J, E: 386595,N: 7316235												
Method	Water	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description		Samples Tests Remarks	Additional 0	Observations		
AUGER					ML Gravelly Sandy SILT (RESIDUAL) low plasticity, grey, fine to medium grained sand, dry, dense.							
4			0 <u>.5</u>		GC	Clayey Sandy GRAVEL (RESIDUAL) fine to medium pale yellow/grey, fine to coarse grained sand, dry, ver						
			1. <u>0</u> - - - 1. <u>5</u>			BOREHOLE TERMINATED AT 0.7m - AUGER REFU	ISAL ON BEDROCK					
			2. <u>0</u> - - - 2. <u>5</u>									
			3 <u>.0</u>									
			3 <u>.5</u>									
			4.0 4.5 4.5									



ABN:

74 128 806 735

Address: 101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 Fax: 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

Client: CONSTRUCTION SCIENCES - RTON

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

Project: General Testing - Engineering

Location: North Rockhampton

Supplied To: n/a

Area Description:

Report Number: 2128/R/44313-1

2135/P/415 Project Number:

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Page 18 of 23 Report Date / Page: 5/02/2019

Q114B Sample Location Test Procedures

Sample Number 2128/S/78966 Bore Hole No. 18


Sampling Method Depth (m)

Date Sampled 24/01/2019

Sampled By Nicole Bella & Mark Walters

Date Tested 24/01/2019 Material Source Moisture Condition Material Type Dry

Material Description Clayey Sandy Gravel



Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



BOREHOLE NUMBER BH19

PAGE 1 OF 1

<u></u>	Construction
==	Sciences

BOREHOLE / TEST PIT 2128E.P.959 LOGS.GPJ GINT AUSTRALIA.GDT 7/2/19

CLIENT Cardno QLD Pty Ltd							PROJECT NAME Prop	osaod Inland I	ink Poad
						P.959			nes Water to Baffle Creek
DAT	ΈS	TARI	ED	23/1/	19	COMPLETED 23/1/19			
						onstruction Sciences Pty Ltd			
			Qui			Should de de la company de la			
			100m						
				1111			LOGGED BTivi.vvaileis		F.Rilaverave
IVOI	ES	_N/A	\ 						
Method	Water	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Descr	iption	Samples Tests Remarks	Additional Observations
						BOREHOLE 19 CANCELLED.			
			1. <u>0</u>						

BOREHOLE NUMBER BH20 PAGE 1 OF 1

<u></u>	Construction
==	Sciences

BOREHOLE / TEST PIT 2128E.P.959 LOGS.GPJ GINT AUSTRALIA.GDT 7/2/19

CLIE			rdno Q	LD F	ty Ltd		PROJECT NAME Propo	saed Inland Li	ink Poad	
			CLIENT Cardno QLD Pty Ltd Proposaed Inland Link Road							
PRO	PROJECT NUMBER 2128E.P.959 PROJECT LOCATION COnnecting Agnes Water to Baffle Creek									le Creek
ΠΔΤ	F.S	TARI	ren 2	23/1/	19	COMPLETED 23/1/19	R I SURFACE		DATUM	
						onstruction Sciences Pty Ltd				
			Quic			, , , , , , , , , , , , , , , , , , ,				
			100m							
NOT	ES	GP	S Co-c	ordina		6J, E: 389574,N: 7315517				
	Water	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Descript		Samples Tests Remarks	Additional	Observations
AUGER					ML	Sandy SILT (COLLUVIUM) low plasticity, pale g dry, very dense.	rey, fine to medium grained sand,			
			0.5		MI	Sandy Clayey SILT (COLLUVIUM) low plasticity	, pale grey, dry, very dense.			
			1.0			BOREHOLE TERMINATED AT 1.0m				
			1 <u>.5</u> _ _							
			2.0							
			-							
			2 <u>.5</u>							
			-							
			3.0							
			-							
			3.5							
			-							
			4.0							
			4.5							



Construction Sciences Pty Ltd

ABN:

74 128 806 735

Address: 101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 Fax: 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

Client: CONSTRUCTION SCIENCES - RTON

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

General Testing - Engineering Project:

Location: North Rockhampton

Supplied To: n/a

Area Description:

Report Number: 2128/R/44313-1

Project Number: 2135/P/415

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Page 19 of 23 Report Date / Page: 5/02/2019

20

Q114B Sample Location Test Procedures

Sample Number 2128/S/78967

Sampling Method

Date Sampled

24/01/2019

Sampled By

Date Tested 24/01/2019

Moisture Condition Dry

Nicole Bella & Mark Walters


Material Source

Bore Hole No.

Depth (m)

Material Type

Material Description Sandy Silt - Sandy Clayey Silt



Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



Approved Signatory: Nicole Bella Form ID: W17Rep Rev 1

BOREHOLE NUMBER BH21

PAGE 1 OF 1

<u></u>	Construction
==	Sciences

BOREHOLE / TEST PIT 2128E.P.959 LOGS.GPJ GINT AUSTRALIA.GDT 7/2/19

CLIENT Cardno QLD Pty Ltd						I	PROJECT NAME Proposaed Inland Link Road			
PROJECT NUMBER 2128E.P.959							PROJECT LOCATION _C	Onnecting Agn	es Water to Baffle Creek	
						COMPLETED 23/1/19			DATUM	
DR	ILLI	NG C	ONTR	RACTO		onstruction Sciences Pty Ltd			BEARING	
EQ	UIP	MENT	_Qu	iickdril	<u> </u>		HOLE LOCATION As Mar	rked on Site Pla	n in Appendix A	
но	LE S	SIZE	100r	mm			LOGGED BY M.Walters		CHECKED BY P.Kilaverave	
NO	TES	GP	S Co	-ordina	ates: 5	56J, E: 387542,N: 7307877				
Method	Water	RL	Depth	Graphic Log	Classification Symbol	Material Descripti	on	Samples Tests Remarks	Additional Observations	
AUGER	>	(m)	(m)		ML	Sandy SILT (ALLUVIUM) low plasticity, brown, fi dense.	ne to medium grained sand, dry,			
AU			-		SC	Clayey SAND (ALLUVIUM) fine to coarse graine fines, dry to moist, dense.	d sand, brown, low plasticity			
			0 <u>.5</u>		CI	Sandy CLAY (RESIDUAL) medium plasticity, brodry to moist, stiff to very stiff.	own, fine to coarse grained sand,			
			-			hard.				
			1.0			BOREHOLE TERMINATED AT 1.0m - AUGER I	EFUSAL ON HARD CLAY			
			-							
			1. <u>5</u>							
			-							
			2 <u>.0</u>							
			- -							
			2 <u>.5</u>							
			-							
			3. <u>0</u>							
			- -							
			3 <u>.5</u>							
			4.0							
			<u></u>							
			4 <u>.5</u>							
			-							
			5.0							



Construction Sciences Pty Ltd

ABN: 74 128 806 735

Address: 101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 Fax: 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

CONSTRUCTION SCIENCES - RTON Client:

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

Project: General Testing - Engineering

Location: North Rockhampton

Supplied To: n/a

Area Description:

Report Number: 2128/R/44313-1

Project Number: 2135/P/415

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Page 20 of 23 Report Date / Page: 5/02/2019

Test Procedures Q114B

Sample Number 2128/S/78968

Sampling Method

24/01/2019

Date Sampled Sampled By

Nicole Bella & Mark Walters

Clayey Sand - Sandy Clay

Date Tested Moisture Condition

Material Description

24/01/2019

Dry to Moist

Bore Hole No.

Depth (m)

21

Seated @ 0.3m

Sample Location

Material Source -

Material Type

Equivalent California Breakdown	a Bearing Ratio Layer and Results	DYNAMIC CONE PENETROMETER TEST PLOT
Layer Limits (mm)	Equivalent CBR	20 -
9 - 99 mm	25	40 -
99 - 207 mm	45	60 -
207 - 214 mm	>60	80 -
214 - 215 mm	>60	100 - 100 -
		120 -
		140 -
		160 -
		180 -
		200 -
		220 -
		0 5 10 15 20 25 30 35 Hammer Blows

Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



Approved Signatory: Nicole Bella Form ID: W17Rep Rev 1

BOREHOLE NUMBER BH22

PAGE 1 OF 1

<u></u> _	Construction
==	Sciences

BOREHOLE / TEST PIT 2128E.P.959 LOGS.GPJ GINT AUSTRALIA.GDT 7/2/19

				QLD F			ROJECT NAME Propo		k Road es Water to Baffle Creek
						COMPLETED _23/1/19 R.L construction Sciences Pty Ltd SL0			
						HO			
			100r			LO			
						66J, E: 387584,N: 7308254	WI.VVAILETS		T.Maverave
Method	Water	RL (m)	Depth (m)	Graphic Log	Classification Symbol	Material Description		Samples Tests Remarks	Additional Observations
AUGER			_ _ _		GC	Clayey Sandy GRAVEL (FILL) fine to coarse grained a brown/grey, low plasticity fines, fine to coarse grained s very dense.	ingular gravel, pale sand, cobbles present, dry,		
			0 <u>.5</u>		SP	SAND (ALLUVIUM) fine to coarse grained sand, grey, to moist, dense.	negligible plastic fines, dry		
			1. <u>0</u>			moist, dense to very dense.			
			- - -		SP	SAND trace Clay (ALLUVIUM) fine to coarse grained s low plasticity fines, trace of fine grained angular gravels	s, moist, very dense.		
			1 <u>.5</u>		SC	<u>Clayey SAND</u> (RESIDUAL) fine to coarse grained sand very dense.	d, red/brown, low plasticity,		
			2.0		CL	Gravelly Sandy CLAY (RESIDUAL) low plasticity, pale medium grained sub-angular gravel, fine to coarse gravery stiff to hard. BOREHOLE TERMINATED AT 2.0m	grey mottle yellow, fine to ined sand, dry to moist,		
			- - -	-					
			2 <u>.5</u>						
			3 <u>.0</u>	_					
			- - -						
			3 <u>.5</u> –						
			4.0						
			-	-					
			4. <u>5</u> -	-					



Construction Sciences Pty Ltd

ABN: 74 128 806 735

Address:

101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 Fax: 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

Client: CONSTRUCTION SCIENCES - RTON

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

Project: General Testing - Engineering

Location: North Rockhampton

Supplied To: n/a

Area Description:

Date Sampled

Sampled By

Report Number: 2128/R/44313-1

2135/P/415 Project Number:

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Page 21 of 23 Report Date / Page: 5/02/2019

Q114B Sample Location Test Procedures Sample Number 2128/S/78969 Bore Hole No. 22

Sampling Method Depth (m) Seated @ 0.5m


24/01/2019

Date Tested 24/01/2019 Material Source Moisture Condition Material Type

Material Description Sand - Clayey Sand - Gravelly Sandy Clay

Dry to Moist

Nicole Bella & Mark Walters



Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



Approved Signatory: Nicole Bella Form ID: W17Rep Rev 1

BOREHOLE NUMBER BH23

PAGE 1 OF 1

<u></u> _	Construction
==	Sciences

CLIENT Cardno QLD Pty Ltd						PROJECT NAME Proposaed Inland Link Road				
PR	OJE	CT N	UMBER _2	128E.I	P.959 PR	OJECT LOCATION _C	Onnecting Ag	nes Water to Ba	ffle Creek	
DR EQ	ILLII UIPI	NG C	Quickdri	OR <u>C</u>	onstruction Sciences Pty Ltd SLO HOL	SLOPE 90° BE HOLE LOCATION As Marked on Site Plan i			BEARING in in Appendix A	
			100mm		LOG	GGED BY M.Walters		CHECKED BY	P.Kilaverave	
NO	TES	GF	S Co-ordin	ates: 5	66J, E: 388092,N: 7312148					
Method	Water	RL (m)	(m) (the distribution of the distribution of t	Classification Symbol	Material Description		Samples Tests Remarks	Addition	al Observations	
AUGER			100	}	Clayey Sandy GRAVEL (FILL) fine to coarse grained ar brown/grey, low plasticity fines, fine to coarse grained savery dense.	ngular gravel, pale and, cobbles present, dry,				
			0.5	SM	Silty SAND (ALLUVIUM) fine to medium grained sand, prints, dry to moist, dense.					
			1.0	CL/CI	Sandy CLAY (RESIDUAL) low to medium plasticity, brosand, dry to moist, stiff to very stiff.	wh, fine to coarse grained				
				SC	Clavey Gravelly SAND (RESIDUAL) fine to coarse grain negligible to low plasticity fines, fine to medium grained dense.	ned sand, pale brown, angular gravel, dry, very				
			1.5		BOREHOLE TERMINATED AT 1.3m - AUGER REFUS	AL ON BEDROCK				
			-							
			2.0							
			_							
			2 <u>.5</u>							
			-							
			3.0							
			3.5							
			4.0							
			-							
			4.5							
			5.0							



Construction Sciences Pty Ltd

ABN: 74 128 806 735

Address:

101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 Fax: 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

Client: CONSTRUCTION SCIENCES - RTON

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

General Testing - Engineering Project:

Location: North Rockhampton

Supplied To: n/a

Area Description:

Date Sampled

Moisture Condition

Report Number: 2128/R/44313-1

Project Number: 2135/P/415

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Page 22 of 23 Report Date / Page: 5/02/2019

Q114B **Test Procedures** Sample Location 23

Sample Number 2128/S/78970 Bore Hole No.


Sampling Method Depth (m) Seated @ 0.4m

Sampled By Nicole Bella & Mark Walters

Date Tested 24/01/2019 Material Source

Dry to Moist Material Description Sandy Clay - Clayey Gravelly Sand

24/01/2019



Material Type

Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



Approved Signatory: Nicole Bella Form ID: W17Rep Rev 1

BOREHOLE NUMBER BH24

PAGE 1 OF 1

<u></u>	Construction
==	Sciences

CLIENT _Cardno QLD Pty Ltd PROJECT NUMBER _2128E.P.959				_		PROJECT NAME Proposaed Inland Link Road PROJECT LOCATION COnnecting Agnes Water to Baffle Creek			
DATE STARTED 23/1/19 COMPLETED 23/1/19 DRILLING CONTRACTOR Construction Sciences Pty Ltd EQUIPMENT Quickdrill					COMPLETED 23/1/19 R.I onstruction Sciences Pty Ltd SL HC	R.L. SURFACE DATUM SLOPE _90° BEARING HOLE LOCATION _As Marked on Site Plan in Appendix A LOGGED BY _M.Walters CHECKED BY _P.Kilaverave			
Method	Water	RL (m)	(m) htdəo Graphic Log	Classification Symbol	Material Description		Samples Tests Remarks	Additional Observations	
AUGER			0.5 1.0 2.5 2.0 3.0 4.0 4.5		Clayey Sandy GRAVEL (FILL) fine to coarse grained brown/grey, low plasticity fines, fine to coarse grained very dense. Gravelly Clayey SAND (ALLUVIUM) fine to coarse gragained gravel, low plasticity fines, dry to moist, dense Sity CLAY (ALLUVIUM) medium plasticity, grey, traces and, moist (below plastic limit), soft. very stiff to hard BOREHOLE TERMINATED AT 2.0m	sand, cobbles present, dry,			



Construction Sciences Pty Ltd

ABN: 74 128 806 735

Address:

101 High Street,

North Rockhampton QLD 4701

Laboratory: Rockhampton Laboratory

Phone: 07 4928 0044 Fax: 07 4926 1286

Email: Rockhampton@constructionsciences.net

INSITU CBR REPORT

Client: CONSTRUCTION SCIENCES - RTON

Client Address: ROCKHAMPTON, 101 High Street, North Rockhampton

Project: General Testing - Engineering

Location: North Rockhampton

Supplied To: n/a

Area Description:

Date Sampled

Report Number: 2128/R/44313-1

Project Number: 2135/P/415

Lot Number:

Internal Test Request: 2128/T/18827

Client Reference/s: 2128E/P/959

Page 23 of 23 Report Date / Page: 5/02/2019

Q114B Test Procedures Sample Location

Sample Number 2128/S/78971 Bore Hole No. 24


Sampling Method Depth (m) Seated @ 0.3m

Sampled By Nicole Bella & Mark Walters

24/01/2019

Date Tested 24/01/2019 Material Source Moisture Condition Dry to Moist Material Type

Material Description Gravelly Sandy Clay - Clayey Silt / Silty Clay



Remarks



The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards. Accredited for compliance with ISO/IEC 17025 - Testing

Accreditation Number: 1986 Corporate Site Number: 2128



Approved Signatory: Nicole Bella Form ID: W17Rep Rev 1 APPENDIX

CERTIFICATES OF TITLE



NATURAL RESOURCES, MINES AND ENERGY, QUEENSLAND

Request No: 30673046

Search Date: 26/02/2019 11:21 Title Reference: 50497906

Date Created: 02/06/2004

Previous Title: 50497850

REGISTERED OWNER

Dealing No: 707765998 31/05/2004

BODY CORPORATE FOR SUNRISE AT 1770 COMMUNITY TITLES

SCHEME 32536 PO BOX 1191

MOOLOOLABA QLD 4557

LAND DESCRIPTION

COMMON PROPERTY OF SUNRISE AT 1770 COMMUNITY TITLES SCHEME 32536
COMMUNITY MANAGEMENT STATEMENT 32536
Local Government: GLADSTONE

EASEMENTS, ENCUMBRANCES AND INTERESTS

- Rights and interests reserved to the Crown by Deed of Grant No. 30401002 (POR 11) Deed of Grant No. 30401003 (POR 11) Deed of Grant No. 30401004 (POR 11)
- 2. EASEMENT No 706434854 13/03/2003 at 12:32
 burdening the land to
 LOT 2 ON SP150900 OVER
 EASEMENT A ON SP150900
- 3. EASEMENT No 706434860 13/03/2003 at 12:32 burdening the land to LOT 4 ON SP150900 OVER EASEMENT B ON SP150900
- 4. EASEMENT No 706434862 13/03/2003 at 12:33 benefiting the land over EASEMENT C ON SP150900
- 5. EASEMENT No 707535431 05/03/2004 at 15:07 burdening the land to LOT 1 ON SP150900 OVER EASEMENT H ON SP160548
- 6. EASEMENT IN GROSS No 707631830 08/04/2004 at 12:38 burdening the land ERGON ENERGY CORPORATION LIMITED A.C.N. 087 646 062 over EASEMENTS J TO P ON SP164525

NATURAL RESOURCES, MINES AND ENERGY, QUEENSLAND

Request No: 30673046

Search Date: 26/02/2019 11:21 Title Reference: 50497906

Date Created: 02/06/2004

EASEMENTS, ENCUMBRANCES AND INTERESTS

7. EASEMENT No 707689879 04/05/2004 at 14:48 benefiting the land over EASEMENT Q ON SP168968

- 8. EASEMENT No 708792753 01/07/2005 at 15:26 burdening the land to LOT 2 ON SP165533 OVER EASEMENT H ON SP160548
- 9. EASEMENT IN GROSS No 708973764 13/09/2005 at 15:45 burdening the land ERGON ENERGY CORPORATION LIMITED over EASEMENTS D.E AND F ON SP182674
- 10. REQUEST FOR NEW CMS No 713555181 05/11/2010 at 12:47 New COMMUNITY MANAGEMENT STATEMENT 32536 ACCOMMODATION MODULE

ADMINISTRATIVE ADVICES - NIL UNREGISTERED DEALINGS - NIL

CERTIFICATE OF TITLE ISSUED - No

Caution - Charges do not necessarily appear in order of priority

** End of Current Title Search **

NATURAL RESOURCES, MINES AND ENERGY, QUEENSLAND

Request No: 30655263

Search Date: 22/02/2019 14:16 Title Reference: 30586141

Date Created: 11/01/1989

Previous Title: 30577228

REGISTERED OWNER

TRAYWAR PTY LTD

ESTATE AND LAND

Estate in Fee Simple

LOT 1 REGISTERED PLAN 620278

Local Government: GLADSTONE

EASEMENTS, ENCUMBRANCES AND INTERESTS

 Rights and interests reserved to the Crown by Deed of Grant No. 30401002 (POR 11) Deed of Grant No. 30401003 (POR 11) Deed of Grant No. 30401004 (POR 11)

2. LEASE No 709385987 22/02/2006 at 15:29
AGNES QUARRIES PTY LTD A.C.N. 094 776 619
THE WHOLE OF THE LAND
TERM: 01/04/2005 TO 31/03/2008 OPTION 3 YEARS

ADMINISTRATIVE ADVICES - NIL UNREGISTERED DEALINGS - NIL

CERTIFICATE OF TITLE ISSUED - Yes 08/03/2006 709385990 Certificate No. 2

Caution - Charges do not necessarily appear in order of priority

** End of Current Title Search **

NATURAL RESOURCES, MINES AND ENERGY, QUEENSLAND

Request No: 30672855

Search Date: 26/02/2019 11:14 Title Reference: 50432519

Date Created: 19/03/2003

Previous Title: 50423384

REGISTERED OWNER

Dealing No: 707885410 13/07/2004

AUSTRALIAN BUSH HERITAGE FUND A.C.N. 053 639 115

ESTATE AND LAND

Estate in Fee Simple

LOT 1 SURVEY PLAN 150900

Local Government: GLADSTONE

EASEMENTS, ENCUMBRANCES AND INTERESTS

 Rights and interests reserved to the Crown by Deed of Grant No. 30401002 (POR 11) Deed of Grant No. 30401003 (POR 11) Deed of Grant No. 30401004 (POR 11)

2. EASEMENT IN GROSS No 706434867 13/03/2003 at 12:33 burdening the land MIRIAM VALE SHIRE COUNCIL over EASEMENT E ON SP150900

- 3. EASEMENT No 707535420 05/03/2004 at 15:06 burdening the land to LOT 2 ON SP150900 OVER EASEMENT G ON SP160548
- 4. EASEMENT No 707535431 05/03/2004 at 15:07 benefiting the land over EASEMENT H ON SP160548
- 5. EASEMENT No 707689879 04/05/2004 at 14:48 burdening the land to LOTS 2 TO 4 ON SP150900 OVER EASEMENT Q ON SP168968
- 6. NATURE REFUGE NOTING No 707757505 27/05/2004 at 15:24 all or part of the within land has been declared a Nature Refuge under the Nature Conservation Act 1992

ADMINISTRATIVE ADVICES - NIL UNREGISTERED DEALINGS - NIL

NATURAL RESOURCES, MINES AND ENERGY, QUEENSLAND

Request No: 30672855

Search Date: 26/02/2019 11:14 Title Reference: 50432519

Date Created: 19/03/2003

CERTIFICATE OF TITLE ISSUED - No

Caution - Charges do not necessarily appear in order of priority

** End of Current Title Search **

COPYRIGHT THE STATE OF QUEENSLAND (NATURAL RESOURCES, MINES AND ENERGY) [2019]

Requested By: D-ENQ GLOBALX TERRAIN

NATURAL RESOURCES, MINES AND ENERGY, QUEENSLAND

Request No: 30655274

Search Date: 22/02/2019 14:17 Title Reference: 50832362

Date Created: 03/12/2010

Previous Title: 30635147

REGISTERED OWNER

Dealing No: 713594640 29/11/2010

CBS CORPORATION PTY LTD A.C.N. 010 350 937

TRUSTEE

UNDER INSTRUMENT 707097829

ESTATE AND LAND

Estate in Fee Simple

LOT 1 SURVEY PLAN 236012

Local Government: GLADSTONE

EASEMENTS, ENCUMBRANCES AND INTERESTS

1. Rights and interests reserved to the Crown by Deed of Grant No. 30635147 (Lot 8 on CP FD461)

ADMINISTRATIVE ADVICES - NIL UNREGISTERED DEALINGS - NIL

CERTIFICATE OF TITLE ISSUED - Yes 08/12/2015 716934956 Certificate No. 1

** End of Current Title Search **

NATURAL RESOURCES, MINES AND ENERGY, QUEENSLAND

Request No: 30655278

Search Date: 22/02/2019 14:17 Title Reference: 50832363

Date Created: 03/12/2010

Previous Title: 30635147

REGISTERED OWNER

Dealing No: 713594640 29/11/2010

CBS CORPORATION PTY LTD A.C.N. 010 350 937

TRUSTEE

UNDER INSTRUMENT 707097829

ESTATE AND LAND

Estate in Fee Simple

LOT 2 SURVEY PLAN 236012

Local Government: GLADSTONE

EASEMENTS, ENCUMBRANCES AND INTERESTS

1. Rights and interests reserved to the Crown by Deed of Grant No. 30635147 (Lot 8 on CP FD461)

ADMINISTRATIVE ADVICES - NIL UNREGISTERED DEALINGS - NIL

CERTIFICATE OF TITLE ISSUED - Yes 08/12/2015 716934956 Certificate No. 1

** End of Current Title Search **

NATURAL RESOURCES, MINES AND ENERGY, QUEENSLAND

Request No: 30378988

Search Date: 15/01/2019 08:31 Title Reference: 50248743

Date Created: 14/12/1998

Previous Title: 30520241

REGISTERED OWNER

Dealing No: 718640239 16/03/2018

THOMAS BALTO PERSONAL REPRESENTATIVE

UNDER INSTRUMENT 718640239

ESTATE AND LAND

Estate in Fee Simple

LOT 7 SURVEY PLAN 111856

Local Government: GLADSTONE

EASEMENTS, ENCUMBRANCES AND INTERESTS

 Rights and interests reserved to the Crown by Deed of Grant No. 30520241 (POR 24)

ADMINISTRATIVE ADVICES - NIL UNREGISTERED DEALINGS - NIL

CERTIFICATE OF TITLE ISSUED - No

** End of Current Title Search **

NATURAL RESOURCES, MINES AND ENERGY, QUEENSLAND

Request No: 30655272

Search Date: 22/02/2019 14:17 Title Reference: 30574156

Date Created: 16/11/1987

REGISTERED OWNER

Dealing No: 717444432 15/08/2016

STEVEN GARY CZERWONKA TRUSTEE

UNDER INSTRUMENT 716714610

ESTATE AND LAND

Estate in Fee Simple

LOT 10 CROWN PLAN FD469

Local Government: GLADSTONE

EASEMENTS, ENCUMBRANCES AND INTERESTS

1. Rights and interests reserved to the Crown by Deed of Grant No. 30574156 (Lot 10 on CP FD469)

ADMINISTRATIVE ADVICES - NIL UNREGISTERED DEALINGS - NIL

CERTIFICATE OF TITLE ISSUED - No

** End of Current Title Search **

CURRENT RESERVE SEARCH

NATURAL RESOURCES, MINES AND ENERGY, QUEENSLAND

Request No: 30378986

Search Date: 15/01/2019 08:30 Title Reference: 49005373

Date GAZETTED: 07/07/1945

PAGE: 5

Opening Ref: BDG 45-9174

Purpose: WATER

Sub-Purpose:
 Local Name:

Address: BULLOCK CREEK

County (R) No: R203 File Ref: RES 7489

TRUSTEES

GLADSTONE REGIONAL COUNCIL GAZETTED ON 07/07/1945 PAGE

LAND DESCRIPTION

LOT 12 CROWN PLAN FD638 GAZETTED ON 07/07/1945 PAGE 5

Local Government: GLADSTONE

Area: 87.632000 Ha. (SURVEYED)

EASEMENTS AND ENCUMBRANCES

1. EASEMENT IN GROSS No 710831879 20/07/2007 at 14:47 burdening the land ERGON ENERGY CORPORATION LIMITED A.C.N. 087 646 062 over EASEMENT X ON SP189311

ADMINISTRATIVE ADVICES

DealingTypeLodgementDateStatus718775841NT DETERM29/05/201816:28CURRENT

NATIVE TITLE ACT 1993 (CTH)

UNREGISTERED DEALINGS - NIL

CERTIFICATE OF TITLE ISSUED - No

Caution - Charges do not necessarily appear in order of priority

** End of Current Reserve Search **

NATURAL RESOURCES, MINES AND ENERGY, QUEENSLAND

Request No: 30655261

Search Date: 22/02/2019 14:16 Title Reference: 50308306

Date Created: 17/04/2000

Previous Title: 40023784

REGISTERED OWNER

Dealing No: 703997409 14/04/2000

SUZANNE LEE TURNER

ESTATE AND LAND

Estate in Fee Simple

LOT 13 SURVEY PLAN 120832

Local Government: GLADSTONE

EASEMENTS, ENCUMBRANCES AND INTERESTS

1. Rights and interests reserved to the Crown by Deed of Grant No. 30627123 (Lot 13 on CP FD1067)

ADMINISTRATIVE ADVICES - NIL UNREGISTERED DEALINGS - NIL

CERTIFICATE OF TITLE ISSUED - No

** End of Current Title Search **

NATURAL RESOURCES, MINES AND ENERGY, QUEENSLAND

Request No: 30655258

Search Date: 22/02/2019 14:16 Title Reference: 30635148

Date Created: 16/03/1993

REGISTERED OWNER

Dealing No: 707097829 17/10/2003

CBS CORPORATION PTY LTD A.C.N. 010 350 937

TRUSTEE

UNDER INSTRUMENT 707097829

ESTATE AND LAND

Estate in Fee Simple

LOT 14 CROWN PLAN FD784

Local Government: GLADSTONE

For exclusions / reservations for public purposes refer to Plan CP ${\tt FD784}$

EASEMENTS, ENCUMBRANCES AND INTERESTS

1. Rights and interests reserved to the Crown by Deed of Grant No. 30635148 (Lot 14 on CP FD784)

ADMINISTRATIVE ADVICES - NIL UNREGISTERED DEALINGS - NIL

CERTIFICATE OF TITLE ISSUED - Yes 11/11/2003 707165327 Certificate No. 2

** End of Current Title Search **

NATURAL RESOURCES, MINES AND ENERGY, QUEENSLAND

Request No: 30655270

Search Date: 22/02/2019 14:16 Title Reference: 30496175

Date Created: 24/06/1982

REGISTERED OWNER

Dealing No: 708501502 14/03/2005

ROBERT JOHN ANSTEY

ANNETTE MAREE ANSTEY JOINT TENANTS

ESTATE AND LAND

Estate in Fee Simple

LOT 15 CROWN PLAN FD526

Local Government: GLADSTONE

For exclusions / reservations for public purposes refer to Plan CP FD526

EASEMENTS, ENCUMBRANCES AND INTERESTS

- 1. Rights and interests reserved to the Crown by Deed of Grant No. 30496175 (POR 15)
- 2. MORTGAGE No 708501503 14/03/2005 at 08:21 NATIONAL AUSTRALIA BANK LIMITED A.B.N. 12 004 044 937
- 3. EASEMENT IN GROSS No 709868546 21/08/2006 at 15:35 burdening the land ERGON ENERGY CORPORATION LIMITED A.C.N. 087 646 062 over EASEMENT V ON SP189309

ADMINISTRATIVE ADVICES

DealingTypeLodgementDateStatus710740296VEG NOTICE22/06/200714:14CURRENT

VEGETATION MANAGEMENT ACT 1999

UNREGISTERED DEALINGS - NIL

CERTIFICATE OF TITLE ISSUED - No

Caution - Charges do not necessarily appear in order of priority

** End of Current Title Search **

NATURAL RESOURCES, MINES AND ENERGY, QUEENSLAND

Request No: 30655266

Search Date: 22/02/2019 14:16 Title Reference: 30574155

Date Created: 16/11/1987

REGISTERED OWNER

Dealing No: 710933138 24/08/2007

KENNITH ALAN D'ARCY

RITA LUCIA D'ARCY JOINT TENANTS

ESTATE AND LAND

Estate in Fee Simple

LOT 16 CROWN PLAN FD526

Local Government: GLADSTONE

EASEMENTS, ENCUMBRANCES AND INTERESTS

- 1. Rights and interests reserved to the Crown by Deed of Grant No. 30574155 (Lot 16 on CP FD526)
- 2. MORTGAGE No 710933139 24/08/2007 at 12:05
 NATIONAL AUSTRALIA BANK LIMITED A.B.N. 12 004 044 937

ADMINISTRATIVE ADVICES - NIL UNREGISTERED DEALINGS - NIL

CERTIFICATE OF TITLE ISSUED - No

Caution - Charges do not necessarily appear in order of priority

** End of Current Title Search **

NATURAL RESOURCES, MINES AND ENERGY, QUEENSLAND

Request No: 30378991

Search Date: 15/01/2019 08:31 Title Reference: 30627046

Date Created: 14/08/1992

REGISTERED OWNER

Dealing No: 708101434 01/10/2004

JOAN PAMELA HILLS

ESTATE AND LAND

Estate in Fee Simple

LOT 17 CROWN PLAN FD527

Local Government: GLADSTONE

EASEMENTS, ENCUMBRANCES AND INTERESTS

1. Rights and interests reserved to the Crown by Deed of Grant No. 30627046 (Lot 17 on CP FD527)

2. EASEMENT IN GROSS No 709822098 02/08/2006 at 14:41 burdening the land ERGON ENERGY CORPORATION LIMITED A.C.N. 087 646 062 over

EASEMENT Y ON SP189312

ADMINISTRATIVE ADVICES

Dealing	Type			Lodgement 1	Date	Status
710740253	VEG NOTICE			22/06/2007	14:12	CURRENT
	VEGETATION	MANAGEMENT	ACT	1999		
711812195	VEG NOTICE			23/07/2008	13:11	CURRENT
	VEGETATION	MANAGEMENT	ACT	1999		
711813134	VEG NOTICE			23/07/2008	15:28	CURRENT
	VEGETATION	MANAGEMENT	ACT	1999		
UNREGISTERED DEALINGS - NIL						

CERTIFICATE OF TITLE ISSUED - No

Caution - Charges do not necessarily appear in order of priority

** End of Current Title Search **

NATURAL RESOURCES, MINES AND ENERGY, QUEENSLAND

Request No: 30655255

Search Date: 22/02/2019 14:16 Title Reference: 30635154

Date Created: 26/03/1993

REGISTERED OWNER

Dealing No: 707097829 17/10/2003

CBS CORPORATION PTY LTD A.C.N. 010 350 937

TRUSTEE

UNDER INSTRUMENT 707097829

ESTATE AND LAND

Estate in Fee Simple

LOT 18 CROWN PLAN FD527

Local Government: GLADSTONE

EASEMENTS, ENCUMBRANCES AND INTERESTS

1. Rights and interests reserved to the Crown by Deed of Grant No. 30635154 (Lot 18 on CP FD527)

ADMINISTRATIVE ADVICES - NIL UNREGISTERED DEALINGS - NIL

CERTIFICATE OF TITLE ISSUED - Yes 11/11/2003 707165347 Certificate No. 2

** End of Current Title Search **

NATURAL RESOURCES, MINES AND ENERGY, QUEENSLAND

Request No: 30378992

Date Created: 01/03/1983

REGISTERED OWNER

Dealing No: 711336743 11/01/2008

WOODKEL PTY LTD A.C.N. 127 765 799

ESTATE AND LAND

Estate in Fee Simple

LOT 19 CROWN PLAN FD527

Local Government: GLADSTONE

EASEMENTS, ENCUMBRANCES AND INTERESTS

- 1. Rights and interests reserved to the Crown by Deed of Grant No. 30507176 (POR 19)
- 2. EASEMENT IN GROSS No 709773076 14/07/2006 at 11:54 burdening the land ERGON ENERGY CORPORATION LIMITED over EASEMENT Z ON SP189313

ADMINISTRATIVE ADVICES

DealingTypeLodgementDateStatus710740197VEG NOTICE22/06/200714:06CURRENT

VEGETATION MANAGEMENT ACT 1999

UNREGISTERED DEALINGS - NIL

CERTIFICATE OF TITLE ISSUED - No

Caution - Charges do not necessarily appear in order of priority

** End of Current Title Search **

NATURAL RESOURCES, MINES AND ENERGY, QUEENSLAND

Request No: 30379000

Search Date: 15/01/2019 08:33 Title Reference: 30507129

Date Created: 18/02/1983

REGISTERED OWNER

Dealing No: 702138767 05/08/1997

GLADSTONE REGIONAL COUNCIL

ESTATE AND LAND

Estate in Fee Simple

LOT 20 CROWN PLAN FD991

Local Government: GLADSTONE

EASEMENTS, ENCUMBRANCES AND INTERESTS

- 1. Rights and interests reserved to the Crown by Deed of Grant No. 30507129 (POR 20)
- 2. SEC 147A NOTATION NO 601083730 (147A) 31/12/1984
 THE PROVISIONS OF SECTION 147A OF THE LAND ACT 1962-1990
 REFER TO SECTION 174 OF THE LAND ACT 1994
 APPLY TO A TRANSFER OF THE WHOLE OR PART OF THE LAND
- 3. EASEMENT IN GROSS No 710537892 27/04/2007 at 13:55 burdening the land ERGON ENERGY CORPORATION LIMITED A.C.N. 087 646 062 over EASEMENT AA ON SP189314

ADMINISTRATIVE ADVICES

Dealing Type Lodgement Date Status
710740225 VEG NOTICE 22/06/2007 14:10 CURRENT
VEGETATION MANAGEMENT ACT 1999

UNREGISTERED DEALINGS - NIL

CERTIFICATE OF TITLE ISSUED - No

Corrections have occurred - Refer to Historical Search

Caution - Charges do not necessarily appear in order of priority

** End of Current Title Search **

NATURAL RESOURCES, MINES AND ENERGY, QUEENSLAND

Request No: 30379011

Search Date: 15/01/2019 08:33 Title Reference: 50594339

Date Created: 02/02/2006

Previous Title: 30507130

50081353

REGISTERED OWNER

Dealing No: 709198831 07/12/2005

GLADSTONE REGIONAL COUNCIL

ESTATE AND LAND

Estate in Fee Simple

LOT 21 SURVEY PLAN 168519

Local Government: GLADSTONE

EASEMENTS, ENCUMBRANCES AND INTERESTS

1. Rights and interests reserved to the Crown by

Deed of Grant No. 30401002 (POR 11)

Deed of Grant No. 30401003 (POR 11)

Deed of Grant No. 30401004 (POR 11)

Deed of Grant No. 30507130 (POR 21)

2. EASEMENT IN GROSS No 710537892 27/04/2007 at 13:55

burdening the land

ERGON ENERGY CORPORATION LIMITED A.C.N. 087 646 062

over

EASEMENT AB ON SP189314

ADMINISTRATIVE ADVICES

Dealing	Type			Lodgement	Date	Status
710740225	VEG NOTICE			22/06/2007	14:10	CURRENT
	VEGETATION	MANAGEMENT	ACT	1999		
711303331	VEG NOTICE			24/12/2007	11:53	CURRENT
	VEGETATION	MANAGEMENT	ACT	1999		
711414989	VEG NOTICE			11/02/2008	16:01	CURRENT
	VEGETATION	MANAGEMENT	ACT	1999		
711589251	VEG NOTICE			18/04/2008	12:35	CURRENT
	VEGETATION	MANAGEMENT	ACT	1999		
UNREGISTER	ED DEALINGS	- NIL				

CERTIFICATE OF TITLE ISSUED - No

Caution - Charges do not necessarily appear in order of priority

** End of Current Title Search **

NATURAL RESOURCES, MINES AND ENERGY, QUEENSLAND

Request No: 30379020

Search Date: 15/01/2019 08:34 Title Reference: 30577133

Date Created: 08/01/1988

Previous Title: 30574198

REGISTERED OWNER

Dealing No: 701245679 04/04/1996

JOHN HARGREAVES

JUNE ANNE HARGREAVES JOINT TENANTS

ESTATE AND LAND

Estate in Fee Simple

LOT 28 REGISTERED PLAN 619598

Local Government: GLADSTONE

EASEMENTS, ENCUMBRANCES AND INTERESTS

1. Rights and interests reserved to the Crown by

Deed of Grant No. 30401002 (POR 11)

Deed of Grant No. 30401003 (POR 11)

Deed of Grant No. 30401004 (POR 11)

ADMINISTRATIVE ADVICES - NIL UNREGISTERED DEALINGS - NIL

CERTIFICATE OF TITLE ISSUED - Yes 19/04/1996 701262703 Certificate No. 2

** End of Current Title Search **

CURRENT STATE TENURE SEARCH

NATURAL RESOURCES, MINES AND ENERGY, QUEENSLAND

Request No: 30378995

Search Date: 15/01/2019 08:32 Title Reference: 47502040

Date Created: 28/02/2007

Opening Ref:

Purpose: NATIONAL PARK

Local Name: DEEPWATER NATIONAL PARK

OWNER

THE STATE OF QUEENSLAND

(REPRESENTED BY

DEPARTMENT OF NATIONAL PARKS, SPORT AND RACING)

ESTATE

Estate in Protected Area Estate

LOT 153 CROWN PLAN NPW866

Local Government: GLADSTONE

Area: 4730.000000 Ha. (ABOUT)

EASEMENTS AND ENCUMBRANCES

ADMINISTRATIVE ADVICES

Dealing Type Lodgement Date Status 718782245 NT DETERM 01/06/2018 10:29 CURRENT

NATIVE TITLE ACT 1993 (CTH)

UNREGISTERED DEALINGS - NIL

CERTIFICATE OF TITLE ISSUED - No

Corrections have occurred - Refer to Historical Search

** End of Current State Tenure Search **

Information provided under section 34 Land Title Act(1994) or section 281 Land Act(1994)

COPYRIGHT THE STATE OF QUEENSLAND (NATURAL RESOURCES, MINES AND ENERGY) [2019]

Requested By: D-ENQ GLOBALX TERRAIN

APPENDIX

MEETING MINUTES



20190116 - Project Initiation:

Wednesday, 16 January 2019

Meeting Details

- Date and Time: 16/01/2019 11:00 AM
- ▶ Location: GRC office, Calliope
- Attendees:

Particinants

- Gerry Moore (Meeting Organizer)
- 2 Jessica Dennien (Accepted in Outlook)
- Anna Scott (Accepted in Outlook)
- Don Dickson (Accepted in Outlook)
- Brent Tangey (Accepted in Outlook)

Agenda

- 1. Meet key project team members;
- 2. Discuss project goals;
- 3. GRC's preferences'; and
- 4. Other details.

Action Items

GM to re-issue signed licence agreement to JD; JD to issue existing hydraulic model data to GM; GM to provide GRC alignment options for review and acceptance; JD to issue Deep Water fire trail route to GM; JD to issue GM GRC's road hierarchy details; JD to confirm AADT with GRC's Planning team:

Important Dates

▶ TBC

Announcements

▶ N/A

Discussion

- Brief discussion around the issues driving the project and public opinion:
- Project to include 4no alignment options shown in project brief plus 1no option through the Deep Water Creek fire trail. Card no to be guided by indicative alignments shown within the project brief and issue to GRC for review;
- Discussion of applicable design guidelines to be applied both interim and ultimate cross sections:
 - o Austroads part 6 for ultimate design; and
 - IPWEA Lower Order Roads Manual ('LORM') for the interim design.
 - Noting the formation width nominated in the project brief would be compliant with the LORM 'formed track' requirements rather than a Austroads rural road. This should be made clear when communicating project outcomes to Councilor's and other stakeholders;
 - Hierarchy details to be provided to confirm road classification and road reserve width requirements;
- Desirable design speed shall be 90kph;
- Posted speed to be 60-80kph;
- Expected usage of road to be low. Unlikely to be more than 150 vehicles per day. GRC's planning team to confirm;
- Soil and flooding conditions of the site are not expected to be great. Possibility of acid sulphate soils in low lying areas. Design options to address this shall be discussed following geotechnical investigations;
- Cardno to consider life-cycle costs for the alignments; and
- Cardno to consider the following pavement types for the interim and ultimate cross section:
 - Interim:
 - Gravel; andLow cost seal.
 - Ultimate:
 - Sealed only. Details to be confirmed.
 - Noted the presence of endangered flora / fauna in the area. Further review and detailed assessment on site to be conducted in following phases of the project i.e. detail design phase;
- $Cardno\ to\ assess\ the\ operational\ speed\ particularly\ the\ long\ straight\ alignment\ shown\ in\ option\ 1;$
- Discussion around the fire track through Deep Water National Park. GM to discuss the possibility / implications of this align ment with Cardno's town planners for a better understanding of issues. Possibly gazettal change with National Parks and GRC?
- GM to confirm whether Cardno have access to additional lidar information and notify JD if not required.

Summary

As above.

Next Meeting

- Date and Time: tbc
- ▶ Location: the
- Agenda: tbc
- Notes: tbc

20190206 - Project Workshop

Wednesday, 6 February 2019 2:00 PM

Meeting Details

- Date and Time: Wednesday 6 February 2019, 2:00pm
- ▶ Location: GRC office, Calliope
- Attendees:
 - ▶ Jessica Dennien (Gladstone Regional Council)
 - ▶ Don Dickson (Gladstone Regional Council)
 - ▶ Brent Tangey (Gladstone Regional Council)
 - Gerry Moore (Cardno)
 - ▶ Stephen Whitaker (Cardno)

Agenda

- 1. Presentation of GRC design options
- 2. Identification and discussion of design matters relating to GRC design options
- 3. Presentation of Cardno alternative design options
- 4. Agreement on path forward for project

Action Items

	Cardno to amend Option 4 to be a 2WD accessible road based on existing alignment
	Cardno to confirm catchment size and applicability of rational method
✓	Council to provide Cardno with protected plant reporting associated with Yabby Road works
	Council and Cardno to agree on criteria for Multi-Criteria Analysis

Important Dates

▶ TBC

Announcements

▶ N/A

Discussion

- Council advised that Option 4 is to be a 2WD accessible road based on existing alignment (rather than a 110km/h design speed as currently shown). Cardno will amend Option 4 to reflect this
- ▶ Council requested that Cardno include discussion in reporting of power pole alignment including potential width issues
- Discussion in relation to the availability of the rational method for use in this instance. Cardno will check the applicable catchment size and confirm approach
- Discussion of culvert sizing agreement between Council and Cardno that culverts should be designed to ultimate width
- Discussion in relation to the potential for speeding, particularly on large straight section of road
 - ▶ Acknowledgement that reserve width prevents substantial variation in geometry
 - ▶ Potential to consider speed control devices, such as associated with culverts
 - Agreement that this would be less of an issue with the initial road construction noting reduced width
 - Cardno will include discussion of speed control in project reporting for further consideration by Council
 - ▶ No dedicated speed control devices will be included in project designs
- Council requested that Cardno ensure that safety and potential liability issues associated with Option 4 be clearly documented in reporting
- Council identified existing knowledge of potential for protected plant species to occur near sewerage treatment plant access on the basis of recent works on Yabby Road
 - ▶ Council will provide Cardno with relevant reporting
 - ▶ Cardno will note potential constraint in project reporting
- Discussion between Council and Cardno as to the presentation of the various options. It was agreed that the assessment of the options should be presented in two stages:
 - ▶ Stage 1 Initial assessment of all options (Council preferred and Cardno alternatives) and selection of three options for further assessment in Stage 2. It was suggested that Options 2, 2A and 4 be taken forward to Stage 2.
 - ▶ Stage 2 Detailed assessment of three options selected in Stage 1
- ▶ Multi Criteria Analysis (MCA)
 - ▶ Cardno suggested it might be suitable for a MCA to form part of the project
 - ▶ Cardno confirmed this can be undertaken as part of existing engagement (no variation)
 - ▶ Council agreed a MCA would be appropriate and useful for Council to take forward the road concept
 - ▶ Council and Cardno are to agree on criteria for the MCA
- Council discussed process moving forward with project.
 - ▶ Discussion with Councillors
 - ▶ Public consultation
 - ▶ Cardno is able to assist with consultation activities moving forward
 - ▶ Cardno noted that there may be some benefit in consultation involvement noting the knowledge Cardno will hold as part of the current work

Summary

Cardno to progress project deliverables in accordance with discussion and key actions and provide to Council for review.

Next Meeting

▶ No further meetings planned

20190306 - Project Workshop

Wednesday, 6 March 2019 12:30 PM

Meeting Details

- Date and Time: Wednesday 6 March 2019, 12:30pm
- ▶ Location: GRC office, Calliope
- Attendees:
 - ▶ Jessica Dennien (Gladstone Regional Council)
 - Anna Scott (Gladstone Regional Council)
 - ▶ Brent Tangey (Gladstone Regional Council)
 - ▶ Gerry Moore (Cardno)
 - ▶ Stephen Whitaker (Cardno)

Agenda

- 1. Presentation of design report, options analysis and design options to Council
- 2. Identification of project direction and next steps

Action Items

Council to provide comments to Cardno on draft report
Council to provide advice in relation to maintenance costs methodology / calculation
Council to provide advice in relation to flood immunity for crossings.
Cardno to update report and issue in final to Council
Council to issue purchase order for variation to scope of work
Cardno to organise survey of Ergon Energy assets on receipt of purchase order

Important Dates

▶ Final Design Report to be provided to Council on 19 March to make Council meeting agenda.

Announcements

▶ N/A

Discussion

- ▶ Cardno presented design report and design options.
- Council requested that further explanation be provided in relation to the use of survey / LIDAR data. Cardno confirmed the report would be amended to clarify the relationship between the two datasets.
- ▶ The survey of the existing Ergon assets was discussed Cardno identified that this can be completed once a purchase order is issued by Council.
- ▶ Cardno outlined findings in relation to drainage assessment:
 - ▶ 20 year ARI used, as per Council instructions.
 - ▶ Large catchment consisting primarily of Deepwater Creek.
 - In order to achieve immunity for crossings, additional works would be required to widen existing waterways (beyond waterway barrier works requirements).
 - One example exists where 19 box culverts may be required.
 - ▶ Allowance has been made in opinion of cost for crossing works, subject to detailed investigations.
 - ▶ Cardno identified that the road as designed is not elevated and may be subject to inundation.
 - ▶ It is recommended that a detailed hydraulic assessment be undertaken in relation the selected design option, using a flood model.
 - ▶ There is the potential for a low level crossing that is inundated to result in sediment being discharged into the Great Barrier Reef (which may result in environmental approval requirements). Possible solution would be to apply a cement stabilised pavement in high risk areas.
- ▶ Cardno explained options analysis process, including Multiple Criteria Analysis (MCA).
- Council asked that further explanation be provided in relation to the scoring used in the MCA.
- Cardno and Council agreed to include an explanatory table that provides commentary on the methodology and reasoning for the scoring in the MCA likely as an appendix to the design report.
- ▶ Council suggested using metrics, where possible, to inform the MCA.
- Council identified that Councillor input is currently being sought to inform the final design report.
- Council requested that cost breakdowns be provided for each design option Cardno identified these have already been prepared and will be included as part of Appendix B of the final design report.
- Council reviewed the opinion of cost summary an error was identified in the formula applied for Option 4 Cardno will correct this error.
- Cardno confirmed that the MCA is based on a spreadsheet that can be amended to alter the methodology for select criteria, as required. A final version of this spreadsheet can be provided as part of the final design report.
- Council and Cardno discussed operating costs Council to provide advice to Cardno in relation to methodology for costing of maintenance.
- Council requested that additional criteria be included in the MCA covering:
 - ▶ Travel time
 - Maintenance cost; and
 - Flooding.
- ▶ Council confirmed that it was beneficial for the design report to provide a recommended design option.
- Cardno and Council discussed a 3D model.
- Cardno confirmed that it currently has a 3D model and this can be provided in a format suitable for viewing by Councillors / Council staff.
- Council expressed interest in a 3D model, even if this required a variation to the scope of work.

• Cardno identified that a purchase order is yet to be issued by Council for the variation provided by Cardno - Council will follow up and issue the purchase order as soon as possible.

Summary

• Council to review draft report and provide complete comments to Cardno for incorporation into final design report.

Next Meeting

▶ No further meetings planned

APPENDIX

F

MCA EXPLANATORY TABLE



Criteria	Weighting	Methodology Explanation			Design Options ¹		
			2	2A	3A	4	5
Opinion of Cost (Construction) – Interim	10%	The score applied to each design option is directly linked to the opinion of cost provided in Appendix B . The following scoring ranges have been used. These are based on the limits of the data set: 1: \$22,000,000 - \$23,000,000 2: \$21,000,000 - \$22,000,000 3: \$20,000,000 - \$21,000,000 4: \$19,000,000 - \$20,000,000 5: \$18,000,000 - \$19,000,000 6: \$17,000,000 - \$18,000,000 7: \$16,000,000 - \$17,000,000 8: \$15,000,000 - \$15,000,000 9: \$14,000,000 - \$15,000,000	2 (\$21,835,620.67)	6 (\$17,445,703.97)	6 (\$17,235,171.65)	10 (\$13,143,343.81)	2 (\$21,837,919.96)
Opinion of Cost (Construction) – Ultimate	10%	The score applied to each design option is directly linked to the opinion of cost provided in Appendix B . The following scoring ranges have been used. These are based on the limits of the data set: 1: \$47,000,000 - \$50,000,000 2: \$44,000,000 - \$47,000,000 3: \$41,000,000 - \$44,000,000 4: \$38,000,000 - \$41,000,000 5: \$35,000,000 - \$38,000,000 6: \$32,000,000 - \$35,000,000 7: \$29,000,000 - \$29,000,000 9: \$23,000,000 - \$29,000,000 10: \$20,000,000 - \$23,000,000	9 (\$24,210,307.45)	9 (\$24,890,998.66)	9 (\$24,688,438.40)	2 (\$45,702,074.56)	7 (\$30,708,662.10)

Criteria	Weighting	Methodology Explanation			Design Options ¹		
			2	2A	3A	4	5
Opinion of Cost (Maintenance) – Interim	2.5%	The score applied to each design option is directly linked to the opinion of cost provided in Appendix B . The following scoring ranges have been used. These are based on the limits of the data set: 1: \$100,000 - \$240,000 2: \$240,000 - \$380,000 3: \$380,000 - \$520,000 4: \$520,000 - \$660,000 5: \$660,000 - \$800,000 6: \$800,000 - \$940,000 7: \$940,000 - \$1,080,000 8: \$1,080,000 - \$1,220,000 9: \$1,220,000 - \$1,360,000 10: \$1,360,000 - \$1,500,000	9 (\$336,472.84)	9 (\$267,272.18)	9 (\$263,953.44)	9 (\$199,451.73)	10 (\$336,509.08)
Opinion of Cost (Maintenance) – Ultimate	2.5%	The score applied to each design option is directly linked to the opinion of cost provided in Appendix B . The following scoring ranges have been used. These are based on the limits of the data set: 1: \$100,000 - \$240,000 2: \$240,000 - \$380,000 3: \$380,000 - \$520,000 4: \$520,000 - \$660,000 5: \$660,000 - \$800,000 6: \$800,000 - \$940,000 7: \$940,000 - \$1,080,000 8: \$1,080,000 - \$1,220,000 9: \$1,220,000 - \$1,360,000 10: \$1,360,000 - \$1,500,000	6 (\$747,812.65)	6 (\$769,272.86)	6 (\$762,886.73)	1 (\$1,425,385.60)	4 (\$952,686.88)

Criteria	Weighting	Methodology Explanation		Design Options ¹				
			2	2A	3A	4	5	
Ownership	10%	A quantitative measurement is not available in relation to land ownership noting the complexity of multiple land holdings, road reserves and varying tenures and therefore a qualitative assessment has been used to inform the scoring for this criterion. The following guidance is provided in relation to the scores given for each design option: 2: This option is partly within road reserves, Council owned freehold land and Council controlled reserve land. The land is wholly controlled by Council in varying forms, although some work would be required to create road reserves. 2A: This option is partly within road reserves, Council owned freehold land and Council controlled reserve land. The land is wholly controlled by Council in varying forms, although some work would be required to create road reserves. 3A: This option partly traverses Deepwater National Park, which is not owned or controlled by Council. The score allocated acknowledges the potential difficulty in securing a road reserve through a National Park. The balance of the option is within Council controlled land (in varying forms). 4: This option is almost wholly within Deepwater National Park, which is not owned or controlled by Council. The score allocated acknowledges the potential difficulty in securing a road reserve through a National Park. 5: This option is wholly within road reserves, with the exception of a small area of Council controlled reserve land. This ownership situation is therefore highly suited to a road.	8	8	3	0	9	

Criteria	Weighting	Methodology Explanation			Design Options ¹		
			2	2A	3A	4	5
Environment - Regulated Vegetation	2%	The score applied to each design option is based on the land area of regulated vegetation impacted by the design option, as documented in Table 5-1. Multipliers of 2 and 3 have been applied to "of concern" and "endangered" vegetation respectively, noting their greater environmental; significance. The following scoring ranges applied: 1: 0-30 hectares impacted 2: 30-60 hectares impacted 3: 60-90 hectares impacted 4: 90-120 hectares impacted 5: 120-150 hectares impacted 6: 150-180 hectares impacted 7: 180-210 hectares impacted 8: 210-240 hectares impacted 9: 240-270 hectares impacted 10: 270-300 hectares impacted	7 (106.04)	7 (109.23)	7 (114.77)	7 (94.27)	1 (286.1)
Environment - Protected Areas	3%	A quantitative measure is unable to be used for protected areas noting the need for the criterion to cover location within and proximity to, protected areas. A qualitative assessment has therefore been used to inform the scoring for this criterion. The following guidance is provided in relation to the scores given for each design option: 1 2: This option partly adjoins a National Park. 2A: This option partly adjoins a National Park. 3A: This option is partly located in a National Park and also partly adjoins a National Park. 4: This option is almost wholly within a National Park. 5: This option is not proximate to any protected areas.	8	8	3	0	10

Criteria	Weighting	Methodology Explanation			Design Options ¹		
			2	2A	3A	4	5
Environment - Waterways	3%	This score has been applied based on the number of mapped waterways crossed by each design option. The following methodology has been employed:					
		1 point for each green waterway crossed	2	2	2	7	3
		2 points for each amber waterway crossed	(8)	(8)	(8)	(3)	(7)
		3 points for each red waterway crossed					
		The above points for each design option have been deducted from a score of 10 to give a score for the criterion.					
Environment - Wetlands	2%	The scoring of the design options has been informed by the assessment undertaken as part of the Environmental Assessment documented in Section 5.3. The following guidance is provided in relation to the scores given for each design option: 2: This option traverses notable areas of wetland.					
		 2A: This option traverses notable areas of wetland. 	3	3	3	6	8
		3A: This option traverses notable areas of wetland.					
		 4: This option traverses small areas of wetland and is also proximate to a number of other areas. 					
		 5: This option traverses small areas of wetland. 					

Criteria	Weighting	Methodology Explanation		Design Options ¹					
			2	2A	3A	4	5		
Environment - Other	2%	This criteria is intended to cover any environmental matters considered in the Environmental Assessment documented in Section 5.3 of the design report and not otherwise assessed as part of a dedicated criterion. On this basis it is difficult to establish a quantitative measure and therefore a qualitative assessment has been used to inform the scoring for this criterion. The following guidance is provided in relation to the scores given for each design option: 2: This option includes areas, in the north, that will require a protected plants flora survey. The option is also proximate to an ERA. 2A: This option includes areas, in the north, that will require a protected plants flora survey. The option is also proximate to an ERA. 3A: This option includes areas, in the north, that will require a protected plants flora survey. The option is also proximate to an ERA. 4: This option includes some areas where a protected plants flora survey will be required. 5: This option is located in small areas where a protected plants flora survey is required. The option is also proximate to an ERA.	5	5	5	6	7		

Criteria	Weighting	Methodology Explanation			Design Options ¹		
			2	2A	3A	4	5
Connection (North)	3%	A quantitative measurement is not available in relation to connectivity noting the varying nature of existing road environments and therefore a qualitative assessment has been used to inform the scoring for this criterion. The following guidance is provided in relation to the scores given for each design option: 2: This option connects to Jobson Road, which presently supports local access to residential properties. The connection point is not considered desirable given the existing function of the road and its resultant construction standard. 2A: This option connects to Anderson Way, which performs a collector function in the local area and is suitable to provide a connection to the new road. 3A: This option connects to Rocky Crossing Road, part of which is presently of a lower order gravel construction. 4: This option connects to Springs Road, which is of a suitable existing standard and is well located to service the proposed new road. 5: This option connects to Uxbridge Road at its intersection with Round Hill Road. The connection point is suitable although it is noted it is located to the west of Agnes Water and may require additional works to facilitate.	4	7	3	8	5

Criteria	Weighting	Methodology Explanation			Design Options ¹		
			2	2A	3A	4	5
Connection (South)	3%	A quantitative measurement is not available in relation to connectivity noting the varying nature of existing road environments and therefore a qualitative assessment has been used to inform the scoring for this criterion. The following guidance is provided in relation to the scores given for each design option: Maude Hill Road (2, 2A, 3A and 5): Maude Hill Road is well located to connect with the new road, although it is noted that the road is presently of gravel construction and does not provide direct connection to Baffle Creek. Wreck Rock Road (4): Wreck Rock Road provides a gravel access track which may not be suited to connection with the ultimate road, although does provide a more direct route to Baffle Creek.	7	7	7	5	7
Serviceability	5%	 A binary scoring system has been used for this criterion noting its simplicity: 10: The design option meets Council's objective for the project. 0: The design option does not meet Council's objective for the project. 	10	10	10	10	10

Criteria	Weighting	Methodology Explanation			Design Options ¹		
			2	2A	3A	4	5
Travel Time (Interim)	5%	The score applied to each design option is based on the estimated travel time using the design option between Agnes Water and Baffle Creek. The following assumptions have been applied for this assessment: "Agnes Water" is defined as the intersection of Round Hill Road, Springs Road and Captain Cook Drive. "Baffle Creek" is defined as the intersection of Coast Road and Fernfield Road. Travel time on the existing road network is based on data obtained from Google Maps without traffic or any potential external road upgrades. Travel time on the design options is based on an average speed of 70km/h for Design Options 2, 2A and 3A, 40km/h for Design Option 4 and 50km/h for Design Option 5. The following scoring ranges have been used. These are based on the limits of the data set: 1: 55-57 minutes 2: 53-55 minutes 4: 49-51 minutes 5: 47-49 minutes 6: 45-47 minutes 7: 43-45 minutes 8: 41-43 minutes 9: 39-41 minutes 10: 37-39 minutes	6 (45 minutes)	6 (45 minutes)	6 (45 minutes)	6 (46 minutes)	2 (54 minutes)

Criteria	Weighting	Methodology Explanation			Design Options ¹		
			2	2A	3A	4	5
Travel Time (Ultimate)	5%	The score applied to each design option is based on the estimated travel time using the design option between Agnes Water and Baffle Creek. The following assumptions have been applied for this assessment: "Agnes Water" is defined as the intersection of Round Hill Road, Springs Road and Captain Cook Drive. "Baffle Creek" is defined as the intersection of Coast Road and Fernfield Road. Travel time on the existing road network is based on data obtained from Google Maps without traffic or any potential external road upgrades. Travel time on the design options is based on an average speed of 70km/h for Design Options 2, 2A, 3A and 4 and 60km/h for Design Option 5. The following scoring ranges have been used. These are based on the limits of the data set: 1: 55-57 minutes 2: 53-55 minutes 3: 51-53 minutes 4: 49-51 minutes 5: 47-49 minutes 6: 45-47 minutes 7: 43-45 minutes 8: 41-43 minutes 9: 39-41 minutes	6 (45 minutes)	6 (45 minutes)	6 (45 minutes)	9 (39 minutes)	4 (50 minutes)

Criteria	Weighting	Methodology Explanation			Design Options ¹		
			2	2A	3A	4	5
Potential Flood Impact	5%	The flood mapping used by the Department of State Development, Manufacturing, Infrastructure and Planning (Flood Hazard Area – Level 1 – Queensland Floodplain Assessment Overlay) has been used to inform the assessment of the design options for this criterion. A detailed hydraulic assessment will need to be undertaken in relation to the project in order to confirm the potential flood impacts. The following guidance is provided in relation to the scoring of each of the design options: 1. 2: This option is located within a number of areas that are subject to flooding. 2A: This option is located within a number of areas that are subject to flooding. 3A: This option is located within a number of areas that are subject to flooding. 4: This option is largely outside floodable areas. 5: This option is largely outside floodable areas.	4	4	4	8	8

Criteria	Weighting	eighting Methodology Explanation	Design Options ¹					
			2	2A	3A	4	5	
Additional Works	4%	The requirement for additional works is based on a variety of factors and is therefore unable to be quantified as part of this assessment. A qualitative assessment has been undertaken and the following guidance is provided in relation to the scoring of each of the design options: 2: This option will likely require the upgrading of Jobson Road to accommodate future traffic volumes in a safe manner. This option also may necessitate the sealing / upgrading of Maude Hill Road and Matchbox Road for the ultimate design. 2A: This option may necessitate the sealing / upgrading of Maude Hill Road and Matchbox Road for the ultimate design. This option also may necessitate the sealing / upgrading of Maude Hill Road and Matchbox Road for the ultimate design. 3A: This option will likely require the upgrading of Rocky Crossing Road. This option also may necessitate the sealing / upgrading of Maude Hill Road and Matchbox Road for the ultimate design. 4: This option will require the upgrading of Wreck Rock Road and Deepwater Road and potentially also the Deepwater Causeway. 5: It is anticipated that this option will require the upgrading of the intersection of Uxbridge Road, Round Hill Road and Eurimbula Road. This option also may necessitate the sealing / upgrading of Maude Hill Road and Eurimbula Road. This option also may necessitate the sealing / upgrading of Maude Hill Road and Eurimbula Road and Matchbox Road for the ultimate design.	5	7	4	3	2	

Criteria	Weighting	Methodology Explanation	Design Options ¹					
			2	2A	3A	4	5	
Social	8%	Social impacts associated with each of the design options are unable to be quantified and therefore a qualitative assessment has been undertaken to inform the scoring of each of the design options. 2: This option's connection to Jobson Road may reduce the amenity of local residents, noting its current function as a local access. Some amenity impacts may also occur on Maude Hill Road in the south of the option. 2A: This option's connection to Anderson Way will introduce additional traffic to the local area with potential amenity impacts, although it is acknowledged that Anderson Way currently provides a collector function. Some amenity impacts may also occur on Maude Hill Road in the south of the option. 3A: This option's connection to Rocky Crossing Road may cause amenity impacts to local residents. Some amenity impacts may also occur on Maude Hill Road in the south of the option. 4: This option has the potential, particularly as part of the interim design, to result in the loss of existing recreational opportunities associated with the existing 4WD trail through Deepwater National Park. 5: Some amenity impacts may occur on Maude Hill Road in the south of the option.	5	7	7	3	8	

Criteria	Weighting	Weighting Methodology Explanation Design Options ¹					
			2	2A	3A	4	5
Safety	12%	Scoring for the safety criterion is based on the compliance of the design options with Council's desired standard for the road (refer to Table 3-1 of the design report). The following guidance is provided in relation to the scoring of the design options: 2: In order to connect to Jobson Road, a section of road which does not meet the desired standard is required. The connection to Maude Hill Road also includes a curve radius which is less than the desired standard (although is compliant with other common standards for this type of road). 2A: The connection to Maude Hill Road includes a curve radius which is less than the desired standard (although is compliant with other common standards for this type of road). 3A: The connection to Maude Hill Road includes a curve radius which is less than the desired standard (although is compliant with other common standards for this type of road). 4: The interim design for this option is wholly non-compliant with relevant standards and has the potential to create significant safety issues. 5: The constraints of the road reserve associated with this option mean it includes several areas of non-compliance with the desired standard	6	8	8	3	4

Criteria	Weighting	Methodology Explanation	Design Options ¹					
			2	2A	3A	4	5	
Existing Utilities Interface	3%	Scoring is based on the proximity of the design options to existing utilities infrastructure such as Ergon Energy assets and Council's sewerage treatment plant. The following guidance is provided in relation to the scoring of the design options:						
		2: This option runs parallel to existing Ergon Energy assets in the south. The interface with these assets is subject to further investigations. This option also increases the proximity of public vehicles to Council's sewerage treatment plant.						
		 2A: This option runs parallel to existing Ergon Energy assets in the south. The interface with these assets is subject to further investigations. 	4	6	6	9	8	
		 3A: This option runs parallel to existing Ergon Energy assets in the south. The interface with these assets is subject to further investigations. 						
		4: There is limited interface between this option and existing utilities.						
		 5: This option is proximate to Ergon Energy assets near the southern connection point. The interface with these assets is subject to further investigations. 						

Notes:

1. Numbers in brackets are the quantitative data used to inform the scoring of each design option, where available. Some criteria are unable to be linked to a quantitative measure and this is explained in the methodology for these criteria.